

RTE	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
**	*	PIATT	62	12
STA.	TO STA.			
FED. ROAD DIST. NO.		ILLINOIS	FED. AID PROJECT	
* 08-00255-00-BR				
** FAS 535				

LOCATION	BIT. MAT. (PRIME COAT) (40800010)	INC. HMA SURFACE (40800050)	AGG SURF CSE TY B (40200800)	SUB-BSE GRAN MTL TY A 4" (31100300)
	GALLON	TON	TON	SQ YD
PE STA. 31+59 RT	40	33		104
PE STA. 31+88 RT			28	
PE STA. 35+01 RT			50	
PE STA. 37+66 RT			68	
PE STA. 45+65 LT			64	
MBTO STA. 46+19 RT			10	
TOTALS	40	33	220	104

LOCATION	EACH
STA. 28+50 RT	1
STA. 31+29 RT	1
STA. 34+68.5 RT	1
STA. 37+28.5 RT	1
TOTAL	4

LOCATION	FOOT
STA. 35+00 TO 37+00 RT	210
SOUTH FLOODPLAIN	510
NORTH FLOODPLAIN	1070
STA. 46+00 TO 48+50 LT	250
STA. 49+10 TO 53+20	410
TOTAL	2450

LOCATION	SQ YD
NW CORNER	525
NE CORNER	565
SE CORNER	375
SW CORNER	380
PE STA. 31+74 RT	20
PE STA. 35+01 RT	19
PE STA. 37+66 RT	19
TOTAL	1903

LOCATION	FOOT
STA. 30+50 RT	12
STA. 32+50 RT	12
STA. 33+50 RT	12
STA. 34+00 LT	12
STA. 35+50 LT	12
STA. 37+00 LT	12
TOTAL	72

ESCA
CONSULTANTS, INC.

DESIGNED BY:	ELH	01/10
DRAWN BY:	HAS	01/10
CHECKED BY:	ELH	05/10
APPROVED BY:	RDP	05/10

SCHEDULES OF QUANTITIES
FAS 535 (SHADY REST ROAD)
SECTION 08-00255-00-BR
PIATT COUNTY