


SUMMARY OF QUANTITIES

CODE NO.	ITEM	UNIT	TOTAL
20100110	TREE REMOVAL (6 TO 15 UNITS DIAMETER)	UNIT	170
20100210	TREE REMOVAL (OVER 15 UNITS DIAMETER)	UNIT	192
20200100	EARTH EXCAVATION	CU YD	7295
20800150	TRENCH BACKFILL	CU YD	137
21101615	TOPSOIL FURNISH AND PLACE 4"	SQ YD	3883
25000210	SEEDING, CLASS 2A	ACRE	0.8
25000400	NITROGEN FERTILIZER NUTRIENT	POUND	72
25000500	PHOSPHORUS FERTILIZER NUTRIENT	POUND	72
25000600	POTASSIUM FERTILIZER NUTRIENT	POUND	72
25000700	AGRICULTURAL GROUND LIMESTONE	TON	1.6
25100115	MULCH, METHOD 2	ACRE	0.8
25100630	EROSION CONTROL BLANKET	SQ YD	244
28000250	TEMPORARY EROSION CONTROL SEEDING	POUND	813
28000400	PERIMETER EROSION BARRIER	FOOT	3525
28000500	INLET AND PIPE PROTECTION	EACH	1
28000510	INLET FILTERS	EACH	30
28100107	STONE RIPRAP, CLASS A4	SQ YD	16
28200200	FILTER FABRIC	SQ YD	16
30200650	PROCESSING MODIFIED SOIL 12"	SQ YD	12482
30201500	LIME	TON	250
31100910	SUB-BASE GRANULAR MATERIAL, TYPE A 12"	SQ YD	1817
40701851	HOT-MIX ASPHALT PAVEMENT (FULL-DEPTH), 8 1/2"	SQ YD	11107
40701881	HOT-MIX ASPHALT PAVEMENT (FULL-DEPTH), 10"	SQ YD	1721
40800050	INCIDENTAL HOT-MIX ASPHALT SURFACING	TON	84
42300200	PORTLAND CEMENT CONCRETE DRIVEWAY PAVEMENT, 6 INCH	SQ YD	251
42400100	PORTLAND CEMENT CONCRETE SIDEWALK 4 INCH	SQ FT	21708
42400200	PORTLAND CEMENT CONCRETE SIDEWALK 5 INCH	SQ FT	144
42400800	DETECTABLE WARNINGS	SQ FT	236
44000100	PAVEMENT REMOVAL	SQ YD	2338
44000200	DRIVEWAY PAVEMENT REMOVAL	SQ YD	405
44000500	COMBINATION CURB AND GUTTER REMOVAL	FOOT	333
44000600	SIDEWALK REMOVAL	SQ FT	790
54213663	PRECAST REINFORCED CONCRETE FLARED END SECTIONS 18"	EACH	1
550A0050	STORM SEWERS, CLASS A, TYPE 1, 12" (RCCP)	FOOT	701
550A0070	STORM SEWERS, CLASS A, TYPE 1, 15" (RCCP)	FOOT	98
550A0090	STORM SEWERS, CLASS A, TYPE 1, 18" (RCCP)	FOOT	186
550A0340	STORM SEWERS, CLASS A, TYPE 2, 12" (RCCP)	FOOT	158
550A0380	STORM SEWERS, CLASS A, TYPE 2, 18" (RCCP)	FOOT	688
55100500	STORM SEWER REMOVAL 12"	FOOT	4
SP 60224600	RESTRICTED DEPTH MANHOLES, 4'-DIAMETER, TYPE 1 FRAME, CLOSED LID	EACH	7
SP 60224700	RESTRICTED DEPTH MANHOLES, 4'-DIAMETER, TYPE 3 FRAME AND GRATE	EACH	2
SP 60226200	RESTRICTED DEPTH MANHOLES, 6'-DIAMETER, TYPE 1 FRAME, CLOSED LID	EACH	2
60235700	INLETS, TYPE A, TYPE 3 FRAME AND GRATE	EACH	16
60240220	INLETS, TYPE B, TYPE 3 FRAME AND GRATE	EACH	12

SUMMARY OF QUANTITIES

CODE NO.	ITEM	UNIT	TOTAL
60255800	MANHOLES TO BE ADJUSTED WITH NEW TYPE 1 FRAME, CLOSED LID	EACH	1
60500060	REMOVING INLETS	EACH	1
60500090	REMOVING INLETS TO MAINTAIN FLOW	EACH	2
60600605	CONCRETE CURB, TYPE B	FOOT	25
60603800	COMBINATION CONCRETE CURB AND GUTTER, TYPE B-6.12	FOOT	116
60604400	COMBINATION CONCRETE CURB AND GUTTER, TYPE B-6.18	FOOT	4431
60618300	CONCRETE MEDIAN SURFACE, 4 INCH	SQ FT	54
67100100	MOBILIZATION	L SUM	1
SP 70103700	TRAFFIC CONTROL COMPLETE	L SUM	1
70300100	SHORT-TERM PAVEMENT MARKING	FOOT	800
70300210	TEMPORARY PAVEMENT MARKING - LETTERS AND SYMBOLS	SQ FT	31
70300230	TEMPORARY PAVEMENT MARKING - LINE 5"	FOOT	7377
70300240	TEMPORARY PAVEMENT MARKING - LINE 6"	FOOT	529
70300280	TEMPORARY PAVEMENT MARKING - LINE 12"	FOOT	532
70300280	TEMPORARY PAVEMENT MARKING - LINE 24"	FOOT	42
70301000	WORK ZONE PAVEMENT MARKING REMOVAL	SQ FT	4252
72000100	SIGN PANEL - TYPE 1	SQ FT	56
72900110	METAL POST - TYPE A	EACH	6
SI 78000300	THERMOPLASTIC PAVEMENT MARKING - LINE 5"	FOOT	16898
SI 78000400	THERMOPLASTIC PAVEMENT MARKING - LINE 6"	FOOT	1293
SI 78000600	THERMOPLASTIC PAVEMENT MARKING - LINE 12"	FOOT	1103
SI 78000650	THERMOPLASTIC PAVEMENT MARKING - LINE 24"	FOOT	143
SI 78004200	PREFORMED PLASTIC PAVEMENT MARKING, TYPE B-INLAID-LETTERS AND SYMBOLS	SQ FT	700
78300100	PAVEMENT MARKING REMOVAL	SQ FT	475
SP X0321556	SANITARY MANHOLES TO BE ADJUSTED	EACH	2
SP X0322033	STORM SEWER (WATER MAIN REQUIREMENTS) 12 INCH	FOOT	47
SP X0322671	STABILIZED CONSTRUCTION ENTRANCE	SQ YD	470
SP XX005661	REMOVE AND RELOCATE SIGN NO. 1	EACH	1
SP XX005662	REMOVE AND RELOCATE SIGN NO. 2	EACH	1
SP Z0013798	CONSTRUCTION LAYOUT	L SUM	1
SP Z0042300	PORTLAND CEMENT CONCRETE SIDEWALK CURB	FOOT	484
SP Z0075300	TIE BARS	EACH	12

SP SEE SPECIAL PROVISIONS
SI SPECIALTY ITEMS

SHEET TITLE		SUMMARY OF QUANTITIES	
PROJECT	FAU RTE. 8046 (MEADOWBROOK ROAD)	PROJECT NO.	09040
SCALE	SECTION 09-00465-00-PV	DATE	4/19/10
DRAWN BY	CITY OF SPRINGFIELD	CHECKED BY	CFC
	SANGAMON COUNTY	DRAWING NO.	3
 Coombe-Bloxdorf P.C. -CIVIL ENGINEERS- -STRUCTURAL ENGINEERS- -LAND SURVEYORS- Phone: 217/544-8477 Design Firm License No. 184-002703 755 South Grand Ave. W. Springfield, IL 62704		OF 30 SHTS	93539