

**PAVEMENT MARKING SCHEDULE**

LOCATION	DESCRIPTION	PPPM - TY B	TPM -	TPM -	TPM -	TPM -	TPM -	TPM -	TPM -
		INLAID L & S	LINE 5'	LINE 5'	DOUBLE LINE 5' YELLOW	LINE 6' WHITE	LINE 24' WHITE	LINE 12' WHITE	LINE 12' YELLOW
		SQ FT	FOOT	FOOT	FOOT	FOOT	FOOT	FOOT	FOOT
<b>MEADOWBROOK ROAD</b>									
STA 2+54 TO STA 9+56, 13.5' LT	LEFT EDGE PVMT		702						
STA 2+54 TO STA 9+52, 13.5' RT	RIGHT EDGE PVMT		698						
STA 2+54 TO STA 7+95, 4.5' LT	CENTERLINE				1082				
STA 7+95 TO STA 8+47.5, 4.5' LT	CENTERLINE TAPERS				210				
STA 7+95 TO STA 9+52	DIAGONALS								13
STA 8+47.5 TO STA 9+52, 3.0' & 6.0' LT	CENTERLINE				428				
STA 9+52	STOP BAR							24	
STA 10+59 TO STA 25+26, 18.0' LT	LEFT EDGE PVMT		1467						
STA 10+59 TO STA 32+84, VARIES 9.0' RT TO 18.0' RT	RIGHT EDGE OF PAVEMENT		2225						
STA 10+59 TO STA 13+72, VARIES 13.0' RT TO 22.0' RT	EDGE BIKE LANE		313						
STA 10+59 TO STA 13+72, VARIES 13.0' RT TO 22.0' RT	DIAGONALS RIGHT OF BIKE LANE								117
STA 10+63.5 TO STA 13+72, 6.0' LT & VARIES 3.0' LT TO 6.0	CENTERLINE				1244				
STA 10+63.5 LT	STOP BAR							18	
STA 10+63.5 TO STA 13+72	DIAGONALS ALONG CENTERLINE								80
STA 13+72 TO STA 18+00, 6.0' LT	EDGE LINE			428					
STA 13+72 TO STA 18+00, 6.0' LT	SKIP-DASH			100					
STA 13+72 TO STA 18+00, 6.0' RT	EDGE LINE			428					
STA 13+72 TO STA 18+00, 6.0' RT	SKIP-DASH			100					
STA 18+00 TO STA 22+67.3, 6.0' RT	EDGE LINE			935					
STA 18+00 TO STA 25+26.3, 6.0' LT	EDGE LINE			1453					
STA 22+67.3 TO STA 25+26.3, 6.0' RT TO 6.0' LT	TAPER			288					
STA 24+11.32 TO STA 25+26.32, 6.0' RT	LANE LINE				115				
STA 18+00 TO STA 25+26	DIAGONALS ALONG CENTERLINE								295
STA 25+91.3 TO STA 32+83.74, 6.0' LT	LANE LINE				1392				
STA 25+91.3 TO STA 30+24.78, 6.0' RT	LANE LINE				874				
STA 30+24.78 TO STA 31+68.78, 6.0' RT TO 6.0' LT	TAPER				288				
STA 31+68.78 TO STA 32+83.78, 6.0' RT	LANE LINE					115			
STA 25+91 TO STA 31+69	DIAGONALS ALONG CENTERLINE								276
STA 25+97.32 TO STA 32+88.06, 18.0' LT	LEFT EDGE PVMT/BIKE LANE		691						
STA 32+84.06	STOP BAR							28	
STA 32+88.06	CROSS WALK					46			
STA 32+94.06	CROSS WALK					51			
STA 33+61.94	CROSS WALK					37			
STA 33+67.94	CROSS WALK					34			
STA 33+71.94	STOP BAR							21	
STA 33+71.94 TO STA 34+86.94, 5.0' LT	LANE LINE					115			
STA 33+71.94 TO STA 35+76.94, 5.0' RT TO 0.0' RT	CENTERLINE				410				
STA 34+86.94 TO STA 35+76.94	SKIP-DASH					24			
STA 14+84.00, STA 14+96.00, STA 16+78.00, STA 17+10.00, STA 24+211.32, STA 24+96.32, STA 31+68.78, STA 31+83.78, STA 34+00.77, STA 34+75.77	LEFT TURN ARROWS		156						
STA 2+65 TO STA 9+25 APPROX 220' SPACE	BIKE SYMBOLS BOTH SIDES		136						
STA 10+95 TO STA 15+60, SPACE AS SHOWN	BIKE SYMBOLS BOTH SIDES		136						
STA 16+75 TO STA 25+15, APPROX 215' SPACES	BIKE SYMBOLS BOTH SIDES		136						
STA 26+04 TO STA 32+75, APPROX 220' SPACES	BIKE SYMBOLS BOTH SIDES		136						
<b>ILES AVENUE</b>									
STA 459+12.62	CROSS WALK					66			
STA 459+18.62	CROSS WALK					74			
STA 460+23.62	CROSS WALK					65			
STA 460+29.62	CROSS WALK					56			
STA 459+00 TO STA 459+13	RIGHT EDGE LINE		13						
STA 459+00 TO STA 459+46.62	LEFT EDGE LINE		64						
STA 459+81.62 TO STA 460+49.49	LEFT EDGE LINE		85						
STA 460+29.62 TO STA 460+49.49	RIGHT EDGE LINE		20						
STA 460+29.62 TO STA 460+49.49	BIKE LANE		20						
STA 459+00 TO STA 459+46.62	DIAGONALS								49
STA 459+00 TO STA 459+46.62	DIAGONALS								112
STA 459+81.62 TO STA 460+49.49	DIAGONAL								15
STA 460+29.62 TO STA 459+49.49	DIAGONAL					64			
STA 9+55.88	CROSS WALK					67			
STA 9+61.88	CROSS WALK					70			
STA 10+53.5	CROSS WALK					67			
STA 10+59.5	CROSS WALK								
STA 460+49.49 TO STA 462+09.49	NORTH EDGE LINE		160						
STA 461+14.49 TO STA 462+09.49	CENTERLINE				380				
STA 460+49.49 TO STA 462+09.49	DIAGONALS								137
STA 461+14.49 TO STA 462+09.49	DIAGONALS								9
<b>McGREGOR</b>									
STA 25+61.96, 33.5' LEFT	CROSS WALK					33			
STA 25+61.48, 38.5' LEFT	CROSS WALK					28			
STA 25+61.98, 44' LEFT	STOP BAR							14	
<b>GREENBRIAR ROAD</b>									
STA 9+05.84 TO STA 9+55.84	RIGHT EDGE LINE		50						
STA 9+05.84 TO STA 9+55.84	CENTERLINE				100				
STA 9+05.84 TO STA 9+55.84	LEFT EDGE LINE		50						
STA 9+55.84	STOP BAR							19	
STA 9+60.5	CROSS WALK					40			
STA 9+66.5	CROSS WALK					45			
STA 10+33.5	CROSS WALK					43			
STA 10+36.5	CROSS WALK					38			
STA 10.43.77	STOP BAR							19	
STA 10+43.77 TO STA 10+83.77	RT/ LT EDGE LINES		100						
STA 10+43.77 TO STA 10+83.77	CENTERLINE				100				
<b>TOTALS</b>		<b>700</b>		<b>16,898</b>		<b>1293</b>	<b>143</b>		<b>1103</b>

**PAVING SCHEDULE**

LOCATION	CCC & G TY B-6.18	HMA PAVEMENT (FULL-DEPTH) 10'	SUB-BASE GRAN MATL TY A 12"	HMA PAVEMENT (FULL-DEPTH) 8 1/2"	PROCESSING LIME MODIFIED SOIL 12"	LIME
STA 9+23.64 TO STA 10+81.14	318	1708	1817	-	-	-
STA 10+81.14 TO STA 13+00.00	220	-	-	1095	1170	23.4
STA 13+00.00 TO STA 18+00.00	781*	-	-	2444	2709	54.2
STA 18+00.00 TO STA 23+00.00	1000	-	-	2444	2787	55.7
STA 23+00.00 TO STA 28+00.00	1012	-	-	2555	2901	58.0
STA 28+00.00 TO STA 33+94.97	1100	-	-	2569	2915	58.3
<b>TOTAL</b>	<b>4431</b>	<b>1708</b>	<b>1817</b>	<b>11107</b>	<b>12482</b>	<b>250</b>

\* INCLUDES QUANTITY FROM ENTRANCE SCHEDULE  
 \*\* INCLUDES NORTH SIDE OF GREENBRIAR ROAD

**TEMPORARY PAVEMENT MARKING SCHEDULE**

LOCATION	TPM L & S	TPM - LINE 5' WHITE	TPM - LINE 5' YELLOW	TPM - DOUBLE LINE 5' YELLOW	TPM - LINE 6' WHITE	TPM - LINE 24' WHITE	TPM - LINE 12' WHITE	TPM - LINE 12' YELLOW
<b>MEADOWBROOK ROAD</b>								
STA 2+54 TO STA 9+56, 13.5' LT		702						
STA 2+54 TO STA 9+52, 13.5' RT		698						
STA 2+54 TO STA 7+95, 4.5' LT				1082				
STA 7+95 TO STA 8+47.5, 4.5' LT				210				
STA 7+95 TO STA 9+52								13
STA 8+47.5 TO STA 9+52, 3.0' & 6.0' LT				428				
STA 9+52							24	
STA 10+59 TO STA 16+70, 18.0' LT		611						
STA 10+59 TO STA 16+70		611						
STA 10+59 TO STA 13+72, VARIES 13.0' RT TO 22.0' RT		313						
STA 10+59 TO STA 13+72, VARIES 13.0' RT TO 22.0' RT								117
STA 10+63.5 TO STA 13+72, 6.0' LT & VARIES 3.0' LT TO 6.0				1244				
STA 10+63.5 LT							18	
STA 10+63.5 TO STA 13+72								80
STA 13+72 TO STA 16+70, 6.0' LT				298				
STA 13+72 TO STA 16+70, 6.0' LT				70				
STA 13+72 TO STA 16+70, 6.0' RT				298				
STA 13+72 TO STA 16+70, 6.0' RT				70				
STA 14+84.00, STA 14+96.00,		31.2						
<b>ILES AVENUE</b>								
STA 459+12.62					66			
STA 459+18.62					74			
STA 460+23.62					65			
STA 460+29.62					56			
STA 459+00 TO STA 459+13		13						
STA 459+00 TO STA 459+46.62		64						
STA 459+81.62 TO STA 460+49.49		85						
STA 460+29.62 TO STA 460+49.49		20						
STA 460+29.62 TO STA 460+49.49		20						
STA 459+00 TO STA 459+46.62								49
STA 459+81.62 TO STA 460+49.49								112
STA 460+29.62 TO STA 459+49.49								15
STA 9+55.88					64			
STA 9+61.88					67			
STA 10+53.5					70			
STA 10+59.5					67			
STA 460+49.49 TO STA 462+09.49		160						
STA 461+14.49 TO STA 462+09.49								
STA 460+49.49 TO STA 462+09.49								137
STA 461+14.49 TO STA 462+09.49								9
<b>TOTALS</b>	<b>31</b>		<b>7377</b>		<b>529</b>	<b>42</b>		<b>532</b>

**SHORT-TERM PAVEMENT MARKING SCHEDULE**

LOCATION	DESCRIPTION	TPM	TPM -	TPM -	TPM -
		L & S	LINE 5' WHITE	LINE 5' YELLOW	DOUBLE LINE 5' YELLOW
		SQ FT	FOOT	FOOT	FOOT
<b>MEADOWBROOK ROAD</b>					
STA 2+54 TO STA 9+56, 13.5' LT	LEFT EDGE PVMT		68		
STA 2+54 TO STA 9+52, 13.5' RT	RIGHT EDGE PVMT		68		
STA 2+54 TO STA 7+95, 4.5' LT	CENTERLINE				104
STA 7+95 TO STA 8+47.5, 4.5' LT	CENTERLINE TAPERS				32
STA 8+47.5 TO STA 9+52, 3.0' & 6.0' LT	CENTERLINE				48
STA 10+59					