

STATE OF ILLINOIS  
DEPARTMENT OF TRANSPORTATION

FAI Route 72  
D 5 OVD SIN STR REPL 2010-01  
Champaign County  
Sheet 3 of 23  
Contract Number 46062

District 5  
Schedule of Overhead Sign Structure Replacement

Location No.:	5-01	State I.D. No.:	5S010I072R181.52		
County:	Champaign	Route:	I-72	M.P.:	181.52
		Direction:	EB		
Description of Work	Unit	Quantity			
REMOVE AND REINSTALL WALKWAY	FOOT	61.00			
REMOVE AND REINSTALL SIGN PANEL	SQ FT	408.00			
FURNISH AND INSTALL SAFETY CHAIN	EACH	2.00			
REPAIR HANDRAIL LOCKING PIN CONNECTION	EACH	5.00			
ELECTRICAL SERVICE DISCONNECT	EACH	1.00			
CHANGEABLE MESSAGE SIGN	CAL DAY	35.00			
OVERHEAD SIGN STRUCTURE - SPAN, TYPE I-A (4'-0" x 4' 6")	FOOT	79.00			
DRILLED SHAFT CONCRETE FOUNDATIONS	CU YD	21.50			
REMOVE OVERHEAD SIGN STRUCTURE - SPAN	EACH	1.00			
REMOVE CONCRETE FOUNDATION OVERHEAD	EACH	2.00			
STRUCTURAL STEEL SUPPORT OVERHEAD SIGN STRUCTURE - SPAN	EACH	2.00			

Location No.:	5-02	State I.D. No.:	5C010I072L181.74		
County:	Champaign	Route:	I-72	M.P.:	181.74
		Direction:	WB		
Description of Work	Unit	Quantity			
REMOVE AND REINSTALL WALKWAY	FOOT	18.00			
REMOVE AND REINSTALL SIGN PANEL	SQ FT	153.00			
FURNISH AND INSTALL SAFETY CHAIN	EACH	2.00			
REPAIR HANDRAIL LOCKING PIN CONNECTION	EACH	1.00			
REPLACE HANDRAIL SUPPORT	EACH	1.00			
ELECTRICAL SERVICE DISCONNECT	EACH	1.00			
CHANGEABLE MESSAGE SIGN	CAL DAY	35.00			
OVERHEAD SIGN STRUCTURE - CANTILEVER, TYPE II-C-A (36" x 5' 6")	FOOT	27.00			
DRILLED SHAFT CONCRETE FOUNDATIONS	CU YD	9.00			
REMOVE OVERHEAD SIGN STRUCTURE - CANTILEVER	EACH	1.00			
REMOVE CONCRETE FOUNDATION OVERHEAD	EACH	1.00			