

SUMMARY OF QUANTITIES			URBAN 100% TOTAL QUANTITIES	CONSTRUCTION TYPE CODE	
CODE NO.	ITEM	UNIT		1000	X220-2A
25000400	NITROGEN FERTILIZER NUTRIENT	POUND	23	23	
25000500	PHOSPHORUS FERTILIZER NUTRIENT	POUND	23	23	
25000600	POTASSIUM FERTILIZER NUTRIENT	POUND	23	23	
20200100	EARTH EXCAVATION	CU YD	460	460	
20201200	REMOVAL AND DISPOSAL OF UNSUITABLE MATERIAL	CU YD	202	202	
20201550	SUB-BASE GRANULAR MATERIAL, TYPE B	CU YD	428	428	
20400800	FURNISHED EXCAVATION	CU YD	30	30	
21101615	TOPSOIL FURNISH AND PLACE, 4"	SQ YD	1232	1232	
25000210	SEEDING, CLASS 2A	ACRE	0.3	0.3	
25100630	EROSION CONTROL BLANKET	SQ YD	1232	1232	
28000250	TEMPORARY EROSION CONTROL SEEDING	POUND	50	50	
28000300	TEMPORARY DITCH CHECKS	EACH	4	4	
28000400	PERIMETER EROSION BARRIER	FOOT	510	510	
40600200	BITUMINOUS MATERIALS (PRIME COAT)	TON	152	152	
40600300	AGGREGATE (PRIME COAT)	TON	682	682	
40600400	MIXTURE FOR CRACKS, JOINTS, AND FLANGEWAYS	TON	103	103	
40600895	CONSTRUCTING TEST STRIP	EACH	4	4	
40600982	HOT-MIX ASPHALT SURFACE REMOVAL - BUTT JOINT	SQ YD	391	391	
40601005	HOT-MIX ASPHALT REPLACEMENT OVER PATCHES	TON	613	613	
40603085	HOT-MIX ASPHALT BINDER COURSE, IL-19.0, N70	TON	29,568	29,568	
40603240	POLYMERIZED HOT-MIX ASPHALT BINDER COURSE, IL-19.0, N90	TON	270	270	
40603340	HOT-MIX ASPHALT SURFACE COURSE, MIX "D", N70	TON	19,146	19,146	
40603595	POLYMERIZED HOT-MIX ASPHALT SURFACE COURSE, MIX "F", N90	TON	4,428	4,428	
44000164	HOT-MIX ASPHALT SURFACE REMOVAL, 3 3/4"	SQ YD	207,366	207,366	
44000165	HOT-MIX ASPHALT SURFACE REMOVAL, 4"	SQ YD	289,564	289,564	
44000920	BITUMINOUS CONCRETE SHOULDER REMOVAL	SQ YD	419	419	
44002216	HOT-MIX ASPHALT REMOVAL OVER PATCHES, 4"	SQ YD	2,736	2,736	
44201765	CLASS D PATCHES, TYPE II, 10 INCH	SQ YD	1631	1631	

\* SPECIALTY ITEM

SUMMARY OF QUANTITIES			URBAN 100% TOTAL QUANTITIES	CONSTRUCTION TYPE CODE	
CODE NO.	ITEM	UNIT		1000	X220-2A
44201769	CLASS D PATCHES, TYPE III, 10 INCH	SQ YD	360	360	
44201771	CLASS D PATCHES, TYPE IV, 10 INCH	SQ YD	268	268	
44300100	AREA REFLECTIVE CRACK CONTROL TREATMENT	SQ YD	33,607	33,607	
44300200	STRIP REFLECTIVE CRACK CONTROL TREATMENT	FOOT	302,786	302,786	
48203029	HOT-MIX ASPHALT SHOULDERS, 8"	SQ YD	1151	1151	
50157301	PROTECTIVE SHIELD (PERMANENT)	SQ YD	711		711
52000340	NEOPRENE EXPANSION JOINT 4"	FOOT	234		234
58700300	CONCRETE SEALER	SQ FT	93832		93832
63500105	DELINEATORS	EACH	1	1	
64200105	SHOULDER RUMBLE STRIP	FOOT	141,544	141,544	
<del>67000400</del>	<del>ENGINEER'S FIELD OFFICE, TYPE A</del>	<del>GAL MO</del>	<del>9</del>	<del>9</del>	
67100100	MOBILIZATION	L SUM	1	1	
70102550	TRAFFIC CONTROL AND PROTECTION FOR TEMPORARY DETOUR	EACH	1	1	
<del>70103017</del>	<del>TRAFFIC CONTROL SURVEILLANCE (SPECIAL)</del>	<del>CAL DA</del>	<del>24</del>	<del>24</del>	
<del>70300100</del>	<del>SHORT TERM PAVEMENT MARKING</del>	<del>FOOT</del>	<del>64576</del>	<del>64576</del>	
<del>70300200</del>	<del>TEMPORARY PAVEMENT MARKING - LINE 4"</del>	<del>FOOT</del>	<del>126600</del>	<del>126600</del>	
<del>70300230</del>	<del>TEMPORARY PAVEMENT MARKING - LINE 5"</del>	<del>FOOT</del>	<del>35770</del>	<del>35770</del>	
<del>70300250</del>	<del>TEMPORARY PAVEMENT MARKING - LINE 8"</del>	<del>FOOT</del>	<del>17951</del>	<del>17951</del>	
<del>70300200</del>	<del>TEMPORARY PAVEMENT MARKING - LINE 12"</del>	<del>FOOT</del>	<del>6068</del>	<del>6068</del>	
70301000	WORK ZONE PAVEMENT MARKING REMOVAL	SQ FT	11669	11669	
70400100	TEMPORARY CONCRETE BARRIER	FOOT	1692	1692	
70400200	RELOCATE TEMPORARY CONCRETE BARRIER	FOOT	1692	1692	
* 78000200	THERMOPLASTIC PAVEMENT MARKING - LINE 4"	FOOT	116,266	116,266	
* 78000500	THERMOPLASTIC PAVEMENT MARKING - LINE 8"	FOOT	52,223	52,223	
* 78000600	THERMOPLASTIC PAVEMENT MARKING - LINE 12"	FOOT	6068	6068	
* 78004220	PREFORMED PLASTIC PAVEMENT MARKING, TYPE B - INLAID - LINE 5"	FOOT	35770	35770	
* 78005110	EPOXY PAVEMENT MARKING - LINE 4"	FOOT	33,304	33,304	
* 78005120	EPOXY PAVEMENT MARKING - LINE 5"	FOOT	35,600	35,600	

**LOYCO, INC.**  
CONSULTING ENGINEERS  
1560 WALL ST, SUITE 222  
NAPERVILLE, ILLINOIS 60563 Ph: (630) 571-9100

DESIGNED - MJY  
DRAWN - ST  
CHECKED - MJY  
DATE - 07/08/2009

REVISED -  
REVISED -  
REVISED -

**STATE OF ILLINOIS  
DEPARTMENT OF TRANSPORTATION**

**SUMMARY OF QUANTITIES  
I-80 (EAST OF 80th AVE. TO I-294)**

SCALE: NONE SHEET NO. 1 OF 2 SHEETS STA. TO STA.

F.A.I. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
80	(95-5-1, ETC, 1819-824) RS-1	WILL & COOK	80	3
D-91-215-09		CONTRACT NO. 60F61		
FED. ROAD DIST. NO.		ILLINOIS FED. AID PROJECT		

Rev.