

SUMMARY OF QUANTITIES			URBAN 100% FED. TOTAL QUANTITIES		CONSTRUCTION TYPE CODE	
CODE NO.	ITEM	UNIT	1000	X220-2A		
* 78100100	RAISED REFLECTIVE PAVEMENT MARKER	EACH	3096	3096		
* 78100105	RAISED REFLECTIVE PAVEMENT MARKER (BRIDGE)	EACH	112	112		
* 78200500	BARRIER WALL MARKERS	EACH	200	200		
78300100	PAVEMENT MARKING REMOVAL	SQ FT	623	623		
78300200	RAISED REFLECTIVE PAVEMENT MARKER REMOVAL	EACH	3208	3096	112	
81603005	UNIT DUCT, 600V, 3-1/C NO. 1, 1/2" NO. 4 GROUND, (XLP-TYPE USE), 1 1/4" DIA., POLYETHYLENE	FOOT	750	750		
* 81900200	TRENCH AND BACKFILL FOR ELECTRICAL WORK	FOOT	718	718		
* 82102400	LUMINAIRE, SODIUM VAPOR, HORIZONTAL MOUNT, 400 WATT	EACH	6	6		
* 83050810	LIGHT POLE, ALUMINUM, 47.5 FT. M.H., 15 FT. MAST ARM	EACH	3	3		
* 84200500	REMOVAL OF EXISTING LIGHTING UNIT, SALVAGE	EACH	1	1		
87000100	CONCRETE FOUNDATION, TYPE E 30 INCH DIAMETER	FOOT	30	30		
89502305	REMOVE EXISTING CONCRETE FOUNDATION	EACH	2	2		
X0320887	POLYMER CONCRETE	CU FT	41		41	
X0321744	SILICONE JOINT SEALER, 2"	FOOT	519		519	
X0322247	MAINTENANCE OF EXISTING TRAFFIC SURVEILLANCE	L SUM	1	1		
X0322256	TEMPORARY INFORMATION SIGNING	SQ FT	1236	1236		
X0322729	MATERIAL TRANSFER DEVICE	TON	65,532	65,532		
X0324194	TEMPORARY EPOXY PAVEMENT MARKING 4"	FOOT	40772	40772		
X0324495	TEMPORARY EPOXY PAVEMENT MARKING 5"	FOOT	17885	17885		
78005140	EPOXY PAVEMENT MARKING- LINE 8"	FOOT	52,223	52,223		
X0324497	TEMPORARY EPOXY PAVEMENT MARKING 12"	FOOT	2347	2347		
X0325702	NIGHTTIME WORK ZONE LIGHTING	L SUM	1	1		
X0324685	TEST STRIP (STONE MATRIX ASPHALT)	EACH	2	2		
X0325775	WET REFLECTIVE TEMPORARY TAPE, TYPE III, 4 INCH	FOOT	362,135	362,135		
X0325840	WET REFLECTIVE TEMPORARY TAPE, TYPE III, 12 INCH	FOOT	15,019	15,019		
X0325876	WET REFLECTIVE TEMPORARY TAPE, TYPE III, 8 INCH	FOOT	87,103	87,103		
X0326107	WET REFLECTIVE TEMPORARY TAPE, TYPE III, 5 INCH	FOOT	177,310	177,310		

* SPECIALTY ITEM

SUMMARY OF QUANTITIES			URBAN 100% FED. TOTAL QUANTITIES		CONSTRUCTION TYPE CODE	
CODE NO.	ITEM	UNIT	1000	X220-2A		
X4066580	POLYMERIZED HOT-MIX ASPHALT SURFACE COURSE, STONE MATRIX ASPHALT, N80	TON	35,817	35,817		
X4066685	POLYMERIZED HOT-MIX ASPHALT BINDER COURSE, STONE MATRIX ASPHALT, N80	TON	29,715	29,715		
X7011015	TRAFFIC CONTROL AND PROTECTION (EXPRESSWAYS)	L SUM	1	1		
X7013820	TRAFFIC CONTROL SURVEILLANCE, EXPRESSWAYS	CAL DA	24	24		
70106800	CHANGEABLE MESSAGE SIGN	CAL MO	24	24		
* X8730312	ELECTRIC CABLE IN CONDUIT, LEAD-IN, NO. 18 4/C, TWISTED, SHIELDED	FOOT	6743	6743		
* X8850102	INDUCTION LOOP	FOOT	1635	1635		
XX004814	SILICONE JOINT SEALER, 3"	FOOT	244		244	
* XX006937	GROUND ROD, 5/8" DIA. X 10 FT.	EACH	6	6		
Z0013798	CONSTRUCTION LAYOUT	L SUM	1	1		
Z0016200	DECK SLAB REPAIR (PARTIAL)	SQ YD	5		5	
Z0016002	DECK SLAB REPAIR (FULL DEPTH, TYPE II)	SQ YD	4		4	
Z0030250	IMPACT ATTENUATORS, TEMPORARY (NON-REDIRECTIVE), TEST LEVEL 3	EACH	3	3		
Z0030350	IMPACT ATTENUATORS, RELOCATE (NON-REDIRECTIVE), TEST LEVEL 3	EACH	2	2		
20076600	TRAINEES	HOOR	2000	2000		
* 78000100	THERMOPLASTIC PAVEMENT MARKING - LETTERS AND SYMBOLS	SQ FT	146	146		
X0325842	WET REFLECTIVE TEMPORARY TAPE, TYPE III, LETTERS AND SYMBOLS	SQ FT	10,798	10,798		
* X8160395	UNIT DUCT, WITH 3-1/C NO. 2 AND 1/C NO. 4 GROUND, 600V (EPR-TYPE RHW), 1 1/2" DIA., POLYETHYLENE	FOOT	1,028	1,028		
* 84200700	LIGHTING FOUNDATION REMOVAL	EACH	3	3		
* 83800205	BREAKAWAY DEVICE, TRANSFORMER BASE, 15 INCH BOLT CIRCLE	EACH	5	5		
* X0324387	LUMINAIRE SAFETY CABLE ASSEMBLY	EACH	6	6		
* X0323574	MAINTENANCE OF LIGHTING SYSTEM	CAL MO	3	3		
* 83600200	LIGHT POLE FOUNDATION, 24" DIAMETER	FOOT	50	50		
48101600	AGGREGATE SHOULDERS, TYPE B 8"	SQ YD	6,550	6,550		
48102100	AGGREGATE WEDGE SHOULDER, TYPE B	TON	1,032	1,032		
* 78008210	POLYUREA PAVEMENT MARKING TYPE I - LINE 4"	FOOT	3,908	3,908		
* 78008220	POLYUREA PAVEMENT MARKING TYPE I - LINE 5"	FOOT	1,020	1,020		
* 78008250	POLYUREA PAVEMENT MARKING TYPE I - LINE 12"	FOOT	1,000	1,000		
X6700410	ENGINEER'S FIELD OFFICE, TYPE A (SPECIAL)	CAL MO	6	6		
* X7240600	REMOVE AND RE-ERECT EXISTING SIGN	EACH	6	6		

LONGO INC.
CONSULTING ENGINEERS
1560 WALL ST, SUITE 222
NAPERVILLE, ILLINOIS 60563 PH 630/577-3100

DESIGNED - MJY
DRAWN - ST
CHECKED - MJY
DATE - 07/08/2009

REVISED -
REVISED -
REVISED -

STATE OF ILLINOIS
DEPARTMENT OF TRANSPORTATION

SUMMARY OF QUANTITIES
I-80 (EAST OF 80th AVE TO I-294)

SCALE: NONE SHEET NO. 2 OF 2 SHEETS STA. TO STA.

F.A.I. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
80	(95-5-1, ETC, 1819-824) RS-1	WILL & COOK	80	4
D-91-215-09		CONTRACT NO. 60F61		
FED. ROAD DIST. NO.		ILLINOIS FED. AID PROJECT		