

SUMMARY OF QUANTITIES			CONSTRUCTION TYPE CODE						SUMMARY OF QUANTITIES			CONSTRUCTION TYPE CODE							
CODE NO	ITEM	UNIT	TOTAL QUANTITIES	LOCATION						CODE NO	ITEM	UNIT	TOTAL QUANTITIES	LOCATION					
				1000	1000									1000	1000				
20101200	TREE ROOT PRUNING	EACH	40		40														
20201006	GRADING AND SHAPING SHOULDERS	UNIT	223	117	106														
40600200	BITUMINOUS MATERIALS (PRIME COAT)	TON	44	23	21														
40600300	AGGREGATE (PRIME COAT)	TON	222	116	106														
40600400	MIXTURE FOR CRACKS, JOINTS, AND FLANGEWAYS	TON	23	12	11														
40600895	CONSTRUCTING TEST STRIP	EACH	2	1	1														
40600982	HOT-MIX ASPHALT SURFACE REMOVAL - BUTT JOINT	SO YD	90	45	45														
40603340	HOT-MIX ASPHALT SURFACE COURSE, MIX "D", N70	TON	4668	2450	2218														
44000158	HOT-MIX ASPHALT SURFACE REMOVAL, 2 1/4"	SO YD	53887	28250	25637														
44201803	CLASS D PATCHES, TYPE II, 13 INCH	SO YD	746	234	512														
44201807	CLASS D PATCHES, TYPE III, 13 INCH	SO YD	304	112	192														
44201809	CLASS D PATCHES, TYPE IV, 13 INCH	SO YD	1658	1082	576														
48102100	AGGREGATE WEDGE SHOULDER, TYPE B	TON	447	235	212														
67000400	ENGINEER'S FIELD OFFICE, TYPE A	CAL MO	6	3	3														
67100100	MOBILIZATION	L SUM	1	.5	.5														
70100310	TRAFFIC CONTROL AND PROTECTION, STANDARD 701421	L SUM	1	.5	.5														
70300100	SHORT-TERM PAVEMENT MARKING	FOOT	18160	9500	8660														
70300220	TEMPORARY PAVEMENT MARKING - LINE 4"	FOOT	45898	24420	21478														
70300280	TEMPORARY PAVEMENT MARKING - LINE 24"	FOOT	50	50															
70301000	WORK ZONE PAVEMENT MARKING REMOVAL	SO FT	6054	3167	2887														
*78000200	THERMOPLASTIC PAVEMENT MARKING - LINE 4"	FOOT	45898	24420	21478														
*78000650	THERMOPLASTIC PAVEMENT MARKING - LINE 24"	FOOT	50	50															
*78100100	RAISED REFLECTIVE PAVEMENT MARKER	EACH	1130	600	530														
*78201000	TERMINAL MARKER - DIRECT APPLIED	EACH	3		3														
78300200	RAISED REFLECTIVE PAVEMENT MARKER REMOVAL	EACH	985	535	450														
X0322256	TEMPORARY INFORMATION SIGNING	SO FT	102.8	51.4	51.4														
X4067107	POLYMERIZED LEVELING BINDER (MACHINE METHOD), 1L-4.75, N50	TON	2185	1145	1040														
20076600	TRAINEE'S	HOUR	500	500															
	* SPECIALTY ITEM @ Y080																		