

SUMMARY OF QUANTITIES			URBAN 100% FED.	CONSTRUCTION TYPE CODE				SUMMARY OF QUANTITIES			URBAN 100% FED.	CONSTRUCTION TYPE CODE								
CODE NO	ITEM	UNIT	TOTAL QUANTITIES	MCHENRY 1000	LAKE 1000	COOK 1000				CODE NO	ITEM	UNIT	TOTAL QUANTITIES	MCHENRY 1000	LAKE 1000	COOK 1000				
20201006	GRADING AND SHAPING SHOULDERS	UNIT	451	103	122	226				* 78000600	THERMOPLASTIC PAVEMENT MARKING - LINE 12"	FOOT	192	44	52	96				
40600200	BITUMINOUS MATERIALS (PRIME COAT)	TON	27	6	7	14				* 78000650	THERMOPLASTIC PAVEMENT MARKING - LINE 24"	FOOT	80	18	22	40				
40600300	AGGREGATE (PRIME COAT)	TON	135	31	36	68				* 78100100	RAISED REFLECTIVE PAVEMENT MARKER	EACH	556	128	150	278				
40600400	MIXTURE FOR CRACKS, JOINTS, AND FLANGWAYS	TON	34	8	9	17				78300200	RAISED REFLECTIVE PAVEMENT MARKER REMOVAL	EACH	556	128	150	278				
40600895	CONSTRUCTING TEST STRIP	EACH	1	0.2	0.3	0.5				X0322256	TEMPORARY INFORMATION SIGNING	SO FT	51.4		25.7	25.7				
40600982	HOT-MIX ASPHALT SURFACE REMOVAL - BUTT JOINT	SO YD	275	63	74	138				X4067107	POLYMERIZED LEVELING BINDER (MACHINE METHOD), IL-4.75, N50	TON	2666	613	720	1333				
40603340	HOT-MIX ASPHALT SURFACE COURSE, MIX "D", N70	TON	5688	1308	1536	2844														
44000158	HOT-MIX ASPHALT SURFACE REMOVAL, 2 1/4"	SO YD	67716	15575	18283	33858														
44201785	CLASS D PATCHES, TYPE I, 12 INCH	SO YD	30	7	8	15														
44201789	CLASS D PATCHES, TYPE II, 12 INCH	SO YD	360	83	97	180														
44201794	CLASS D PATCHES, TYPE III, 12 INCH	SO YD	64	15	17	32														
48102100	AGGREGATE WEDGE SHOULDER, TYPE B	TON	2442	562	659	1221														
67000400	ENGINEER'S FIELD OFFICE, TYPE A	CAL MO	6	1	2	3														
67100100	MOBILIZATION	L SUM	1	0.2	0.3	0.5														
70100460	TRAFFIC CONTROL AND PROTECTION, STANDARD 701306	L SUM	1	0.2	0.3	0.5														
70100600	TRAFFIC CONTROL AND PROTECTION, STANDARD 701336	L SUM	1	0.2	0.3	0.5														
70102620	TRAFFIC CONTROL AND PROTECTION, STANDARD 701501	L SUM	1	0.2	0.3	0.5														
70102635	TRAFFIC CONTROL AND PROTECTION, STANDARD 701701	L SUM	1	0.2	0.3	0.5														
70300100	SHORT-TERM PAVEMENT MARKING	FOOT	7136	1642	1927	3567														
70300210	TEMPORARY PAVEMENT MARKING - LETTERS AND SYMBOLS	SO FT	145	33	39	73														
70300220	TEMPORARY PAVEMENT MARKING - LINE 4"	FOOT	78515	18059	21199	39257														
70300240	TEMPORARY PAVEMENT MARKING - LINE 6"	FOOT	243	55	66	122														
70300260	TEMPORARY PAVEMENT MARKING - LINE 12"	FOOT	192	44	52	96														
70300280	TEMPORARY PAVEMENT MARKING - LINE 24"	FOOT	80	18	22	40														
70301000	WORK ZONE PAVEMENT MARKING REMOVAL	SO FT	2379	547	642	1190														
* 78000100	THERMOPLASTIC PAVEMENT MARKING - LETTERS AND SYMBOLS	SO FT	145	33	39	73														
* 78000200	THERMOPLASTIC PAVEMENT MARKING - LINE 4"	FOOT	78515	18059	21199	39257														
* 78000400	THERMOPLASTIC PAVEMENT MARKING - LINE 6"	FOOT	244	56	66	122														
										* SPECIALTY ITEMS										