

SUMMARY OF QUANTITIES			URBAN TOTAL QUANTITIES	CONSTRUCTION TYPE CODE					SUMMARY OF QUANTITIES			URBAN TOTAL QUANTITIES	CONSTRUCTION TYPE CODE					
CODE NO	ITEM	UNIT		1000 100% FED						CODE NO	ITEM		UNIT	1000 100% FED				
20201006	GRADING AND SHAPING SHOULDERS	UNIT	147	147														
40600200	BITUMINOUS MATERIALS (PRIME COAT)	TON	43	43														
40600300	AGGREGATE (PRIME COAT)	TON	215	215														
40600400	MIXTURE FOR CRACKS, JOINTS, AND FLANGEWAYS	TON	80.5	80.5														
40600895	CONSTRUCTING TEST STRIP	EACH	1	1														
40600982	HOT-MIX ASPHALT SURFACE REMOVAL - BUTT JOINT	SO YD	534	534														
40603340	HOT-MIX ASPHALT SURFACE COURSE, MIX "D", N70	TON	4517	4517														
42001300	PROTECTIVE COAT	SO YD	47	47														
44000155	HOT-MIX ASPHALT SURFACE REMOVAL, 1 1/2"	SO YD	376	376														
44000158	HOT-MIX ASPHALT SURFACE REMOVAL, 2 1/4"	SO YD	53397	53397														
44001700	COMBINATION CONCRETE CURB AND GUTTER REMOVAL AND REPLACEMENT	FOOT	210	210														
48102100	AGGREGATE WEDGE SHOULDER, TYPE B	TON	587.4	587.4														
Δ 55039700	STORM SEWERS TO BE CLEANED	FOOT	1500	1500														
60300310	FRAMES AND LIDS TO BE ADJUSTED (SPECIAL)	EACH	63	63														
60406100	FRAMES AND LIDS, TYPE I, CLOSED LID	EACH	53	53														
67000400	ENGINEER'S FIELD OFFICE, TYPE A	CAL MO	6	6														
67100100	MOBILIZATION	L SUM	1	1														
70100450	TRAFFIC CONTROL AND PROTECTION, STANDARD 701201	L SUM	1	1														
70100460	TRAFFIC CONTROL AND PROTECTION, STANDARD 701306	L SUM	1	1														
70102635	TRAFFIC CONTROL AND PROTECTION, STANDARD 701701	L SUM	1	1														
70300100	SHORT-TERM PAVEMENT MARKING	FOOT	12746	12746														
70300210	TEMPORARY PAVEMENT MARKING - LETTERS AND SYMBOLS	SO FT	936.4	936.4														
70300220	TEMPORARY PAVEMENT MARKING - LINE 4"	FOOT	46737	46737														
70300240	TEMPORARY PAVEMENT MARKING - LINE 6"	FOOT	3961	3961														
70300260	TEMPORARY PAVEMENT MARKING - LINE 12"	FOOT	1237	1237														
70300280	TEMPORARY PAVEMENT MARKING - LINE 24"	FOOT	621	621														
70301000	WORK ZONE PAVEMENT MARKING REMOVAL	SO FT	1416	1416														
• 78000100	THERMOPLASTIC PAVEMENT MARKING - LETTERS AND SYMBOLS	SO FT	936.4	936.4														
• 78000200	THERMOPLASTIC PAVEMENT MARKING - LINE 4"	FOOT	46737	46737														
• 78000400	THERMOPLASTIC PAVEMENT MARKING - LINE 6"	FOOT	3961	3961														
• 78000600	THERMOPLASTIC PAVEMENT MARKING - LINE 12"	FOOT	1237	1237														
• 78000650	THERMOPLASTIC PAVEMENT MARKING - LINE 24"	FOOT	621	621														
• 78100100	RAISED REFLECTIVE PAVEMENT MARKER	EACH	602	602														
78300200	RAISED REFLECTIVE PAVEMENT MARKER REMOVAL	EACH	482	482														
* 88600600	DETECTOR LOOP REPLACEMENT	FOOT	2027	2027														
X0322256	TEMPORARY INFORMATION SIGNING	SO FT	51.4	51.4														
X4067107	POLYMERIZED LEVELING BINDER (MACHINE METHOD), IL-4.75, N50	TON	2103	2103														
Δ Z0014800	CULVERT TO BE CLEANED	FOOT	920	920														
Δ Z0018500	DRAINAGE STRUCTURES TO BE CLEANED	EACH	42	42														
Z0048665	RAILROAD PROTECTIVE LIABILITY INSURANCE	L SUM	1	1														
*X4421803	CLASS D PATCHES, TYPE II, 13 1/4"	SOYD	765	765														
*X4421807	CLASS D PATCHES, TYPE III, 13 1/4"	SOYD	333	333														
*X4421809	CLASS D PATCHES, TYPE IV, 13 1/4"	SOYD	3790	3790														
70102620	TRAFFIC CONTROL AND PROTECTION, STANDARD 701501	L SUM	1	1														
70102625	TRAFFIC CONTROL AND PROTECTION, STANDARD 701606	L SUM	1	1														
<i>Non-participating</i>																		
* SPECIALTY ITEMS																		