

SUMMARY OF QUANTITIES

PAY ITEM NUMBER	DESCRIPTION	UNIT	URBAN	
			100% FED. TOTAL QUANTITY	1000-2A
40600200	BITUMINOUS MATERIALS (PRIME COAT)	TON	89	89
40600300	AGGREGATE (PRIME COAT)	TON	1,170	1,170
40600400	MIXTURE FOR CRACKS, JOINTS, AND FLANGEWAYS	TON	106	106
40600895	CONSTRUCTING TEST STRIP	EACH	2	2
40600982	HOT-MIX ASPHALT SURFACE REMOVAL - BUTT JOINT	SQ YD	2,123	2,123
40603595	POLYMERIZED HOT-MIX ASPHALT SURFACE COURSE, MIX "F", N90	TON	20,946	20,946
42101300	PROTECTIVE COAT	SQ YD	1,782	1,782
44000159	HOT-MIX ASPHALT SURFACE REMOVAL, 2 1/2"	SQ YD	212,712	212,712
44001700	COMBINATION CONCRETE CURB AND GUTTER REMOVAL AND REPLACEMENT	FOOT	2,560	2,560
44003100	MEDIAN REMOVAL	SQ FT	8,257	8,257
44201713	CLASS D PATCHES, TYPE I, 6 INCH	SQ YD	270	270
44201717	CLASS D PATCHES, TYPE II, 6 INCH	SQ YD	2,401	2,401
44201721	CLASS D PATCHES, TYPE III, 6 INCH	SQ YD	1,201	1,201
44201723	CLASS D PATCHES, TYPE IV, 6 INCH	SQ YD	480	480
44201785	CLASS D PATCHES, TYPE I, 12 INCH	SQ YD	196	196
44201789	CLASS D PATCHES, TYPE II, 12 INCH	SQ YD	655	655
44201794	CLASS D PATCHES, TYPE III, 12 INCH	SQ YD	327	327
44201796	CLASS D PATCHES, TYPE IV, 12 INCH	SQ YD	131	131
48102100	AGGREGATE WEDGE SHOULDER, TYPE B	TON	923	923
NP 55039700	STORM SEWERS TO BE CLEANED	FOOT	330	330
60300310	FRAMES AND LIDS TO BE ADJUSTED (SPECIAL)	EACH	113	113
60618300	CONCRETE MEDIAN SURFACE, 4 INCH	SQ FT	870	870
60619600	CONCRETE MEDIAN, TYPE SB-6.12	SQ FT	6,286	6,286
60624600	CORRUGATED MEDIAN	SQ FT	1,101	1,101
* 63100045	TRAFFIC BARRIER TERMINAL, TYPE 2	EACH	2	2
* 63100167	TRAFFIC BARRIER TERMINAL, TYPE 1 (SPECIAL) TANGENT	EACH	12	12

* DENOTES SPECIALTY ITEM

NP Non-participating

PAY ITEM NUMBER	DESCRIPTION	UNIT	URBAN	
			100% FED. TOTAL QUANTITY	1000-2A
63200310	GUARDRAIL REMOVAL	FOOT	561	561
67000400	ENGINEER'S FIELD OFFICE, TYPE A	CAL MO	6	6
67100100	MOBILIZATION	L SUM	1	1
70102825	TRAFFIC CONTROL AND PROTECTION, STANDARD 701806	L SUM	1	1
70102630	TRAFFIC CONTROL AND PROTECTION, STANDARD 701601	L SUM	1	1
70102632	TRAFFIC CONTROL AND PROTECTION, STANDARD 701602	L SUM	1	1
70102635	TRAFFIC CONTROL AND PROTECTION, STANDARD 701701	L SUM	1	1
70300100	SHORT-TERM PAVEMENT MARKING	FOOT	22,476	22,476
70300210	TEMPORARY PAVEMENT MARKING - LETTERS AND SYMBOLS	SQ FT	6,178	6,178
70300220	TEMPORARY PAVEMENT MARKING - LINE 4"	FOOT	224,764	224,764
70300240	TEMPORARY PAVEMENT MARKING - LINE 6"	FOOT	19,492	19,492
70300260	TEMPORARY PAVEMENT MARKING - LINE 12"	FOOT	2,652	2,652
70300280	TEMPORARY PAVEMENT MARKING - LINE 24"	FOOT	6,008	6,008
* 78000100	THERMOPLASTIC PAVEMENT MARKING - LETTERS AND SYMBOLS	SQ FT	3,089	3,089
* 78000200	THERMOPLASTIC PAVEMENT MARKING - LINE 4"	FOOT	112,382	112,382
* 78000400	THERMOPLASTIC PAVEMENT MARKING - LINE 6"	FOOT	9,746	9,746
* 78000500	THERMOPLASTIC PAVEMENT MARKING - LINE 8"	FOOT	1,326	1,326
* 78000600	THERMOPLASTIC PAVEMENT MARKING - LINE 12"	FOOT	3,004	3,004
* 78000650	THERMOPLASTIC PAVEMENT MARKING - LINE 24"	FOOT	1,873	1,873
* 78100100	RAISED REFLECTIVE PAVEMENT MARKER	EACH	3,130	3,130
* 78201000	TERMINAL MARKER - DIRECT APPLIED	EACH	12	12
78300200	RAISED REFLECTIVE PAVEMENT MARKER REMOVAL	EACH	3,130	3,130
* 88600600	DETECTOR LOOP REPLACEMENT	FOOT	8,144	8,144
X0322256	TEMPORARY INFORMATION SIGNING	SQ FT	612	612
X4067107	POLYMERIZED LEVELING BINDER (MACHINE METHOD), IL-4.75, N50	TON	8,934	8,934
NP Z0018500	DRAINAGE STRUCTURES TO BE CLEANED	EACH	33	33

* 20076600 TRAINEES

HOUR 1000 1000

0 1080

FILE NAME =	USER NAME = .USER.	DESIGNED -	REVISED -	STATE OF ILLINOIS DEPARTMENT OF TRANSPORTATION	IL 59 - IL 64 TO BATAVIA ROAD SUMMARY OF QUANTITIES	F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.	
*FILE#		DRAWN -	REVISED -			338	(111 & 112) RS-8	DUPAGE	42	3	
	PLOT SCALE = 50,000' / IN.	CHECKED -	REVISED -			CONTRACT NO. 60H70					
	PLOT DATE = 6/24/2009	DATE -	REVISED -			ILLINOIS FED. AID PROJECT					