

SUMMARY OF QUANTITIES			CONSTRUCTION TYPE CODE					SUMMARY OF QUANTITIES			CONSTRUCTION TYPE CODE							
CODE NO	ITEM	UNIT	TOTAL QUANTITIES	URBAN I000-2A					CODE NO	ITEM	UNIT	TOTAL QUANTITIES	URBAN I000-2A					
20201006	GRADING AND SHAPING SHOULDERS	UNIT	92	92					70300210	TEMPORARY PAVEMENT MARKING - LETTERS AND SYMBOLS	SO FT	521	521					
40600200	BITUMINOUS MATERIALS (PRIME COAT)	TON	30	30					70300220	TEMPORARY PAVEMENT MARKING - LINE 4"	FOOT	29,743	29,743					
40600300	AGGREGATE (PRIME COAT)	TON	149	149					70300240	TEMPORARY PAVEMENT MARKING - LINE 6"	FOOT	1,680	1,680					
40600400	MIXTURE FOR CRACKS, JOINTS, AND FLANGWAYS	TON	50	50					70300260	TEMPORARY PAVEMENT MARKING - LINE 12"	FOOT	350	350					
40600895	CONSTRUCTING TEST STRIP	EACH	1	1					70300280	TEMPORARY PAVEMENT MARKING - LINE 24"	FOOT	200	200					
40600982	HOT-MIX ASPHALT SURFACE REMOVAL - BUTT JOINT	SO YD	415	415					* 78000100	THERMOPLASTIC PAVEMENT MARKING - LETTERS AND SYMBOLS	SO FT	521	521					
40601005	HOT-MIX ASPHALT REPLACEMENT OVER PATCHES	TON	416	416					* 78000200	THERMOPLASTIC PAVEMENT MARKING - LINE 4"	FOOT	29,743	29,743					
40603340	HOT-MIX ASPHALT SURFACE COURSE, MIX "D", N70	TON	3,117	3,117					* 78000400	THERMOPLASTIC PAVEMENT MARKING - LINE 6"	FOOT	1,680	1,680					
42001300	PROTECTIVE COAT	SO YD	42	42					* 78000600	THERMOPLASTIC PAVEMENT MARKING - LINE 12"	FOOT	350	350					
44000157	HOT-MIX ASPHALT SURFACE REMOVAL, 2"	SO YD	30,684	30,684					* 78000650	THERMOPLASTIC PAVEMENT MARKING - LINE 24"	FOOT	200	200					
44001700	COMBINATION CONCRETE CURB AND GUTTER REMOVAL AND REPLACEMENT	FOOT	275	275					* 78100100	RAISED REFLECTIVE PAVEMENT MARKER	EACH	152	152					
44002212	HOT-MIX ASPHALT REMOVAL OVER PATCHES, 3"	SO YD	2,469	2,469					78300200	RAISED REFLECTIVE PAVEMENT MARKER REMOVAL	EACH	115	115					
44201749	CLASS D PATCHES, TYPE I, 9 INCH	SO YD	741	741					* 88600600	DETECTOR LOOP REPLACEMENT	FOOT	1089	1089					
44201753	CLASS D PATCHES, TYPE II, 9 INCH	SO YD	987	987					X0322256	TEMPORARY INFORMATION SIGNING	SO FT	154.2	154.2					
44201757	CLASS D PATCHES, TYPE III, 9 INCH	SO YD	741	741					X4067107	POLYMERIZED LEVELING BINDER (MACHINE METHOD), IL-4, 75, N50	TON	1445	1445					
48102100	AGGREGATE WEDGE SHOULDER, TYPE B	TON	389	389					* 55039700	STORM SEWERS TO BE CLEANED	FOOT	100	100					
60300305	FRAMES AND LIDS TO BE ADJUSTED	EACH	15	15					* 20018500	DRAINAGE STRUCTURES TO BE CLEANED	EACH	8	8					
60300310	FRAMES AND LIDS TO BE ADJUSTED (SPECIAL)	EACH	19	19														
67000400	ENGINEER'S FIELD OFFICE, TYPE A	CAL MO	3	3														
67100100	MOBILIZATION	L SUM	1	1														
70102620	TRAFFIC CONTROL AND PROTECTION, STANDARD 701501	L SUM	1	1														
70102635	TRAFFIC CONTROL AND PROTECTION, STANDARD 701701	L SUM	1	1														
70300100	SHORT-TERM PAVEMENT MARKING	FOOT	6,696	6,696														

\* Specialty Items

NON-PARTICIPATING (100% STATE)

Rev. 8-31-09