

SUMMARY OF QUANTITIES				CONSTRUCTION TYPE CODE					SUMMARY OF QUANTITIES				CONSTRUCTION TYPE CODE							
CODE NO	ITEM	UNIT	TOTAL QUANTITIES	URBAN I000-2A						CODE NO	ITEM	UNIT	TOTAL QUANTITIES	URBAN I000-2A						
																				URBAN 100% FED.
20201006	GRADING AND SHAPING SHOULDERS	UNIT	86	86						70300210	TEMPORARY PAVEMENT MARKING - LETTERS AND SYMBOLS	SO FT	448	448						
40600200	BITUMINOUS MATERIALS (PRIME COAT)	TON	15	15						70300220	TEMPORARY PAVEMENT MARKING - LINE 4"	FOOT	27846	27846						
40600300	AGGREGATE (PRIME COAT)	TON	71	71						70300240	TEMPORARY PAVEMENT MARKING - LINE 6"	FOOT	1547	1547						
40600400	MIXTURE FOR CRACKS, JOINTS, AND FLANGEWAYS	TON	18	18						70300260	TEMPORARY PAVEMENT MARKING - LINE 12"	FOOT	350	350						
40600895	CONSTRUCTING TEST STRIP	EACH	1	1						70300280	TEMPORARY PAVEMENT MARKING - LINE 24"	FOOT	200	200						
40600982	HOT-MIX ASPHALT SURFACE REMOVAL - BUTT JOINT	SO YD	385	385						* 78000100	THERMOPLASTIC PAVEMENT MARKING - LETTERS AND SYMBOLS	SO FT	448	448						
40601005	HOT-MIX ASPHALT REPLACEMENT OVER PATCHES	TON	392	392						* 78000200	THERMOPLASTIC PAVEMENT MARKING - LINE 4"	FOOT	27846	27846						
40603340	HOT-MIX ASPHALT SURFACE COURSE, MIX "D", N70	TON	2449	2449						* 78000400	THERMOPLASTIC PAVEMENT MARKING - LINE 6"	FOOT	1547	1547						
42001300	PROTECTIVE COAT	SO YD	42	42						* 78000600	THERMOPLASTIC PAVEMENT MARKING - LINE 12"	FOOT	350	350						
44000157	HOT-MIX ASPHALT SURFACE REMOVAL, 2"	SO YD	28766	28766						* 78000650	THERMOPLASTIC PAVEMENT MARKING - LINE 24"	FOOT	200	200						
44001700	COMBINATION CONCRETE CURB AND GUTTER REMOVAL AND REPLACEMENT	FOOT	125	125						* 78100100	RAISED REFLECTIVE PAVEMENT MARKER	EACH	142	142						
44002212	HOT-MIX ASPHALT REMOVAL OVER PATCHES, 3"	SO YD	2333	2333						78300200	RAISED REFLECTIVE PAVEMENT MARKER REMOVAL	EACH	107	107						
44201749	CLASS D PATCHES, TYPE I, 9 INCH	SO YD	700	700						* 88600600	DETECTOR LOOP REPLACEMENT	FOOT	959	959						
44201753	CLASS D PATCHES, TYPE II, 9 INCH	SO YD	933	933						X0322256	TEMPORARY INFORMATION SIGNING	SO FT	154.2	154.2						
44201757	CLASS D PATCHES, TYPE III, 9 INCH	SO YD	700	700						X4067107	POLYMERIZED LEVELING BINDER (MACHINE METHOD), IL-4.75, N50	TON	1133	1133						
48102100	AGGREGATE WEDGE SHOULDER, TYPE B	TON	368	368																
60300305	FRAMES AND LIDS TO BE ADJUSTED	EACH	15	15																
60300310	FRAMES AND LIDS TO BE ADJUSTED (SPECIAL)	EACH	19	19																
67000400	ENGINEER'S FIELD OFFICE, TYPE A	CAL MO	3	3																
67100100	MOBILIZATION	L SUM	1	1																
70102620	TRAFFIC CONTROL AND PROTECTION, STANDARD 701501	L SUM	1	1																
70102635	TRAFFIC CONTROL AND PROTECTION, STANDARD 701701	L SUM	1	1																
70300100	SHORT-TERM PAVEMENT MARKING	FOOT	6269	6269																

\* Specialty Items