

URBAN  
100% FED.


CODE NO.	ITEM DESCRIPTION	UNIT	TOTAL QUANTITY	CONSTRUCTION TYPE CODE	
				1000 QUANTITY	
40600200	BITUMINOUS MATERIALS (PRIME COAT)	TON	20	20	
40600300	AGGREGATE (PRIME COAT)	TON	96	96	
40600400	MIXTURE FOR CRACKS, JOINTS, AND FLANGEWAYS	TON	15	15	
40600895	CONSTRUCTING TEST STRIP	EACH	2	2	
40600982	HOT-MIX ASPHALT SURFACE REMOVAL - BUTT JOINT	SQ YD	271	271	
40601005	HOT-MIX ASPHALT REPLACEMENT OVER PATCHES	TON	222	222	
40603595	POLYMERIZED HOT-MIX ASPHALT SURFACE COURSE, MIX "F", N90	TON	4690	4690	
44000159	HOT-MIX ASPHALT SURFACE REMOVAL, 2 1/2"	SQ YD	47786	47786	
44001700	COMBINATION CONCRETE CURB AND GUTTER REMOVAL AND REPLACEMENT	FOOT	1510	1510	
44002216	HOT-MIX ASPHALT REMOVAL OVER PATCHES, 4"	SQ YD	991	991	
44201761	CLASS D PATCHES, TYPE I, 10 INCH	SQ YD	84	84	
44201765	CLASS D PATCHES, TYPE II, 10 INCH	SQ YD	336	336	
44201769	CLASS D PATCHES, TYPE III, 10 INCH	SQ YD	384	384	
44201771	CLASS D PATCHES, TYPE IV, 10 INCH	SQ YD	187	187	
NP 55039700	STORM SEWERS TO BE CLEANED	FOOT	1575	1575	
60300105	FRAMES AND GRATES TO BE ADJUSTED	EACH	10	10	
60300310	FRAMES AND LIDS TO BE ADJUSTED (SPECIAL)	EACH	50	50	
67000400	ENGINEER'S FIELD OFFICE, TYPE A	CAL MO	6	6	
67100100	MOBILIZATION	L SUM	1	1	
70100310	TRAFFIC CONTROL AND PROTECTION, STANDARD 701421	L SUM	1	1	
70102635	TRAFFIC CONTROL AND PROTECTION, STANDARD 701701	L SUM	1	1	
70300100	SHORT-TERM PAVEMENT MARKING	FOOT	9920	9920	
70300210	TEMPORARY PAVEMENT MARKING - LETTERS AND SYMBOLS	SQ FT	261	261	
70300220	TEMPORARY PAVEMENT MARKING - LINE 4"	FOOT	24690	24690	
70300240	TEMPORARY PAVEMENT MARKING - LINE 6"	FOOT	1820	1820	
70300260	TEMPORARY PAVEMENT MARKING - LINE 12"	FOOT	460	460	
70300280	TEMPORARY PAVEMENT MARKING - LINE 24"	FOOT	490	490	
70301000	WORK ZONE PAVEMENT MARKING REMOVAL	SQ FT	1102	1102	
* 78000100	THERMOPLASTIC PAVEMENT MARKING - LETTERS AND SYMBOLS	SQ FT	261	261	

URBAN  
100% FED.

CODE NO.	ITEM DESCRIPTION	UNIT	TOTAL QUANTITY	CONSTRUCTION TYPE CODE	
				1000 QUANTITY	
* 78000200	THERMOPLASTIC PAVEMENT MARKING - LINE 4"	FOOT	24690	24690	
* 78000400	THERMOPLASTIC PAVEMENT MARKING - LINE 6"	FOOT	1820	1820	
* 78000600	THERMOPLASTIC PAVEMENT MARKING - LINE 12"	FOOT	460	460	
* 78000650	THERMOPLASTIC PAVEMENT MARKING - LINE 24"	FOOT	490	490	
* 78100100	RAISED REFLECTIVE PAVEMENT MARKER	EACH	887	887	
78300200	RAISED REFLECTIVE PAVEMENT MARKER REMOVAL	EACH	887	887	
* 88600600	DETECTOR LOOP REPLACEMENT	FOOT	1592	1592	
X0322256	TEMPORARY INFORMATION SIGNING	SQ FT	104	104	
X4067107	POLYMERIZED LEVELING BINDER (MACHINE METHOD), IL-4.75, N50	TON	2010	2010	
NP Z0018500	DRAINAGE STRUCTURES TO BE CLEANED	EACH	45	45	
⊙ Z0076600	TRAINEES	HOUR	500	500	

\* SPECIALTY ITEM  
NP = Non-participating  
⊙ Y080

FILE NAME = p:\2007\ME07080\Var\Ver\_P\H1\Cadd\W017\_IL43\Shs\0350\sh1-IL43.dgn  
 USER NAME = Millennium Engineering



200 22ND Street, Suite 216, Lombard, IL 60148  
 630.785.1110 voice, 630.839.2566 fax  
 WWW.MPS-IL.COM  
**MILLENNIA PROFESSIONAL SERVICES**

DESIGNED - TVN	REVISED -
DRAWN - TVN	REVISED -
CHECKED - RPD	REVISED -
DATE - 7/8/2009	REVISED -

**STATE OF ILLINOIS**  
**DEPARTMENT OF TRANSPORTATION**

**IL ROUTE 43**  
**ILLINOIS ROUTE 60 TO GAGE LANE**

**SUMMARY OF QUANTITIES**

F.A.U. RTE. 2706	SECTION CY-RS-6	COUNTY LAKE	TOTAL SHEETS 21	SHEET NO. 3
FED. ROAD DIST. NO. 1 [ILLINOIS] FED. AID PROJECT			CONTRACT NO. 60H90	

Rev.

SCALE: NTS SHEET NO. OF SHEETS STA. TO STA.

p:\2007\ME07080\Var\Ver\_P\H1\Cadd\W017\_IL43\Shs\0350\sh1-IL43.dgn