

SUMMARY OF QUANTITIES				URBAN 100% FED.	CONSTRUCTION TYPE CODE
CODE NO.	DESCRIPTION	UNIT	TOTAL QUANTITY		ROADWAY 1000-2A
40201000	AGGREGATE FOR TEMPORARY ACCESS	TON	10		10
40600200	BITUMINOUS MATERIALS (PRIME COAT)	TON	40		40
40600300	AGGREGATE (PRIME COAT)	TON	190		190
40600400	MIXTURE FOR CRACKS, JOINTS, AND FLANGEWAYS	TON	6		6
40600535	LEVELING BINDER (HAND METHOD), N70	TON	10		10
40600895	CONSTRUCTING TEST STRIP	EACH	2		2
40600982	HOT-MIX ASPHALT SURFACE REMOVAL - BUTT JOINT	SQ YD	588		588
40601005	HOT-MIX ASPHALT REPLACEMENT OVER PATCHES	TON	330		330
40603340	HOT-MIX ASPHALT SURFACE COURSE, MIX "D", N70	TON	4,000		4,000
42300400	PORTLAND CEMENT CONCRETE DRIVEWAY PAVEMENT, 8 INCH	SQ YD	10		10
42400300	PORTLAND CEMENT CONCRETE SIDEWALK 6 INCH	SQ FT	1,500		1,500
44000158	HOT-MIX ASPHALT SURFACE REMOVAL, 2 1/4"	SQ YD	47,000		47,000
44000200	DRIVEWAY PAVEMENT REMOVAL	SQ YD	10		10
44000600	SIDEWALK REMOVAL	SQ FT	1,500		1,500
44001700	COMBINATION CONCRETE CURB AND GUTTER REMOVAL AND REPLACEMENT	FOOT	600		600
44002212	HOT-MIX ASPHALT REMOVAL OVER PATCHES, 3"	SQ YD	1,950		1,950
44003510	MEDIAN REMOVAL PARTIAL DEPTH	SQ FT	1,520		1,520
44201765	CLASS D PATCHES, TYPE II, 10 INCH	SQ YD	390		390
44201769	CLASS D PATCHES, TYPE III, 10 INCH	SQ YD	610		610
44201771	CLASS D PATCHES, TYPE IV, 10 INCH	SQ YD	680		680
NP 55039700	STORM SEWERS TO BE CLEANED	FOOT	1,900		1,900
60257900	MANHOLES TO BE RECONSTRUCTED	EACH	1		1
60300305	FRAMES AND LIDS TO BE ADJUSTED	EACH	10		10
60300310	FRAMES AND LIDS TO BE ADJUSTED (SPECIAL)	EACH	170		170
60406000	FRAMES AND LIDS, TYPE 1, OPEN LID	EACH	15		15
60406100	FRAMES AND LIDS, TYPE 1, CLOSED LID	EACH	15		15
67000400	ENGINEER'S FIELD OFFICE, TYPE A	CAL MO	6		6
67100100	MOBILIZATION	L SUM	1		1
70102620	TRAFFIC CONTROL AND PROTECTION, STANDARD 701501	L SUM	1		1
70102625	TRAFFIC CONTROL AND PROTECTION, STANDARD 701606	L SUM	1		1
70102630	TRAFFIC CONTROL AND PROTECTION, STANDARD 701601	L SUM	1		1
<b>20048665 RAILROAD PROTECTIVE LIABILITY INSURANCE</b>			<b>L SUM</b>	<b>1</b>	<b>1</b>

\* DENOTES SPECIALTY ITEM

SUMMARY OF QUANTITIES				URBAN 100% FED.	CONSTRUCTION TYPE CODE
CODE NO.	DESCRIPTION	UNIT	TOTAL QUANTITY		ROADWAY 1000-2A
70102635	TRAFFIC CONTROL AND PROTECTION, STANDARD 701701	L SUM	1		1
70102640	TRAFFIC CONTROL AND PROTECTION, STANDARD 701801	L SUM	1		1
70300100	SHORT-TERM PAVEMENT MARKING	FOOT	7,280		7,280
70300210	TEMPORARY PAVEMENT MARKING - LETTERS AND SYMBOLS	SQ FT	3,500		3,500
70300220	TEMPORARY PAVEMENT MARKING - LINE 4"	FOOT	25,800		25,800
70300240	TEMPORARY PAVEMENT MARKING - LINE 6"	FOOT	19,200		19,200
70300260	TEMPORARY PAVEMENT MARKING - LINE 12"	FOOT	8,400		8,400
70300280	TEMPORARY PAVEMENT MARKING - LINE 24"	FOOT	2,700		2,700
70301000	WORK ZONE PAVEMENT MARKING REMOVAL	SQ FT	11,900		11,900
* 78000100	THERMOPLASTIC PAVEMENT MARKING - LETTERS AND SYMBOLS	SQ FT	1,150		1,150
* 78000200	THERMOPLASTIC PAVEMENT MARKING - LINE 4"	FOOT	17,900		17,900
* 78000400	THERMOPLASTIC PAVEMENT MARKING - LINE 6"	FOOT	6,400		6,400
* 78000600	THERMOPLASTIC PAVEMENT MARKING - LINE 12"	FOOT	2,800		2,800
* 78000650	THERMOPLASTIC PAVEMENT MARKING - LINE 24"	FOOT	900		900
X0322256	TEMPORARY INFORMATION SIGNING	SQ FT	51		51
X4067107	POLYMERIZED LEVELING BINDER (MACHINE METHOD), IL-4.75, N50	TON	1,860		1,860
NP Z0018500	DRAINAGE STRUCTURES TO BE CLEANED	EACH	180		180

@ 20076600 TRAINEES HOUR 500 500

@ Y080

NP = Non-participating

FILE NAME = N:\PROJ\3368\29\Design\Proposed\Plan\3368\_29\93-Quantities.dgn

**Ciorba Group, Inc.**  
CONSULTING ENGINEERS  
5507 North Cumberland Avenue, Suite 402  
Chicago, Illinois 60655  
Tel. 773.775.4099 Fax 773.775.4014

USER NAME = mready	DESIGNED - MWR	REVISED -
PLOT SCALE = 1:8000' / 1" IN.	DRAWN - MWR	REVISED -
PLOT DATE = 6/24/2009	CHECKED - SNS	REVISED -
	DATE - 6/24/2009	REVISED -

**STATE OF ILLINOIS  
DEPARTMENT OF TRANSPORTATION**

**STATE STREET  
69TH STREET TO 60TH STREET  
SUMMARY OF QUANTITIES**

SCALE: SHEET NO. OF SHEETS STA. TO STA.

F.A.U. RTE.	SECTION	COUNTY	TOTAL SHEETS	Rev. SHEET NO.
2907	1Y (5,6 & 7) RS	COOK	17	3
FED. ROAD DIST. NO. 1 ILLINOIS FED. AID PROJECT			CONTRACT NO. 62404	