



NOTES

1. ALL PROPOSED PAVEMENT MARKINGS ON HMA ROADWAY SURFACE SHALL BE THERMOPLASTIC.
2. ALL PAVEMENT MARKINGS ON PORTLAND CEMENT CONCRETE SURFACES SHALL BE EPOXY.
3. ALL EXISTING PAVEMENT MARKING IMPACTED BY THIS PROJECT OR STAGING OPERATION SHALL BE REMOVED & REPLACED IN KIND. PAYMENTS SHALL BE ACCORDING TO APPLICABLE PAY ITEMS SHOWN IN THE SUMMARY OF QUANTITIES.
4. THE SEEDING DATES FOR BARE EARTH SEEDING OF MIXTURE CLASSES 4 & 4B SHALL BE FROM MAY 15 TO JUNE 30 AND OCTOBER 30 TO DECEMBER 1.

LEGEND

- TOPSOIL FURNISH & PLACE, 4" NITROGEN FERTILIZER NUTRIENT PHOSPHORUS FERTILIZER NUTRIENT POTASSIUM FERTILIZER NUTRIENT SEEDING, CLASS 2A EROSION CONTROL BLANKET
- TOPSOIL FURNISH & PLACE, 4" SEEDING, CLASS 4 EROSION CONTROL BLANKET
- TOPSOIL FURNISH & PLACE, 4" NITROGEN FERTILIZER NUTRIENT PHOSPHORUS FERTILIZER NUTRIENT POTASSIUM FERTILIZER NUTRIENT SODDING, SALT TOLERANT

REVISIONS	
NAME	DATE

ILLINOIS DEPARTMENT OF TRANSPORTATION
 F.A.U. 2843 DIXIE HIGHWAY
 OVER BUTTERFIELD CREEK
 PAVEMENT MARKING AND
 LANDSCAPING

SCALE: VERT. 1"=50'
 HORIZ. 1"=50'
 DATE 6-25-09

DRAWN BY AW
 DESIGNED BY AW
 CHECKED BY MF

RME Rubinos & Mesia Engineers, Inc.
 200 S. Michigan Ave., Suite 1500 Chicago IL 60604-2482
 T-312 670 6800 F-312 665 1479