

SUMMARY OF QUANTITIES			CONSTRUCTION TYPE CODE						SUMMARY OF QUANTITIES			CONSTRUCTION TYPE CODE									
CODE NO	ITEM	UNIT	URBAN 100% FED.								TOTAL QUANTITIES										
			TOTAL QUANTITIES	I-000								I-000									
20200100	EARTH EXCAVATION	CU YD	21	21							70100600	TRAFFIC CONTROL AND PROTECTION, STANDARD 701336	L SUM	1	1						
20201006	GRADING AND SHAPING SHOULDERS	UNIT	176	176							70300100	SHORT-TERM PAVEMENT MARKING	FOOT	3912	3912						
35501300	HOT-MIX ASPHALT BASE COURSE, 6"	SQ YD	44	44							70300210	TEMPORARY PAVEMENT MARKING - LETTERS AND SYMBOLS	SQ FT	462	462						
40600200	BITUMINOUS MATERIALS (PRIME COAT)	TON	22	22							70300220	TEMPORARY PAVEMENT MARKING - LINE 4"	FOOT	46246	46246						
40600300	AGGREGATE (PRIME COAT)	TON	10	10							70300240	TEMPORARY PAVEMENT MARKING - LINE 6"	FOOT	1553	1553						
40600400	MIXTURE FOR CRACKS, JOINTS, AND FLANGWAYS	TON	6	6							70300250	TEMPORARY PAVEMENT MARKING - LINE 8"	FOOT	205	205						
40600895	CONSTRUCTING TEST STRIP	EACH	2	2							70300260	TEMPORARY PAVEMENT MARKING - LINE 12"	FOOT	1056	1056						
40600982	HOT-MIX ASPHALT SURFACE REMOVAL - BUTT JOINT	SQ YD	349	349							70300280	TEMPORARY PAVEMENT MARKING - LINE 24"	FOOT	357	357						
<del>40601005</del>	<del>HOT-MIX ASPHALT REPLACEMENT OVER PATCHES</del>	<del>TON</del>	<del>3027</del>	<del>3027</del>							70301000	WORK ZONE PAVEMENT MARKING REMOVAL	SQ FT	1304	1304						
40403310	HOT-MIX ASPHALT SURFACE COURSE, MIX "C", N50	TON	5	5							78000100	THERMOPLASTIC PAVEMENT MARKING - LETTERS AND SYMBOLS	SQ FT	462	462						
40603340	HOT-MIX ASPHALT SURFACE COURSE, MIX "D", N70	TON	4770	4770							* 78000200	THERMOPLASTIC PAVEMENT MARKING - LINE 4"	FOOT	46246	46246						
42001300	PROTECTIVE COAT	SQ YD	132	132							* 78000400	THERMOPLASTIC PAVEMENT MARKING - LINE 6"	FOOT	1553	1553						
42300400	PORTLAND CEMENT CONCRETE DRIVEWAY PAVEMENT, 8 INCH	SQ YD	34	34							* 78000500	THERMOPLASTIC PAVEMENT MARKING - LINE 8"	FOOT	205	205						
42400200	PORTLAND CEMENT CONCRETE SIDEWALK 5 INCH	SQ FT	109	109							* 78000600	THERMOPLASTIC PAVEMENT MARKING - LINE 12"	FOOT	1056	1056						
44000155	HOT-MIX ASPHALT SURFACE REMOVAL, 1 1/2"	SQ YD	1956	1956							* 78000650	THERMOPLASTIC PAVEMENT MARKING - LINE 24"	FOOT	357	357						
44000158	HOT-MIX ASPHALT SURFACE REMOVAL, 2 1/4"	SQ YD	54828	54828							* 78100100	RAISED REFLECTIVE PAVEMENT MARKER	EACH	868	868						
44000200	DRIVEWAY PAVEMENT REMOVAL	SQ YD	44	44							78300200	RAISED REFLECTIVE PAVEMENT MARKER REMOVAL	EACH	276	276						
44000600	SIDEWALK REMOVAL	SQ FT	109	109							* 88600600	DETECTOR LOOP REPLACEMENT	FOOT	342	342						
44001700	COMBINATION CONCRETE CURB AND GUTTER REMOVAL AND REPLACEMENT	FOOT	384	384							X0322256	TEMPORARY INFORMATION SIGNING	SQ FT	52	52						
<del>44002232</del>	<del>HOT-MIX ASPHALT REMOVAL OVER PATCHES, 8"</del>	<del>SQ YD</del>	<del>6755</del>	<del>6755</del>							X4067107	POLYMERIZED LEVELING BINDER (MACHINE METHOD), IL-4.75, N50	TON	2159	2159						
44201815	CLASS D PATCHES, TYPE II, 14 INCH	SQ YD	1000	1000							XX006806	HOT-MIX ASPHALT DRIVEWAY PAVEMENT	SQ YD	10	10						
44201819	CLASS D PATCHES, TYPE III, 14 INCH	SQ YD	700	700							NP Z0018500	DRAINAGE STRUCTURES TO BE CLEANED	EACH	25	25						
44201821	CLASS D PATCHES, TYPE IV, 14 INCH	SQ YD	500	500							Z0048665	RAILROAD PROTECTIVE LIABILITY INSURANCE	L SUM	1	1						
48102100	AGGREGATE WEDGE SHOULDER, TYPE B	TON	610	610																	
48203021	HOT-MIX ASPHALT SHOULDERS, 6"	SQ YD	123	123																	
NP 55039700	STORM SEWERS TO BE CLEANED	FOOT	500	500																	
60300105	FRAMES AND GRATES TO BE ADJUSTED	EACH	16	16																	
* 63000001	STEEL PLATE BEAM GUARD RAIL, TYPE A, 6 FOOT POSTS	FOOT	400	400																	
* 63100167	TRAFFIC BARRIER TERMINAL, TYPE 1 (SPECIAL) TANGENT	EACH	8	8																	
63200310	GUARDRAIL REMOVAL	FOOT	500	500																	
67000400	ENGINEER'S FIELD OFFICE, TYPE A	CAL MO	3	3																	
67100100	MOBILIZATION	L SUM	1	1																	
70100450	TRAFFIC CONTROL AND PROTECTION, STANDARD 701201	L SUM	1	1																	
70100460	TRAFFIC CONTROL AND PROTECTION, STANDARD 701306	L SUM	1	1																	

NP= NON-PARTICIPATING  
\*Specialty Items

STATE OF ILLINOIS  
DEPARTMENT OF TRANSPORTATION

IL 176 (IL 21 TO ST. MARY'S ROAD)  
SUMMARY OF QUANTITIES

FILE NAME =	USER NAME = bauerl	DESIGNED -	REVISED -	SCALE: NONE	SHEET NO. 4 OF SHEETS	STA.	TO STA.	F.A.U. RTE.	SECTION	COUNTY	TOTAL SHEET
		DRAWN -	REVISED -					1238	(0, 144 & 144x) RS-4	LAKE	25
		CHECKED -	REVISED -					CONTRACT NO. 62661			
		DATE	REVISED -					FED. ROAD DIST. NO. 1 ILLINOIS FED. AID PROJECT			