

SUMMARY OF QUANTITIES			CONSTRUCTION TYPE CODE						SUMMARY OF QUANTITIES			CONSTRUCTION TYPE CODE							
CODE NO	ITEM	UNIT	URBAN 100% FED.						CODE NO	ITEM	UNIT	URBAN 100% FED.							
			TOTAL QUANTITIES	ROADWAY 1000	BRIDGE SFTY-2A							TOTAL QUANTITIES	ROADWAY 1000	BRIDGE SFTY-2A					
31101200	SUB-BASE GRANULAR MATERIAL, TYPE B 4"	SO YD	30		30					60602800	CONCRETE GUTTER, TYPE B	FOOT	6	6					
40600200	BITUMINOUS MATERIALS (PRIME COAT)	TON	22	22						60604400	COMBINATION CONCRETE CURB AND GUTTER, TYPE B-6.18	FOOT	156	156					
40600300	AGGREGATE (PRIME COAT)	TON	106	106						* 63000001	STEEL PLATE BEAM GUARD RAIL, TYPE A, 6 FOOT POSTS	FOOT	500	500					
40600400	MIXTURE FOR CRACKS, JOINTS, AND FLANGWAYS	TON	40	40						* 63100167	TRAFFIC BARRIER TERMINAL, TYPE 1 (SPECIAL) TANGENT	EACH	8	8					
40600895	CONSTRUCTING TEST STRIP	EACH	2	2						63200310	GUARDRAIL REMOVAL	FOOT	500	500					
40600982	HOT-MIX ASPHALT SURFACE REMOVAL - BUTT JOINT	SO YD	186	186						67000400	ENGINEER'S FIELD OFFICE, TYPE A	CAL MO	6	6					
40603340	HOT-MIX ASPHALT SURFACE COURSE, MIX "D", N70	TON	2208	2208						67100100	MOBILIZATION	L SUM	1	1					
42001300	PROTECTIVE COAT	SO YD	34	34						70100450	TRAFFIC CONTROL AND PROTECTION, STANDARD 701201	L SUM	1	1					
42001430	BRIDGE APPROACH PAVEMENT CONNECTOR (FLEXIBLE)	SO YD	50		50					70100460	TRAFFIC CONTROL AND PROTECTION, STANDARD 701306	L SUM	1	1					
44000100	PAVEMENT REMOVAL	SO YD	160	160						70100600	TRAFFIC CONTROL AND PROTECTION, STANDARD 701336	L SUM	1	1					
44000158	HOT-MIX ASPHALT SURFACE REMOVAL, 2 1/4"	SO YD	26276	26276						70102620	TRAFFIC CONTROL AND PROTECTION, STANDARD 701501	L SUM	1	1					
44000400	GUTTER REMOVAL	FOOT	20	20						70300100	SHORT-TERM PAVEMENT MARKING	FOOT	1725	1725					
44000500	COMBINATION CURB AND GUTTER REMOVAL	FOOT	20		20					70300210	TEMPORARY PAVEMENT MARKING - LETTERS AND SYMBOLS	SO FT	432	432					
44000700	APPROACH SLAB REMOVAL	SO YD	120		120					70300220	TEMPORARY PAVEMENT MARKING - LINE 4"	FOOT	20068	20068					
44001700	COMBINATION CONCRETE CURB AND GUTTER REMOVAL AND REPLACEMENT	FOOT	150	150						70300240	TEMPORARY PAVEMENT MARKING - LINE 6"	FOOT	1710	1710					
44201798	CLASS D PATCHES, TYPE I, 13 INCH	SO YD	130	130						70300250	TEMPORARY PAVEMENT MARKING - LINE 8"	FOOT	280	280					
44201803	CLASS D PATCHES, TYPE II, 13 INCH	SO YD	525	525						70300260	TEMPORARY PAVEMENT MARKING - LINE 12"	FOOT	711	711					
44201807	CLASS D PATCHES, TYPE III, 13 INCH	SO YD	265	265						70300280	TEMPORARY PAVEMENT MARKING - LINE 24"	FOOT	318	318					
44201809	CLASS D PATCHES, TYPE IV, 13 INCH	SO YD	400	400						70301000	WORK ZONE PAVEMENT MARKING REMOVAL	SO FT	3640	3640					
48203021	HOT-MIX ASPHALT SHOULDERS, 6"	SO YD	123	123						70400100	TEMPORARY CONCRETE BARRIER	FOOT	400		400				
50102400	CONCRETE REMOVAL	CU YD	10		10					70400200	RELOCATE TEMPORARY CONCRETE BARRIER	FOOT	400		400				
50300225	CONCRETE STRUCTURES	CU YD	25		25					*78000100	THERMOPLASTIC PAVEMENT MARKING - LETTERS AND SYMBOLS	SO FT	432	432					
50300255	CONCRETE SUPERSTRUCTURE	CU YD	114		114					*78000200	THERMOPLASTIC PAVEMENT MARKING - LINE 4"	FOOT	20068	20068					
50300260	BRIDGE DECK GROOVING	SO YD	220		220					*78000400	THERMOPLASTIC PAVEMENT MARKING - LINE 6"	FOOT	1710	1710					
50300300	PROTECTIVE COAT	SO YD	256		256					*78000500	THERMOPLASTIC PAVEMENT MARKING - LINE 8"	FOOT	280	280					
50800205	REINFORCEMENT BARS, EPOXY COATED	POUND	29,540		29,540					*78000600	THERMOPLASTIC PAVEMENT MARKING - LINE 12"	FOOT	711	711					
50800515	BAR SPLICERS	EACH	408		408					*78000650	THERMOPLASTIC PAVEMENT MARKING - LINE 24"	FOOT	318	318					
60255500	MANHOLES TO BE ADJUSTED	EACH	2	2															
60265700	VALVE VAULTS TO BE ADJUSTED	EACH	8	8															
60300105	FRAMES AND GRATES TO BE ADJUSTED	EACH	16	16															
60300310	FRAMES AND LIDS TO BE ADJUSTED (SPECIAL)	EACH	60	60															
60406000	FRAMES AND LIDS, TYPE 1, OPEN LID	EACH	5	5															

**STATE OF ILLINOIS
DEPARTMENT OF TRANSPORTATION**

**IL 176 (IL 21 TO ST. MARY'S ROAD)
SUMMARY OF QUANTITIES**

FILE NAME =	USER NAME = kellers	DESIGNED -	REVISED -	SCALE: SHEET NO. OF SHEETS STA. TO STA.				F.A.U. RTE. 1238	SECTION (0 & 31) RS-7	COUNTY LAKE	TOTAL SHEETS 32	SHEET NO. 3
PLOT SCALE = 500000' / IN.		CHECKED -	REVISED -	CONTRACT NO. 62662				FED. ROAD DIST. NO. 1 ILLINOIS FED. AID PROJECT				
PLOT DATE = 7/2/2009		DATE -	REVISED -									

Rev.