

J000-2A

CODE NO.	ITEM DESCRIPTION	UNIT	URBAN TOTAL QUANTITY	80% FEDERAL 20% STATE					100% ITASCA
				RDWY	BRIDGE	LANDSCAPING	RETAINING WALL	GUARD RAIL	TRAFFIC SIGNAL
				J000-2A	X071-2A				Y031-1F
20100110	TREE REMOVAL (6 TO 15 UNITS DIAMETER)	UNIT	125	125					
20100500	TREE REMOVAL, ACRES	ACRE	2	2					
20101000	TEMPORARY FENCE	FOOT	538	538					
20101200	TREE ROOT PRUNING	EACH	33	33					
20101300	TREE PRUNING (1 TO 10 INCH DIAMETER)	EACH	5	5					
20101350	TREE PRUNING (OVER 10 INCH DIAMETER)	EACH	5	5					
20200100	EARTH EXCAVATION	CU YD	2,498	2,498					
20201200	REMOVAL AND DISPOSAL OF UNSUITABLE MATERIAL	CU YD	2,303	2,303					
20400800	FURNISHED EXCAVATION	CU YD	11,206	11,206					
20600200	GRANULAR EMBANKMENT, SPECIAL	CU YD	117	117					
20700400	POROUS GRANULAR EMBANKMENT, SPECIAL	CU YD	237		237				
20800150	TRENCH BACKFILL	CU YD	659	659					
21001000	GEOTECHNICAL FABRIC FOR GROUND STABILIZATION	SQ YD	700	700					
* 21101615	TOPSOIL FURNISH AND PLACE, 4"	SQ YD	11,852		11,852				
* 25000210	SEEDING, CLASS 2A	ACRE	2		2				
* 25000310	SEEDING, CLASS 4	ACRE	0.4		0.4				
* 25000400	NITROGEN FERTILIZER NUTRIENT	POUND	95		95				
* 25000500	PHOSPHORUS FERTILIZER NUTRIENT	POUND	95		95				
* 25000600	POTASSIUM FERTILIZER NUTRIENT	POUND	95		95				
Δ 25000750	MOWING	ACRE	0.4		0.4				
* 25100630	EROSION CONTROL BLANKET	SQ YD	10,512	10,512					
* 25200110	SODDING, SALT TOLERANT	SQ YD	1,704		1,704				
* 25200200	SUPPLEMENTAL WATERING	UNIT	220		220				
* 25300600	TRANSPLANTED SALVAGED TREES	EACH	2		2				
28000250	TEMPORARY EROSION CONTROL SEEDING	POUND	233	233					
28000300	TEMPORARY DITCH CHECKS	EACH	15	15					
28000400	PERIMETER EROSION BARRIER	FOOT	3,372	3,372					

* SPECIALTY ITEM
Δ Non-participating

REVISIONS	
NAME	DATE

ILLINOIS DEPARTMENT OF TRANSPORTATION
ILLINOIS ROUTE 53 (FAU 2578)

SUMMARY OF QUANTITIES

SCALE: NONE
DATE: 6/12/09
DRAWN BY: CPK
CHECKED BY: JJC