

F.A.U. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
1503	08-00260-01-PV	KANE	176	5
STA. N/A		TO STA. N/A		
FED. ROAD DIST. NO.	ILLINOIS	FED. AID PROJECT		

SPECIALITY ITEMS	SPECIAL PROVISIONS	CODE NO.	PAY ITEM	UNIT	TOTAL QUANTITY	CONSTRUCTION TYPE CODE			
						ROADWAY 1000	LIGHTING Y030-IE	SIGNALS Y031	NON-PART
	*	42400800	DETECTABLE WARNINGS	SQ FT	240	240			
		44000100	PAVEMENT REMOVAL	SQ YD	22,896	22,896			
		44000157	HOT-MIX ASPHALT SURFACE REMOVAL, 2"	SQ YD	7,016	7,016			
	*	44000200	DRIVEWAY PAVEMENT REMOVAL	SQ YD	1,666	1,666			
		44000500	COMBINATION CURB AND GUTTER REMOVAL	FOOT	1,027	1,027			
		44000600	SIDEWALK REMOVAL	SQ FT	2,204	2,204			
	*	44001700	COMBINATION CONCRETE CURB AND GUTTER REMOVAL AND REPLACEMENT	FOOT	74	74			
		44201771	CLASS D PATCH, TYPE IV, 10 INCH	SQ YD	222	222			
	*	44300900	STRIP REFLECTIVE CRACK CONTROL TREATMENT SYSTEM A	FOOT	307	307			
		48100500	AGGREGATE SHOULDERS, TYPE A 6"	SQ YD	25	25			
	*	50105220	PIPE CULVERT REMOVAL	FOOT	419	419			
		50300300	PROTECTIVE COAT	SQ YD	5,046	5,046			
		542C0217	PIPE CULVERTS, CLASS C, TYPE 1 12"	FOOT	171	171			
		542C0232	PIPE CULVERTS, CLASS C, TYPE 1 27"	FOOT	53	53			
	*	55019500	STORM SEWERS, TYPE 1, REINFORCED CONCRETE CULVERT, STORM DRAIN, AND SEWER PIPE, CLASS IV 12"	FOOT	312	312			
	*	55019600	STORM SEWERS, TYPE 1, REINFORCED CONCRETE CULVERT, STORM DRAIN, AND SEWER PIPE, CLASS IV 15"	FOOT	82	82			
	*	55019700	STORM SEWERS, TYPE 1, REINFORCED CONCRETE CULVERT, STORM DRAIN, AND SEWER PIPE, CLASS IV 18"	FOOT	128	128			
	*	55021600	STORM SEWERS, TYPE 2, REINFORCED CONCRETE CULVERT, STORM DRAIN, AND SEWER PIPE, CLASS III 12"	FOOT	1,324	1,324			
	*	55021700	STORM SEWERS, TYPE 2, REINFORCED CONCRETE CULVERT, STORM DRAIN, AND SEWER PIPE, CLASS III 15"	FOOT	27	27			
	*	55021800	STORM SEWERS, TYPE 2, REINFORCED CONCRETE CULVERT, STORM DRAIN, AND SEWER PIPE, CLASS III 18"	FOOT	138	138			
	*	55022000	STORM SEWERS, TYPE 2, REINFORCED CONCRETE CULVERT, STORM DRAIN, AND SEWER PIPE, CLASS III 24"	FOOT	306	306			
	*	55022200	STORM SEWERS, TYPE 2, REINFORCED CONCRETE CULVERT, STORM DRAIN, AND SEWER PIPE, CLASS III 30"	FOOT	541	541			
	*	55022400	STORM SEWERS, TYPE 2, REINFORCED CONCRETE CULVERT, STORM DRAIN, AND SEWER PIPE, CLASS III 36"	FOOT	485	485			
	*	55022700	STORM SEWERS, TYPE 2, REINFORCED CONCRETE CULVERT, STORM DRAIN, AND SEWER PIPE, CLASS III 54"	FOOT	1,734	1,734			
	*	55024100	STORM SEWERS, TYPE 3, REINFORCED CONCRETE CULVERT, STORM DRAIN, AND SEWER PIPE, CLASS IV 24"	FOOT	28	28			
	*	55024500	STORM SEWERS, TYPE 3, REINFORCED CONCRETE CULVERT, STORM DRAIN, AND SEWER PIPE, CLASS IV 36"	FOOT	70	70			
	*	55024800	STORM SEWERS, TYPE 3, REINFORCED CONCRETE CULVERT, STORM DRAIN, AND SEWER PIPE, CLASS IV 54"	FOOT	136	136			
	*	55026200	STORM SEWERS, TYPE 4, REINFORCED SEWER PIPE, CLASS V 24"	FOOT	26	26			
	*	55039700	STORM SEWERS TO BE CLEANED	FOOT	327	327			
		55100500	STORM SEWER REMOVAL 12"	FOOT	980	980			
		55100700	STORM SEWER REMOVAL 15"	FOOT	686	686			
		55100900	STORM SEWER REMOVAL 18"	FOOT	391	391			
		55101200	STORM SEWER REMOVAL 24"	FOOT	64	64			
		55101300	STORM SEWER REMOVAL 27"	FOOT	924	924			
	*	55102000	STORM SEWER REMOVAL 54"	FOOT	12	12			
S	*	56103000	DUCTILE IRON WATER MAIN 6"	FOOT	195	195			
S	*	56103100	DUCTILE IRON WATER MAIN 8"	FOOT	211	211			
S	*	56103300	DUCTILE IRON WATER MAIN 12"	FOOT	183	185			
S	*	56103400	DUCTILE IRON WATER MAIN 16"	FOOT	3,276	3,276			
S	*	56105000	WATER VALVES 8"	EACH	4	4			
S	*	56105200	WATER VALVES 12"	EACH	2	2			
S	*	56105760	BUTTERFLY VALVES 16"	EACH	5	5			
S	*	56400300	FIRE HYDRANTS TO BE ADJUSTED	EACH	2	2			
S	*	56400500	FIRE HYDRANTS TO BE REMOVED	EACH	11	11			
S	*	56400820	FIRE HYDRANT WITH AUXILIARY VALVE AND VALVE BOX	EACH	15	15			
	*	60108100	PIPE UNDERDRAINS 4" (SPECIAL)	FOOT	558	558			

PLOT DATE = 1/9/2009
 FILE NAME = H:\Users\122895\ITP\1\Civil\Shk\SUMQTY.2.dgn
 USER = USER

REVISIONS	
NAME	DATE

ILLINOIS DEPARTMENT OF TRANSPORTATION
 SUMMARY OF QUANTITIES
 SHEET 2 OF 6
 SCALE: VERT. N/A
 DATE 1/7/09
 DRAWN BY TC
 CHECKED BY TC/SBP

