

F.A.U. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
1503	08-00260-01-PV	KANE	176	23
STA. N/A		TO STA. N/A		
FED. ROAD DIST. NO.		ILLINOIS	FED. AID PROJECT	

DRAINAGE NUMBER	TYPE	STATION	OFFSET	LT/RT	RIM ELEVATION	INVERT NORTH	INVERT NORTHEAST	INVERT NORTHWEST	INVERT SOUTH	INVERT SOUTHWEST	INVERT SOUTHEAST	INVERT EAST	INVERT WEST
220	MANHOLES, TYPE A, 6' DIAMETER, TYPE 1 FRAME, CLOSED LID	69+95	6	LT	723.02				717.34			712.45	712.45
221	CATCH BASIN, TY C, TYPE 24 FRAME AND GRATE	69+95	30	RT	722.52	717.52							
222	CATCH BASIN, TY C, TYPE 24 FRAME AND GRATE	70+85	30	LT	721.39				716.39				
223	MANHOLES, TYPE A, 6' DIAMETER, TYPE 1 FRAME, CLOSED LID	70+85	5	LT	721.87	716.26			716.21			711.82	711.82
224	CATCH BASIN, TY C, TYPE 24 FRAME AND GRATE	70+85	30	RT	721.39	716.39							
225	MANHOLE, TYPE A, 6 DIA, TYPE 1 FRAME, CLOSED LID	72+12	70	LT	717.00			709.50		709.50			
226	MANHOLE, TYPE A, 6' DIAMETER, TYPE 24 FRAME AND GRATE	72+05	30	LT	719.12	711.05			711.05				
226A	CATCH BASIN, TYPE A, 6' DIAMETER, TYPE 1 FRAME, CLOSED LID	72+05	52	LT	718.50		711.00		711.00				
227	JUNCTION CHAMBER, TYPE 1 FRAME, CLOSED LID	72+05	5	LT	719.63	711.15			713.89				711.15
228	CATCH BASIN, TYPE A, 4' DIAMETER, TYPE 24 FRAME AND GRATE	72+05	30	RT	719.15	714.07			714.07				
229	INLETS, TYPE A, TYPE 8 GRATE	71+90	39	RT	719.25	714.13							
271	CATCH BASINS, TYPE A, 4' DIAMETER, TYPE 8 GRATE	603+73	22	RT	734.66	726.96						726.96 EXIST	
272	INLETS, TYPE A, TYPE 8 GRATE	604+95	25	LT	735.35				730.96				
273	MANHOLES, TYPE A, 4' DIAMETER, TYPE 8 GRATE	604+67	26	LT	734.36	730.81						730.81	
274	CATCH BASINS, TYPE A, 5' DIAMETER, TYPE 8 GRATE	604+67	23	RT	734.07	726.68			726.68				730.66

NOTES:

1. STORM SEWER STRUCTURES 1-85 LOCATED ALONG INDIAN TRAIL ROAD AND WEST OF CHURCH ROAD, ARE LOCATED OUTSIDE THE LIMITS OF THIS PROJECT.
2. THE OFFSETS TO DRAINAGE STRUCTURES LOCATED IN THE CURB LINE ARE MEASURED TO THE EDGE OF PAVEMENT AND NOT TO THE CENTER OF THE STRUCTURE.
THE OFFSETS TO DRAINAGE STRUCTURES LOCATED WITHIN THE PAYMENT ARE MEASURED TO THE CENTER OF THE STRUCTURE.
THE OFFSETS TO DRAINAGE STRUCTURES LOCATED OUTSIDE THE CURB LINE ARE MEASURED TO THE CENTER OF THE STRUCTURE.
3. ALL MANHOLE COVERS SHALL BE STAMPED WITH "CITY OF AURORA".

PLOT DATE = 1/5/2009
FILE NAME = H:\Aurora\120805\TPH\1\Gvt1\SHA\DRN_SCH.dgn
PLOT SCALE = N/A
USER NAME = USER



Robert H. Anderson & Associates, Inc.
Consulting Engineers & Land Surveyors
License No. 084-029281
Phone No. 630-584-3530

REVISIONS	
NAME	DATE

ILLINOIS DEPARTMENT OF TRANSPORTATION
DRAINAGE SCHEDULE
SHEET 4 OF 4

SCALE: VERT. N/A
DATE 1/7/09
DRAWN BY TC
CHECKED BY TC/SBP