

CODED PAY ITEM NO.	ITEM	UNIT	TOTAL QUANTITY	1000-2A	Y007	Y031-1F	Y030-1E	Y060
				ROADWAY	CULVERT	TRAFFIC SIGNALS	LIGHTING	WATERMAIN
				80% FEDERAL / 20% LOCAL	80% FEDERAL / 20% LOCAL	80% FEDERAL / 20% LOCAL	80% FEDERAL / 20% LOCAL	80% FEDERAL / 20% LOCAL
X	X0325792	WATER METER INSTALLED	EACH	1				1
	X4021000	TEMPORARY ACCESS (PRIVATE ENTRANCE)	EACH	3	3			
	X4022000	TEMPORARY ACCESS (COMMERCIAL ENTRANCE)	EACH	3	3			
	X4023000	TEMPORARY ACCESS (ROAD)	EACH	1	1			
	X4067107	POLYMERIZED LEVELING BINDER (MACHINE METHOD), IL-4.75, N50	TON	882	882			
X	X8050010	SERVICE INSTALLATION, GROUND MOUNTED	EACH	1			1	
X	X8620020	UNINTERRUPTIBLE POWER SUPPLY	EACH	1			1	
X	X8730027	ELECTRIC CABLE IN CONDUIT, GROUNDING, NO. 6 1C	FOOT	1355			1355	
X	X8730250	ELECTRIC CABLE IN CONDUIT, NO. 20 3/C, TWISTED, SHIELDED	FOOT	1344			1344	
X	X8950130	MODIFY EXISTING LIGHTING CONTROLLER	EACH	1			1	
X	XX008150	AERIAL CABLE, 5-1/C NO. 8 WITH MESSENGER WIRE	FOOT	1836			1836	
X	XX008151	TEMPORARY WOOD POLE, 55 FT., CLASS 4, 15 FT. MAST ARM	EACH	18			18	
X	XX008152	TEMPORARY WOOD POLE, 45 FT., CLASS 4	EACH	4			4	
	XX007995	PAVED DITCH REMOVAL	SQ YD	375	375			
	X0326653	PAVED DITCH (SPECIAL)	SQ YD	611	611			
	XX008153	DRILL AND GROUT #3 TIE BARS	EACH	138	138			
X	XX008154	RELOCATE EXISTING RADIO INTERCONNECT SYSTEM	EACH	2			2	
X	XX008155	WATER METER VAULT	EACH	1				1
X	A2008517	TREE, ULMUS JAPONICA X WILSONIANA 'MORTON' (ACCOLADE ELM), 2 1/2" CALIPER, BALLED AND BURLAPPED	EACH	5	5			
X	XX008156	LINE STOPS 10"	EACH	1				1
X	81702110	ELECTRIC CABLE IN CONDUIT, 600V (XLP-TYPE USE) 1/C NO. 10	FOOT	1600			1600	
X	83600200	LIGHT POLE FOUNDATION, 24" DIAMETER	FOOT	2			2	
X	84400105	RELOCATE EXISTING LIGHTING UNIT	EACH	2			2	

X INDICATES SPECIALTY ITEM

REV. 9-4-09

FILE NAME =	USER NAME =	DESIGNED <i>BLG/KRK</i>	REVISED -	STATE OF ILLINOIS DEPARTMENT OF TRANSPORTATION	SUMMARY OF QUANTITIES ESSINGTON ROAD AT HENNEPIN DRIVE AND MALL LOOP DRIVE	F.A.U. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.	
		DRAWN <i>BLG/KRK</i>	REVISED -			0326	06-00130-00-CH	WILL	116	11	
		CHECKED <i>DJK</i>	REVISED -			CONTRACT NO. 63185					
		DATE <i>5-29-09</i>	REVISED -			SCALE: SHEET NO. 8 OF 8 SHEETS		FED. ROAD DIST. NO. 7 ILLINOIS		FED. AID PROJECT M-8003(654)	