

CODED PAY ITEM NO.	ITEM	UNIT	TOTAL QUANTITY	1000-2A	Y007	Y031-1F	Y030-1E	Y060
				ROADWAY	CULVERT	TRAFFIC SIGNALS	LIGHTING	WATERMAIN
				80% FEDERAL / 20% LOCAL	80% FEDERAL / 20% LOCAL	80% FEDERAL / 20% LOCAL	80% FEDERAL / 20% LOCAL	80% FEDERAL / 20% LOCAL
40600982	HOT-MIX ASPHALT SURFACE REMOVAL - BUTT JOINT	SQ YD	148	148				
40603085	HOT-MIX ASPHALT BINDER COURSE, IL-19.0, N70	TON	2322	2322				
40603240	POLYMERIZED HOT-MIX ASPHALT BINDER COURSE, IL-19.0, N90	TON	1604	1604				
40603340	HOT-MIX ASPHALT SURFACE COURSE, MIX "D", N70	TON	1293	1293				
40603595	POLYMERIZED HOT-MIX ASPHALT SURFACE COURSE, MIX "F", N90	TON	774	774				
42001300	PROTECTIVE COAT	SQ YD	5189	5189				
42300710	PORTLAND CEMENT CONCRETE DRIVEWAY PAVEMENT, 6 INCH, SPECIAL	SQ YD	59	59				
42300800	PORTLAND CEMENT CONCRETE DRIVEWAY PAVEMENT, 8 INCH, SPECIAL	SQ YD	312	312				
42400430	PORTLAND CEMENT CONCRETE SIDEWALK 5 INCH, SPECIAL	SQ FT	22244	22244				
42400800	DETECTABLE WARNINGS	SQ FT	186	186				
44000100	PAVEMENT REMOVAL	SQ YD	507	507				
44000157	HOT-MIX ASPHALT SURFACE REMOVAL, 2"	SQ YD	15304	15304				
44000159	HOT-MIX ASPHALT SURFACE REMOVAL, 2 1/2"	SQ YD	1113	1113				
44000198	HOT-MIX ASPHALT SURFACE REMOVAL, VARIABLE DEPTH	SQ YD	1270	1270				
44000200	DRIVEWAY PAVEMENT REMOVAL	SQ YD	495	495				
44000500	COMBINATION CURB AND GUTTER REMOVAL	FOOT	6199	6199				
44000600	SIDEWALK REMOVAL	SQ FT	16807	16807				
44201737	CLASS D PATCHES, TYPE I, 8 INCH	SQ YD	252	252				
44201741	CLASS D PATCHES, TYPE II, 8 INCH	SQ YD	764	764				
44201745	CLASS D PATCHES, TYPE III, 8 INCH	SQ YD	1082	1082				
44201747	CLASS D PATCHES, TYPE IV, 8 INCH	SQ YD	854	854				
50105220	PIPE CULVERT REMOVAL	FOOT	327		327			
51500100	NAME PLATES	EACH	1		1			
54001000	BOX CULVERT END SECTIONS	EACH	2		2			
54010605	PRECAST CONCRETE BOX CULVERT 6' X 5'	FOOT	381		381			
54213657	PRECAST REINFORCED CONCRETE FLARED END SECTIONS 12"	EACH	5	5				
550A0050	STORM SEWERS, CLASS A, TYPE 1 12"	FOOT	286	286				
550A0340	STORM SEWERS, CLASS A, TYPE 2 12"	FOOT	141	141				
550A0450	STORM SEWERS, CLASS A, TYPE 2 36"	FOOT	47	47				
55100500	STORM SEWER REMOVAL 12"	FOOT	335	335				
55101600	STORM SEWER REMOVAL 36"	FOOT	56	56				

X INDICATES SPECIALTY ITEM

FILE NAME =	USER NAME =	DESIGNED <i>BLG/KRK</i>	REVISED -	<b>STATE OF ILLINOIS DEPARTMENT OF TRANSPORTATION</b>	<b>SUMMARY OF QUANTITIES</b>		F.A.U. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
		DRAWN <i>BLG/KRK</i>	REVISED -		ESSINGTON ROAD AT HENNEPIN DRIVE AND MALL LOOP DRIVE		0326	06-00130-00-CH	WILL	116	5
		CHECKED <i>DJK</i>	REVISED -		SCALE:	SHEET NO. 2 OF 8 SHEETS		FED. ROAD DIST. NO. 7   ILLINOIS		CONTRACT NO. 63185	
		DATE <i>5-29-09</i>	REVISED -				FED. AID PROJECT M-8003(654)				