

CODED PAY ITEM NO.	ITEM	UNIT	TOTAL QUANTITY	1000-2A	Y007	Y031-1F	Y030-1E	Y060
				ROADWAY	CULVERT	TRAFFIC SIGNALS	LIGHTING	WATERMAIN
				80% FEDERAL / 20% LOCAL	80% FEDERAL / 20% LOCAL	80% FEDERAL / 20% LOCAL	80% FEDERAL / 20% LOCAL	80% FEDERAL / 20% LOCAL
X	78001180 PAINT PAVEMENT MARKING - LINE 24"	FOOT	35	35				
X	78100100 RAISED REFLECTIVE PAVEMENT MARKER	EACH	259	259				
X	78300100 PAVEMENT MARKING REMOVAL	SQFT	1202	1202				
X	78300200 RAISED REFLECTIVE PAVEMENT MARKER REMOVAL	EACH	40	40				
X	81000600 CONDUIT IN TRENCH, 2" DIA., GALVANIZED STEEL	FOOT	753			753		
X	81000700 CONDUIT IN TRENCH, 2 1/2" DIA., GALVANIZED STEEL	FOOT	262			262		
X	81000800 CONDUIT IN TRENCH, 3" DIA., GALVANIZED STEEL	FOOT	40			40		
X	81001000 CONDUIT IN TRENCH, 4" DIA., GALVANIZED STEEL	FOOT	319			319		
X	81001100 CONDUIT IN TRENCH, 5" DIA., GALVANIZED STEEL	FOOT	53			53		
X	81018500 CONDUIT PUSHED, 2" DIA., GALVANIZED STEEL	FOOT	166			166		
X	81018900 CONDUIT PUSHED, 4" DIA., GALVANIZED STEEL	FOOT	478			478		
X	81019000 CONDUIT PUSHED, 5" DIA., GALVANIZED STEEL	FOOT	103			103		
X	81400100 HANDHOLE	EACH	8			8		
X	81400200 HEAVY-DUTY HANDHOLE	EACH	7			7		
X	81400300 DOUBLE HANDHOLE	EACH	3			3		
X	81800340 AERIAL CABLE, 3-1/C NO. 8 WITH MESSENGER WIRE	FOOT	671				671	
X	81900200 TRENCH AND BACKFILL FOR ELECTRICAL WORK	FOOT	1208			1208		
X	84100110 REMOVAL OF TEMPORARY LIGHTING UNITS	EACH	22				22	
X	84200500 REMOVAL OF EXISTING LIGHTING UNIT, SALVAGE	EACH	4				4	
X	84200600 REMOVAL OF EXISTING LIGHTING UNIT, NO SALVAGE	EACH	11				11	
X	84200700 LIGHTING FOUNDATION REMOVAL	EACH	15				15	
X	84500110 REMOVAL OF LIGHTING CONTROLLER	EACH	1				1	
X	84500120 REMOVAL OF ELECTRIC SERVICE INSTALLATION	EACH	1				1	
X	84500130 REMOVAL OF LIGHTING CONTROLLER FOUNDATION	EACH	1				1	
X	85700205 FULL-ACTUATED CONTROLLER AND TYPE IV CABINET, SPECIAL	EACH	1			1		
X	87301215 ELECTRIC CABLE IN CONDUIT, SIGNAL NO. 14 2C	FOOT	2982			2982		
X	87301225 ELECTRIC CABLE IN CONDUIT, SIGNAL NO. 14 3C	FOOT	1377			1377		
X	87301245 ELECTRIC CABLE IN CONDUIT, SIGNAL NO. 14 5C	FOOT	4082			4082		
X	87301255 ELECTRIC CABLE IN CONDUIT, SIGNAL NO. 14 7C	FOOT	3999			3999		
X	87301305 ELECTRIC CABLE IN CONDUIT, LEAD-IN, NO.14 1 PAIR	FOOT	6129			6129		
X	87301805 ELECTRIC CABLE IN CONDUIT, SERVICE, NO. 6 2C	FOOT	24			24		
X	87502480 TRAFFIC SIGNAL POST, GALVANIZED STEEL, 14 FT.	EACH	2			2		

X INDICATES SPECIALTY ITEM

FILE NAME =	USER NAME =	DESIGNED <i>BLG/KRK</i>	REVISED -	STATE OF ILLINOIS DEPARTMENT OF TRANSPORTATION	SUMMARY OF QUANTITIES		F.A.U. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
		DRAWN <i>BLG/KRK</i>	REVISED -		ESSINGTON ROAD AT HENNEPIN DRIVE AND MALL LOOP DRIVE		0326	06-00130-00-CH	WILL	116	8
		CHECKED <i>DJK</i>	REVISED -		SCALE:	SHEET NO. 5 OF 8 SHEETS	FED. ROAD DIST. NO. 7 ILLINOIS		CONTRACT NO. 63185		
		DATE <i>5-29-09</i>	REVISED -				FED. AID PROJECT M-8003(654)				