

	CODED PAY ITEM NO.	ITEM	UNIT	TOTAL QUANTITY	1000-2A	Y007	Y031-1F	Y030-1E	Y060
					ROADWAY	CULVERT	TRAFFIC SIGNALS	LIGHTING	WATERMAIN
					80% FEDERAL / 20% LOCAL	80% FEDERAL / 20% LOCAL	80% FEDERAL / 20% LOCAL	80% FEDERAL / 20% LOCAL	80% FEDERAL / 20% LOCAL
X	A2000120	TREE, ACER X FREEMANII AUTUMN BLAZE (AUTUMN BLAZE FREEMAN MAPLE), 2 1/2" CALIPER, BALLED AND BURLAPPED	EACH	5	5				
X	A2004820	TREE, GLEDITSIA TRIACANTHOS INERMIS SKYLINE (SKYLINE THORNLESS COMMON HONEYLOCUST), 2 1/2" CALIPER, BALLED AND BURLAPPED	EACH	18	18				
X	B2004120	TREE, MALUS PRAIRIFIRE (PRAIRIFIRE CRABAPPLE), 2 1/2" CALIPER, TREE FORM, BALLED AND BURLAPPED	EACH	6	6				
X	D2000160	EVERGREEN, ABIES CONCOLOR (WHITE FIR), 5' HEIGHT, BALLED AND BURLAPPED	EACH	4	4				
X	K1005481	SHREDDED BARK MULCH 3"	SQ YD	396	396				
	Z0001050	AGGREGATE SUBGRADE 12"	SQ YD	5600	5600				
	Z0022800	FENCE REMOVAL	FOOT	284	284				
Δ	Z0076600	TRAINEES	HOURL	1500	1500				
X	XX001249	ORNAMENTAL FENCE	FOOT	86	86				
X	XX002112	TEMPORARY LUMINAIRE, SODIUM VAPOR, HORIZONTAL MOUNT, 400 WATT	EACH	18				18	
X	XX003661	ELECTRIC CABLE IN CONDUIT, COAXIAL	FOOT	254			254		
X	XX004705	CONNECT TO EXISTING WATER MAIN 10"	EACH	1					1
X	XX004706	CONNECT TO EXISTING WATER MAIN 6"	EACH	1					1
X	XX004972	LINE STOPS 12"	EACH	2					2
X	XX005770	STRUCTURE TO BE ABANDONED	EACH	1					1
X	XX005773	CONNECT TO EXISTING WATER MAIN 12"	EACH	4					4
X	XX005937	L.E.D. INTERNALLY ILLUMINATED STREET NAME SIGN	EACH	6			6		
	XX007567	HOT-MIX ASPHALT DRIVEWAY PAVEMENT, 4"	SQYD	180	180				
X	XX011700	WATER MAIN FITTINGS	POUND	2145					2145
X	X0320772	WATER MAIN REMOVAL 12"	FOOT	51					51
	X0321556	SANITARY MANHOLES TO BE ADJUSTED	EACH	11	11				
	X0322256	TEMPORARY INFORMATION SIGNING	SQFT	115	115				
	X0323381	STORM SEWERS, (WATER MAIN REQUIREMENTS) TYPE 1, 12"	FOOT	80	80				
	X0323426	SEDIMENT CONTROL, DRAINAGE STRUCTURE INLET FILTER CLEANING	EACH	228	228				
X	X0323827	WATER MAIN REMOVAL 10"	FOOT	43					43
	X0323863	STORM SEWERS, (WATER MAIN REQUIREMENTS) TYPE 2, 12"	FOOT	167	167				
X	X0323927	MAINTENANCE OF LIGHTING SYSTEM	EACH	1				1	
	X0323973	SEDIMENT CONTROL, SILT FENCE	FOOT	2861	2861				
	X0323974	SEDIMENT CONTROL, SILT FENCE MAINTENANCE	FOOT	300	300				
X	X0325705	RE-OPTIMIZE TRAFFIC SIGNAL SYSTEM LEVEL 2	EACH	1			1		
X	X0325737	TEMPORARY TRAFFIC SIGNAL TIMING	EACH	1			1		

X INDICATES SPECIALTY ITEM
Δ Y080

FILE NAME =	USER NAME =	DESIGNED <i>BLG/KRK</i>	REVISED -	STATE OF ILLINOIS DEPARTMENT OF TRANSPORTATION	SUMMARY OF QUANTITIES ESSINGTON ROAD AT HENNEPIN DRIVE AND MALL LOOP DRIVE			F.A.U. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
		DRAWN <i>BLG/KRK</i>	REVISED -					0326	06-00130-00-CH	WILL	116	10
PLOT SCALE =	CHECKED <i>DJK</i>	REVISIED -			SCALE:	SHEET NO. 7 OF 8 SHEETS	CONTRACT NO. 63185					
PLOT DATE =	DATE <i>5-29-09</i>	REVISIED -			FED. ROAD DIST. NO. 7 ILLINOIS			FED. AID PROJECT M-8003(654)				