

SUMMARY OF QUANTITIES

ITEM NO.	ITEMS	UNIT	SFTY-18 QUANTITY
20100110	TREE REMOVAL (6 TO 15 UNITS DIAMETER)	UNIT	82
*20101200	TREE ROOT PRUNING	EACH	5
20200100	EARTH EXCAVATION	CU YD	880
20201200	REMOVAL AND DISPOSAL OF UNSUITABLE MATERIAL	CU YD	35
20700420	POROUS GRANULAR EMBANKMENT, SUBGRADE	CU YD	35
20800250	TRENCH BACKFILL, SPECIAL	CU YD	14
*21101615	TOPSOIL FURNISH AND PLACE, 4"	SQ YD	477
*25000400	NITROGEN FERTILIZER NUTRIENT	POUND	78
*25000500	PHOSPHORUS FERTILIZER NUTRIENT	POUND	78
*25000600	POTASSIUM FERTILIZER NUTRIENT	POUND	78
*25200110	SODDING, SALT TOLERANT	SQ YD	4222
*25200200	SUPPLEMENTAL WATERING	UNIT	20
35101800	AGGREGATE BASE COURSE, TYPE B 6"	SQ YD	444
40201000	AGGREGATE FOR TEMPORARY ACCESS	TON	20
40603310	HOT-MIX ASPHALT SURFACE COURSE, MIX "C", N50	TON	77
42300300	PORTLAND CEMENT CONCRETE DRIVEWAY PAVEMENT, 7 INCH	SQ YD	64
42400430	PORTLAND CEMENT CONCRETE SIDEWALK 5 INCH, SPECIAL	SQ FT	18500
42400800	DETECTABLE WARNINGS	SQ FT	240
44000200	DRIVEWAY PAVEMENT REMOVAL	SQ YD	790
44000600	SIDEWALK REMOVAL	SQ FT	1565
44001700	COMBINATION CONCRETE CURB AND GUTTER REMOVAL AND REPLACEMENT	FOOT	326
*56103000	DUCTILE IRON WATER MAIN, 6"	FOOT	10
*56400500	FIRE HYDRANTS TO BE REMOVED	EACH	1
*56400820	FIRE HYDRANT WITH AUXILIARY VALVE AND VALVE BOX	EACH	1
70102620	TRAFFIC CONTROL AND PROTECTION, STANDARD 701501	L.SUM	1
70102640	TRAFFIC CONTROL AND PROTECTION, STANDARD 701801	L.SUM	1
*78000400	THERMOPLASTIC PAVEMENT MARKING - LINE 6"	FOOT	1300
*B2006116	TREE, SYRINGA PEKINENSIS MORTON (CHINA SNOW PEKING LILAC), 2" CALIPER, TREE FORM, BALLED AND BURLAPPED	EACH	6
Z0013798	CONSTRUCTION LAYOUT	L.SUM	1
XX002258	STRUCTURES TO BE ADJUSTED	EACH	5
XX003535	AGGREGATE BASE COURSE, TYPE B 2"	SQ YD	733
*XX011700	WATER MAIN FITTINGS	POUND	550
167100100	MOBILIZATION	L.SUM	1

*INDICATES SPECIALTY ITEM