

EARTHWORK QUANTITIES											
STATION	DISTANCE	EARTH EXCAVATION	EMBANKMENT	UNSUITABLE MATERIAL	SUB-BASE GRANULAR MATERIAL, TYPE C	EARTH EXCAVATION	EARTH EXCAVATION (ADJ. FOR SHRINKAGE)	EMBANKMENT	EARTHWORK BALANCE WASTE (+) OR SHORTAGE (-)	REMOVAL & DISPOSAL OF UNSUITABLE MATERIALS	SUB-BASE GRANULAR MATERIAL, TYPE C
(XXX+XX)	(FT.)	(SQ. FT.)	(SQ. FT.)	(SQ. FT.)	(SQ. FT.)	(CU. YD.)	(CU. YD.)	(CU. YD.)	(CU. YD.)	(CU. YD.)	(CU. YD.)
REED ROAD											
402+00		31.1	0.0	0.0	0.0						
	15					17.4	14.8	0.0	14.8	0.0	0.0
402+15		31.7	0.0	0.0	0.0						
	35					40.6	34.5	1.5	33.0	0.0	0.2
402+50		30.9	2.3	0.0	0.3						
	50					51.8	44.0	8.7	35.3	0.0	1.1
403+00		25.0	7.1	0.0	0.9						
	50					41.3	35.1	19.1	16.0	0.0	1.9
403+50		19.6	13.6	0.0	1.2						
	50					33.6	28.6	28.1	0.5	0.0	2.6
404+00		16.6	16.8	0.0	1.6						
	50					27.7	23.5	41.7	-18.1	0.0	3.0
404+50		13.3	28.2	0.0	1.6						
	50					21.1	17.9	49.2	-31.3	0.0	3.1
405+00		9.5	24.9	0.0	1.7						
	50					17.5	14.9	35.7	-20.9	0.0	2.4
405+50		9.4	13.7	0.0	0.9						
	18					6.4	5.5	4.6	0.9	0.0	0.3
405+68		9.9	9.5	0.0	0.0						
	32					12.5	10.6	5.6	5.0	0.0	0.6
406+00		11.2	11.3	0.0	1.0						
	50					19.9	16.9	10.5	6.5	0.0	1.9
406+50		10.2	14.7	0.0	1.1						
	50					21.4	18.2	13.6	4.6	0.0	2.0
407+00		12.9	17.2	0.0	1.1						
	50					25.0	21.3	15.9	5.4	0.0	2.2
407+50		14.1	18.2	0.0	1.3						
	50					23.9	20.3	16.8	3.5	0.0	2.3
408+00		11.7	21.3	0.0	1.2						
	50					18.9	16.1	19.7	-3.7	0.0	2.1
408+50		8.8	22.0	0.0	1.1						
	50					14.3	12.2	20.4	-8.2	0.0	1.9
409+00		6.7	23.0	0.0	0.9						
	50					11.2	9.5	21.3	-11.7	0.0	1.9
409+50		5.4	25.1	0.0	1.1						
	50					15.8	13.4	23.2	-9.8	0.0	2.3
410+00		11.6	27.0	0.0	1.3						
	50					28.9	24.5	25.0	-0.4	0.0	2.4
410+50		19.6	25.1	0.0	1.2						
	50					38.2	32.5	23.3	9.2	0.0	2.2
411+00		21.7	19.7	0.0	1.1						
	50					35.7	30.4	18.2	12.1	0.0	1.9
411+50		16.9	19.1	0.0	0.9						
	50					28.0	23.8	17.7	6.1	0.0	1.7
412+00		13.4	22.6	0.0	0.9						
	50					25.0	21.3	20.9	0.3	0.0	1.5
412+50		13.6	21.3	0.0	0.8						
	50					24.6	20.9	19.7	1.2	0.0	1.5
413+00		12.9	20.5	0.0	0.9						
	50					25.0	21.2	19.0	2.2	0.0	1.5
413+50		14.1	21.0	0.0	0.8						
	50					28.5	24.2	19.4	4.8	0.0	0.7

EARTHWORK QUANTITIES											
STATION	DISTANCE	EARTH EXCAVATION	EMBANKMENT	UNSUITABLE MATERIAL	SUB-BASE GRANULAR MATERIAL, TYPE C	EARTH EXCAVATION	EARTH EXCAVATION (ADJ. FOR SHRINKAGE)	EMBANKMENT	EARTHWORK BALANCE WASTE (+) OR SHORTAGE (-)	REMOVAL & DISPOSAL OF UNSUITABLE MATERIALS	SUB-BASE GRANULAR MATERIAL, TYPE C
(XXX+XX)	(FT.)	(SQ. FT.)	(SQ. FT.)	(SQ. FT.)	(SQ. FT.)	(CU. YD.)	(CU. YD.)	(CU. YD.)	(CU. YD.)	(CU. YD.)	(CU. YD.)
REED ROAD											
414+00		16.7	15.7	0.0	0.9						
	50					34.1	29.0	14.5	14.5	0.0	1.6
414+50		20.1	15.7	0.0	0.9						
	50					34.7	29.5	14.6	14.9	0.0	1.6
415+00		17.3	15.1	0.0	0.9						
	50					37.4	31.8	14.0	17.8	0.0	1.6
415+50		23.1	17.0	0.0	0.9						
	50					47.8	40.6	15.7	24.9	0.0	1.6
416+00		28.5	18.0	0.0	0.9						
	50					44.8	38.1	16.7	21.4	0.0	1.7
416+50		19.9	25.7	0.0	0.9						
	50					47.6	40.5	23.8	16.6	0.0	0.9
417+00		31.6	28.7	0.0	0.0						
	50					57.7	49.0	26.6	22.4	37.2	0.0
417+50		30.7	25.0	40.2	0.0						
	50					81.0	68.9	23.2	45.7	95.9	0.0
418+00		56.8	22.0	63.3	0.0						
	18					50.8	43.2	7.3	35.9	47.0	0.0
418+18		95.7	19.8	77.5	0.0						
	32					80.3	68.3	11.7	56.6	71.3	0.0
418+50		39.9	21.5	42.9	0.0						
	50					70.5	59.9	19.9	40.0	76.9	0.0
419+00		36.2	21.1	40.2	0.0						
	50					45.8	38.9	19.6	19.3	47.8	0.7
419+50		13.2	22.4	11.4	0.7						
	50					28.4	24.2	20.7	3.5	21.1	1.5
420+00		17.5	20.6	11.4	0.9						
	50					31.1	26.4	19.1	7.3	21.1	1.7
420+50		16.1	17.8	11.4	1.0						
	50					30.9	26.3	16.5	9.8	10.6	1.9
421+00		17.3	18.0	0.0	1.1						
	50					41.2	35.0	16.7	18.3	0.0	1.9
421+50		27.1	14.4	0.0	1.0						
	50					60.2	51.2	13.3	37.8	0.0	1.8
422+00		37.9	10.9	0.0	1.0						
	50					76.1	64.6	10.1	54.5	0.0	1.8
422+50		44.3	10.6	0.0	1.0						
	50					77.7	66.0	9.8	56.2	0.0	1.7
423+00		39.6	8.9	0.0	0.9						
	50					61.1	51.9	8.2	43.7	0.0	1.8
423+50		26.3	9.5	0.0	1.0						
	50					39.3	33.4	8.8	24.6	5.2	1.9
424+00		16.1	9.1	5.6	1.1						
	50					21.3	18.1	8.5	9.6	10.2	2.1
424+50		6.9	10.2	5.5	1.2						
	50					12.4	10.6	9.5	1.1	10.1	2.3
425+00		6.5	13.0	5.4	1.3						
	50					16.0	13.6	12.1	1.6	9.8	2.1
425+50		10.8	9.4	5.2	1.0						
	50					18.8	16.0	8.7	7.3	8.6	1.3
426+00		9.6	5.1	4.1	0.4						
	33					8.0	6.8	3.1	3.7	3.2	0.3
426+33		3.5	0.0	1.1	0.0						

TOTAL REED ROAD (CU. YD.)

EARTH EXCAVATION 20200100	1792	1538	872	+666	REMOVAL AND DISPOSAL OF UNSUITABLE MATERIALS	SUB-BASE GRANULAR MATERIAL, TYPE C
					20201200	31102000