



F.A.U. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
1680	05-00038-00-PV	KANE/KENDALL	130	15
STA.	TO STA.			
FED. ROAD DIST. NO. _	ILLINOIS	FED. AID PROJECT		

PAVEMENT QUANTITIES SCHEDULE

STATION	STATION	L	PAVT W	ADD. PAVT A	TOTAL PAVT A	SHLD W	ADD. SHLD A	SHLD A	PAVED SHLDR REM SY	PVT. REM. SY	COMB. C&G REM. FT	HMA SURF REM. 1.5" SY	HMA SURF REM. 2" SY	HMA SURF REM. VAR. DEPTH SY	HMA SURF REM. BUTT JOINT SY	CLASS D PATCH, TYPE II, 7 INCH SY	CLASS D PATCH, TYPE III, 7 INCH SY	CLASS D PATCH, TYPE IV, 7 INCH SY	CLASS D PATCH, TYPE IV, 9 INCH SY	AGG. SUBGR. 12" SY	COMB CC&G TY B-6.12 FT	BIT. MATL. PR. CT GAL	AGG. PR. CT TON	STRIP REFL. CRACK CONT. FT	LEVEL BIND (MM), N70 TON	ADDIT. LEVEL BIND (MM), N70 TON	HMA SURF CSE, MIX D, N50 TON	HMA SURF CSE, MIX D, N70 TON	HMA FULL DEPTH, 4.25" SQ YD	HMA BASE CSE, 6.75" SQ YD	HMA BASE CSE, 7.5" SQ YD	POLY HMA BIND CSE, N90 TON	POLY HMA SURF CSE, N90 TON	HMA FULL DEPTH, PVT. 10" SQ YD	HMA SHLDRS 8" SQ YD																										
BASELINE ROAD																																																													
200024.00	200400.00	376.00	28	48	1218															1475.1	772.0	731	2													1217.8																									
200400.00	200850.00	450.00	28		1400															1700.0	900.0	840	3													1400.0																									
200850.00	201250.00	400.00	28		1244															1464.4	660.0	747	2													1244.4																									
201250.00	201460.66	210.66	28		655															846.1	572.0	393	1													655.4																									
BASELINE EXTENSION																																																													
BASELINE / BASELINE EXTENSION INTERSE					655																									700.0	135.0	393	1																		655.0										
EXISTING BASELINE ROAD (OVERLAY ONLY)																																																													
EXISTING BASELINE ROAD					1280																											358.0		942.0		290.0		116.0				128	3																		143.4
HORSEMEN TRAIL																																																													
414.23	800.00	385.77	6		257							8.0	36.0						20.0		385.8	385.8	129												257.2																										
414.23	800.00	385.77	5		214							18.0		352.0				18.0			342.9	385.8	107													214.3																									
800.00	1250.00	450.00	2		100							82.0	44.0		154.0	8.0		138.0			243.3	430.0	50													100.0																									
800.00	1250.00	450.00	11		550											14.0		43.0			673.3	370.0	275													550.0																									
1250.00	1500.00	250.00	2		56							60.0	20.0		190.0			17.0			138.9	250.0	28													55.6																									
1250.00	1483.00	233.00	11.5		298								18.0								381.1	250.0	149													297.7																									
OVERLAY (ON EXISTING ROAD AND WIDENING)																																																													
414.23	800.00	385.77	36	94	1637																	164	3			91.7	98.8									137.5																									
800.00	1250.00	450.00	36	105	1905																	191	4			106.7	102.8									160.0																									
1250.00	1500.00	250.00	36	2	1002																	100	2			56.1	52.4									84.2																									
CATERPILLAR DRIVE																																																													
REMOVAL ITEMS, PATCHING & MISC. ITEMS																																																													
300060.00	300900.00	840.00	24		2240					735.0		85.0	2240.0									693.0														693.0																									
300900.00	300975.00	75.00	26.25		219																	218.8														218.8																									
300975.00	301042.95	82.95	24		221																															221.2																									
301042.95	300975.00	832.05	33		3051																															3050.8																									
WIDENING AREA - TRAVEL LANE																																																													
300062.98	300220.00	157.02	12		209																																																								
300220.00	300505.00	285.00	12		380																																																								
300505.00	300920.00	330.00	8		293																																																								
300920.00	300142.95	81.95	4		36																																																								
WIDENING AREA - PAVED SHOULDER																																																													
300062.98	300220.00	157.02				4		69.79																													69.8																								
300220.00	300515.00	295.00				4		131.1																													131.1																								
300515.00	300880.00	285.00				6		190																													190.0																								
300880.00	300142.95	81.95				4		36.42																												36.4																									
OVERLAY (ON EXISTING ROAD AND WIDENING)																																																													
300060.00	300220.00	160.00	73	379.7	1677																																																								
300220.00	300610.00	390.00	73		3163																																																								
300610.00	301005.58	395.58	67	283.3	3228																																																								
301005.58	300060.00				707																																																								
ORCHARD ROAD																																																													
8027.75	8065.00	37.25	4		17																																																								
8065.00	8227.75	162.75	8		145																																																								
8227.75	8435.00	207.25	12	76	352																																																								
8435.00	8652.74	115.00	4	12	63																																																								
WIDENING AREA - PAVED SHOULDER																																																													
8027.75	8435.00	407.25				4	21.11	202.1	464.0																												202.1																								
8435.00	8652.74	115.00				4	8.22	59.33	138.0																												59.3																								
CANNONBALL TRAIL																																																													
783.67	976.08	192.41	22	25	495																																																								
										572.0											100.0											428.1	297	1											495.3																
TOTALS																																																													
									1,337	1,098	203	5,731	942	352	1,645	22	55	297	200	10,428	5,251	6,475	41	3,985	798	255	144	1,257	496	1,475	710	602	247	297	5,173	689																									

PLAN	SURVEYED	DATE
NOTE BOOK	PLOTTED	BY
NO.	BY	
	DATE	
	BY	
	DATE	
	BY	
	DATE	

PROFILE	SURVEYED	DATE
NOTE BOOK	PLOTTED	BY
NO.	BY	
	DATE	
	BY	
	DATE	
	BY	
	DATE	

REVISIONS		ILLINOIS DEPARTMENT OF TRANSPORTATION
NAME	DATE	
SCALE:		DRAWN BY: KKP
DATE: 03-26-09		
		CHECKED BY: TVW

PAVEMENT SCHEDULE