

SPECIAL PROVISION	PAY ITEM NUMBER	DESCRIPTION	UNIT	QUANTITY
△	81000700	CONDUIT IN TRENCH, 2-1/2" DIA., GALVANIZED STEEL	FOOT	61
△	81000800	CONDUIT IN TRENCH, 3" DIA., GALVANIZED STEEL	FOOT	54
△	81001000	CONDUIT IN TRENCH, 4" DIA., GALVANIZED STEEL	FOOT	23
△	81001100	CONDUIT IN TRENCH, 5" DIA., GALVANIZED STEEL	FOOT	20
△	81018500	CONDUIT PUSHED, 2" DIA., GALVANIZED STEEL	FOOT	710
△	81018700	CONDUIT PUSHED, 3" DIA., GALVANIZED STEEL	FOOT	35
△	81018900	CONDUIT PUSHED, 4" DIA., GALVANIZED STEEL	FOOT	539
△	81019000	CONDUIT PUSHED, 5" DIA., GALVANIZED STEEL	FOOT	95
△	81400100	HANDHOLE	EACH	14
△	81400300	DOUBLE HANDHOLE	EACH	2
△	81700215	ELECTRIC CABLE IN CONDUIT, 600 V (EPR-TYPE RHW) 2-1/C NO. 10	FOOT	1,071
• △	82103250	LUMINAIRE, SODIUM VAPOR, HORIZONTAL MOUNT, PHOTO-CELL CONTROL, 250 WATT	EACH	5
△	84200700	LIGHTING FOUNDATION REMOVAL	EACH	1
• △	85700205	FULL-ACTUATED CONTROLLER AND TYPE IV CABINET, SPECIAL	EACH	2
• △	86400100	TRANSCEIVER - FIBER OPTIC	EACH	2
• △	87301215	ELECTRIC CABLE IN CONDUIT, SIGNAL NO. 14 2C	FOOT	2,455
• △	87301225	ELECTRIC CABLE IN CONDUIT, SIGNAL NO. 14 3C	FOOT	2,315
• △	87301245	ELECTRIC CABLE IN CONDUIT, SIGNAL NO. 14 5C	FOOT	1,915
• △	87301255	ELECTRIC CABLE IN CONDUIT, SIGNAL NO. 14 7C	FOOT	2,311
• △	87301805	ELECTRIC CABLE IN CONDUIT, SERVICE, NO. 6 2C	FOOT	62
• △	87704100	STEEL COMBINATION MAST ARM ASSEMBLY AND POLE 34 FT. (SPECIAL)	EACH	2
• △	87704110	STEEL COMBINATION MAST ARM ASSEMBLY AND POLE 36 FT. (SPECIAL)	EACH	2
• △	87704140	STEEL COMBINATION MAST ARM ASSEMBLY AND POLE 42 FT (SPECIAL)	EACH	1
• △	87800100	CONCRETE FOUNDATION, TYPE A	FOOT	20
• △	87800200	CONCRETE FOUNDATION, TYPE D	FOOT	8
• △	87800400	CONCRETE FOUNDATION, TYPE E 30-INCH DIAMETER	FOOT	10
• △	87800415	CONCRETE FOUNDATION, TYPE E 36-INCH DIAMETER	FOOT	61
△	87900200	DRILL EXISTING HANDHOLE	EACH	2
• △	88030020	SIGNAL HEAD, LED, 1-FACE, 3-SECTION, MAST-ARM MOUNTED	EACH	7
• △	88030050	SIGNAL HEAD, LED, 1-FACE, 3-SECTION, BRACKET MOUNTED	EACH	3
• △	88030070	SIGNAL HEAD, LED, 1-FACE, 4-SECTION, BRACKET MOUNTED	EACH	2
• △	88030080	SIGNAL HEAD, LED, 1-FACE, 4-SECTION, MAST-ARM MOUNTED	EACH	3
• △	88030100	SIGNAL HEAD, LED, 1-FACE, 5-SECTION, BRACKET MOUNTED	EACH	3
• △	88030110	SIGNAL HEAD, LED, 1-FACE, 5-SECTION, MAST-ARM MOUNTED	EACH	5
• △	88102717	PEDESTRIAN SIGNAL HEAD, LED, 1-FACE, BRACKET MOUNTED WITH COUNTDOWN TIMER	EACH	8

FILE NAME = I:\Lakeco\0822401\dr-an\sheet5\500_05.dgn

CMT © Copyright CMT, Inc.
CRAWFORD, MURPHY & TILLY, INC.
CONSULTING ENGINEERS
License No. 184-00063

USER NAME = Steve Prange
PLOT SCALE = 1:8000' / IN.
PLOT DATE = 05/29/09

DESIGNED - SJP
DRAWN - SJP
CHECKED - KDN
DATE - 05/29/09

REVISED -
REVISED -
REVISED -
REVISED -



SUMMARY OF QUANTITIES				
SCALE:	SHEET NO.	OF	SHEETS	STA. TO STA.

F.A. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
1016	02-00110-12-WR	LAKE	206	7
CONTRACT NO. 63209				
FED. ROAD DIST. NO. 1 ILLINOIS FED. AID PROJECT				