

10. SCHEDULE OF AGGREGATE AND RELATED ITEMS

FROM	TO	LT OR RT	21001000 GEOTECH FAB F/GR STAB SQ YD				35100500 AGG BASE CSE A 6 SQ YD			Z0001050 AGG SUBGRADE 12 SQ YD		
			PAVEMENT AREA	MEDIAN AREA	CURB AREA	PAVEMENT/MEDIAN EDGE (1')	MULTI-USE PATH	MEDIAN/SHOULDER	DRIVEWAYS	PAVEMENT AREA	CURB AREA (4.58')	MEDIAN AREA (3.42')
WASHINGTON STREET												
131+00	137+00	LT	9155		1363	298	3051	178	438	8497	1396	
		RT	8932		1363	298		1183		8497	1396	
137+00	143+00	LT	25107		2822	616	5016			24672	2857	
		RT	18007		2748	600		2310	628	17569	2782	
143+00	149+00	LT	20823		2749	600	6252			20385	2782	
		RT	18007		2748	600		2393		17561	2782	
149+00	155+00	LT	17988		2743	599	6242			17550	2781	
		RT	18024		2753	601		2380	724	17586	2781	
155+00	161+00	LT	17609	319	2753	694	6852	453		17171	2780	319
		RT	17586	319	2743	692		3014	846	17148	2780	319
161+00	167+00	LT	17766	621	2748	782	7626	906	190	17330	2782	621
		RT	17767	621	2748	782		3424	791	17329	2781	621
167+00	173+00	LT	19195		2750	600	6259			18603	2783	
		RT	19220		2748	600		2354	1237	18772	2781	
173+00	179+00	LT	23274	1221	2952	1002	5283	2286		22354	2985	1221
		RT	16288	1222	2739	955		4574	1387	15850	2778	1222
179+00	10+00	LT	2417	245	329	144	1002	3100		2076	364	245
		RT	2417	244	449	169		2603	554	2004	483	244
TRI-STATE PARKWAY												
16+00	20+00	LT	2563		59	13				2111	92	
		RT	2533		59	13				1047	92	
TOTAL SQUARE FEET			294678	4813	42365	10658	47583	31158	6795	284112	43038	4813
TOTAL SQUARE YARDS			32742	535	4707	1184	5287	3461	755	31568	4782	535
TOTALS					39168			9503			37990	

11. SCHEDULE OF PIPE UNDERDRAINS

FROM	TO	60107800 PIPE UNDERDRAINS 8 FOOT		X6013600 PIPE UNDERDRAIN 4 MOD FOOT	
		WASHINGTON STREET			
130+00	140+00				1210
140+00	152+00				2368
152+00	164+00				2333
164+00	176+00	143			1924
176+00	10+00				789
TOTALS		143			8624

FILE NAME = L:\LAKECO\0822401\Draw\Sheets\SCDL_05.dgn



USER NAME = Jeff Sedg
 DESIGNED - SJP
 DRAWN - SJP
 PLOT SCALE = 1.0000" = 1" IN.
 CHECKED - KDN
 PLOT DATE = 05/29/09
 REVISIONS:
 REVISIONS -
 REVISIONS -
 REVISIONS -
 REVISIONS -



SCHEDULE OF QUANTITIES

SCALE: SHEET NO. 5 OF 10 SHEETS STA. TO STA.

F.A. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
1016	02-00110-12-WR	LAKE	206	14
FED. ROAD DIST. NO. 1 ILLINOIS FED. AID PROJECT			CONTRACT NO. 63209	