


12. SCHEDULE OF DRAINAGE REMOVAL AND ADJUSTMENT ITEMS

FROM	TO	44004000 PAVED DITCH REMOVAL FOOT	55039700 SS CLEANED FOOT	50104400 CONC HDWL REM EACH	50105220 PIPE CULVERT REMOV FOOT	56400300 FIRE HYDNITS TO BE ADJ EACH	56400800 FIRE HYDNT & VAL MVD EACH	60255500 MAN ADJUST EACH	60260100 INLETS ADJUST EACH	60265700 VV ADJUST EACH	60266100 VV RECONST EACH
WASHINGTON STREET											
131+00	137+00				82		1				1
137+00	143+00				44						2
143+00	149+00				211	2					
149+00	155+00				323						
155+00	161+00			2	364		1			1	
156+85	156+85				66						
161+00	167+00			1	458		1				1
167+00	173+00				213	2					
173+00	179+00	45			15	1		1	2		2
179+00	10+00		100								
TRI-STATE PARKWAY											
16+00	20+00										
TOTALS		45	100	3	1776	5	3	1	2	1	6

12. SCHEDULE OF DRAINAGE REMOVAL AND ADJUSTMENT ITEMS CONTINUED

FROM	TO	60300205 FR & GRATES ADJUST SP EACH	60500060 REMOV INLETS EACH	X0321556 SANITARY MANHOLE ADJ EACH	60260050 SAN MAN RECONST EACH	LC600000 DRAIN STR TO BE CL&GR EACH	XX003503 FLARED END SEC REM EACH
WASHINGTON STREET							
131+00	137+00		1				
137+00	143+00						
143+00	149+00		4				
149+00	155+00		4	1	1		
155+00	161+00		1		1		1
161+00	167+00		6		1		
167+00	173+00		3				
173+00	179+00	1	3			1	
179+00	10+00	6				15	
TRI-STATE PARKWAY							
16+00	20+00	2				2	
TOTALS		9	22	1	3	18	1

FILE NAME = L:\LAKC\CD\022240\Drawn\Sheeta\SED_L06.dgn



USER NAME = Monica Crimon	DESIGNED - SJP	REVISED -
	DRAWN - SJP	REVISED -
PLOT SCALE = 1/8" = 1' IN.	CHECKED - KDN	REVISED -
PLOT DATE = 07/15/09	DATE - 07/15/09	REVISED -



SCHEDULE OF QUANTITIES

SCALE: SHEET NO. 6 OF 10 SHEETS STA. TO STA.

F.A. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
1016	02-00110-12-WR	LAKE	206	15
CONTRACT NO. 63209				
FED. ROAD DIST. NO. 1 ILLINOIS FED. AID PROJECT				