

SUMMARY OF QUANTITIES

LOCATION OF WORK		STP - TCM					
		WOLF RD. 80% FED 20% LOCAL	WOLF RD. 100% LOCAL	WOLF RD. 80% FED 20% LOCAL	WOLF RD. 80% FED 20% LOCAL		
FUNDING SOURCE		STP	LOCAL	STP	STP		
SUMMARY OF QUANTITIES		CONSTRUCTION TYPE CODE					
ITEM #	ITEM	UNIT	TOTAL QUANTITIES	I000-2A	SFTY-1B	Y031-1F	Y030-1E
20101100	TREE TRUNK PROTECTION	EACH	4	4	0	0	0
20800250	TRENCH BACKFILL, SPECIAL	CU YD	30	30	0	0	0
25200110	SODDING, SALT TOLERANT	SQ YD	350	350	0	0	0
25200200	SUPPLEMENTAL WATERING	UNIT	30	30	0	0	0
29000510	INLET FILTERS	EACH	6	6	0	0	0
31101100	SUB-BASE GRANULAR MATERIAL, TYPE B	CU YD	450	448	2	0	0
35102200	AGGREGATE BASE COURSE, TYPE B 10"	SQ YD	75	75	0	0	0
35300500	PORTLAND CEMENT CONCRETE BASE COURSE 10"	SQ YD	500	490	10	0	0
40201000	AGGREGATE FOR TEMPORARY ACCESS	TON	75	75	0	0	0
40600100	BITUMINOUS MATERIALS (PRIME COAT)	GAL	55	55	0	0	0
40600300	AGGREGATE (PRIME COAT)	TON	1	1	0	0	0
40603085	HOT-MIX ASPHALT BINDER COURSE, IL-19.0, N70	TON	90	88	2	0	0
40603340	HOT-MIX ASPHALT SURFACE COURSE, MIX "D", N70	TON	60	59	1	0	0
42300200	PORTLAND CEMENT CONCRETE DRIVEWAY PAVEMENT, 6 INCH	SQ YD	30	30	0	0	0
42400200	PORTLAND CEMENT CONCRETE SIDEWALK, 5 INCH	SQ FT	3800	3605	195	0	0
42400400	PORTLAND CEMENT CONCRETE SIDEWALK, 7 INCH	SQ FT	150	150	0	0	0
42400800	DETECTABLE WARNINGS	SQ FT	110	110	0	0	0
44000100	PAVEMENT REMOVAL	SQ YD	850	850	0	0	0
44000200	DRIVEWAY PAVEMENT REMOVAL	SQ YD	75	65	10	0	0
44000500	COMBINATION CURB AND GUTTER REMOVAL	FOOT	825	825	0	0	0
44000600	SIDEWALK REMOVAL	SQ FT	4250	4250	0	0	0
50300225	CONCRETE STRUCTURES	CU YD	1.25	1.25	0	0	0
50800105	REINFORCEMENT BARS	POUND	44	44	0	0	0
50901765	PIPE HANDRAIL, SPECIAL	FOOT	27	27	0	0	0
550A0040	STORM SEWERS, CLASS A, TYPE 1, 10"	FOOT	20	20	0	0	0
550B0040	STORM SEWERS, TYPE 1, R.C.C.P., CLASS IV 12"	FOOT	55	55	0	0	0
55100400	STORM SEWER REMOVAL 10"	FOOT	26	26	0	0	0
55100500	STORM SEWER REMOVAL 12"	FOOT	30	30	0	0	0
55101600	STORM SEWER REMOVAL 36"	FOOT	5	5	0	0	0
60206905	CATCH BASINS, TYPE C, TYPE 1 FRAME, OPEN LID	EACH	5	5	0	0	0
60221100	MANHOLES, TYPE A, 5'-DIAMETER, TYPE 1 FRAME CLOSED LID	EACH	1	1	0	0	0
60260050	SANITARY MANHOLES TO BE RECONSTRUCTED	EACH	1	1	0	0	0
60266600	WATER VALVE BOXES TO BE ADJUSTED	EACH	1	1	0	0	0
60602800	CONCRETE GUTTER, TYPE B	FOOT	234	234	0	0	0
60603800	COMBINATION CONCRETE CURB AND GUTTER, TYPE B-6.12	FOOT	650	650	0	0	0
60619600	CONCRETE MEDIAN, TYPE SB-6.12	SQ FT	105	105	0	0	0
67100100	MOBILIZATION	L. SUM	1	0.5	0	0.25	0.25
70102620	TRAFFIC CONTROL AND PROTECTION, STANDARD 701501	L. SUM	1	0.5	0	0.25	0.25
70102635	TRAFFIC CONTROL AND PROTECTION, STANDARD 701701	L. SUM	1	0.5	0	0.25	0.25
70102640	TRAFFIC CONTROL AND PROTECTION, STANDARD 701801	L. SUM	1	0.5	0	0.25	0.25
72000100	SIGN PANEL - TYPE 1	SQ FT	31	31	0	0	0
72900100	METAL POST - TYPE A	FOOT	84	84	0	0	0
*78000100	THERMOPLASTIC PAVEMENT MARKING - LETTERS AND SYMBOLS	SQ FT	36.4	0	0	36.4	0
*78000200	THERMOPLASTIC PAVEMENT MARKING - LINE 4"	FOOT	400	0	0	400	0
*78000400	THERMOPLASTIC PAVEMENT MARKING - LINE 6"	FOOT	100	0	0	100	0
*78000600	THERMOPLASTIC PAVEMENT MARKING - LINE 12"	FOOT	436	0	0	436	0
*78000650	THERMOPLASTIC PAVEMENT MARKING - LINE 24"	FOOT	140	0	0	140	0
*78300100	PAVEMENT MARKING REMOVAL	SQ FT	350	0	0	350	0
*81018600	CONDUIT PUSHED, 2 1/2" DIA., GALVANIZED STEEL	FOOT	57	0	0	57	0
*85000200	MAINTENANCE OF EXISTING TRAFFIC SIGNAL INSTALLATION	EACH	1	0	0	1	0
*87301215	ELECTRIC CABLE IN CONDUIT, SIGNAL NO. 14 2C	FOOT	692	0	0	692	0
*87301225	ELECTRIC CABLE IN CONDUIT, SIGNAL NO. 14 3C	FOOT	1282	0	0	1282	0
*87502440	TRAFFIC SIGNAL POST, GALVANIZED STEEL, 10 FT	EACH	1	0	0	1	0
*87800100	CONCRETE FOUNDATION, TYPE A	FOOT	4	0	0	4	0
*87900200	DRILL EXISTING HANDHOLE	EACH	1	0	0	1	0
*88102717	PEDESTRIAN SIGNAL HEAD, LED, 1-FACE, BRACKET MOUNTED WITH COUNTDOWN TIMER	EACH	4	0	0	4	0
*88102747	PEDESTRIAN SIGNAL HEAD, LED, 2-FACE, BRACKET MOUNTED WITH COUNTDOWN TIMER	EACH	2	0	0	2	0
*88800100	PEDESTRIAN PUSH-BUTTON	EACH	6	0	0	6	0
*89502200	MODIFY EXISTING CONTROLLER	EACH	1	0	0	1	0
88600100	DETECTOR LOOP, TYPE I	FOOT	83	0	0	83	0
*X0321478	MAINTENANCE OF EXISTING LIGHTING SYSTEM COMPLETE	L. SUM	1	0	0	0	1
X0321556	SANITARY MANHOLE TO BE ADJUSTED	EACH	2	2	0	0	0
*X0322951	CABLE SPLICE, SPECIAL	EACH	4	0	0	0	4
X6063401	COMBINATION CONCRETE CURB AND GUTTER, TYPE M-4.12	FOOT	75	75	0	0	0
X8950200	REBUILD EXISTING HANDHOLE	EACH	3	3	0	0	0
XX000671	COMBINATION CONCRETE CURB AND GUTTER, TYPE B-4.12	FOOT	445	442	3	0	0
XX005238	TOPSOIL FURNISH AND PLACE, VARIABLE DEPTH	CU YD	75	75	0	0	0
Z0013798	CONSTRUCTION LAYOUT	L. SUM	1	0.5	0	0.25	0.25
Z0017190	DOWEL BARS 1"	EACH	800	800	0	0	0
Z0018400	DRAINAGE STRUCTURES TO BE ADJUSTED	EACH	2	2	0	0	0
Z0018700	DRAINAGE STRUCTURES TO BE REMOVED	EACH	3	3	0	0	0
XX008121	LUMINAIRE, SODIUM VAPOR, ORNAMENTAL, 35 WATT WITH ARM ASSEMBLY	EACH	4	0	0	0	4
42400430	PORTLAND CEMENT CONCRETE SIDEWALK, 5 INCH, SPECIAL	SQ FT	2950	2950	0	0	0

* INDICATES SPECIALTY ITEM