

SUMMARY OF QUANTITIES			
PAY ITEM NO.	DESIGNATION	UNIT	TOTAL QUANTITY
			Y030-1E
67100100	MOBILIZATION	L SUM	1
* 70101700	TRAFFIC CONTROL AND PROTECTION	L SUM	1
80400100	ELECTRIC SERVICE INSTALLATION	EACH	1
81018700	CONDUIT PUSHED, 3" DIA., GALVANIZED STEEL	FOOT	1496
81603210	UNIT DUCT, 600V, 3-1C NO.4, 1/C NO.6 GROUND, (EPR-TYPE RHW), 1/4" DIA. POLYETHYLENE	FOOT	8566
81900200	TRENCH AND BACKFILL FOR ELECTRICAL WORK	FOOT	6675
82102250	LUMINAIRE, SODIUM VAPOR, HORIZONTAL MOUNT, 250 WATT	EACH	17
82102400	LUMINAIRE, SODIUM VAPOR, HORIZONTAL MOUNT, 400 WATT	EACH	26
83050810	LIGHT POLE, ALUMINUM, 47.5 FT. M.H., 15 FT. MAST ARM	EACH	39
83600200	LIGHT POLE FOUNDATION, 24" DIAMETER	FOOT	390
83800205	BREAKAWAY DEVICE, TRANSFORMER BASE, 15 INCH BOLT CIRCLE	EACH	39
* X0323792	LIGHTING CONTROLLER, SINGLE DOOR, CONSOLE TYPE	EACH	1
* X0324387	LUMINAIRE SAFETY CABLE ASSEMBLY	EACH	43
* 80400200	ELECTRIC UTILITY SERVICE CONNECTION	L SUM	1
* XX006937	GROUND ROD, 5/8" DIA. X 10 FT.	EACH	39

* DESIGNATES SPECIAL PROVISIONS



GANDHI AND ASSOCIATES, INC.
ENGINEERS AND PLANNERS
6035 N. NORTHWEST HIGHWAY
SUITE 306
CHICAGO, ILLINOIS 60631 TEL. (773) 774-5900

FILE NAME =	USER NAME = _M ELSHOLI.	DESIGNED - MAE	REVISED -	STATE OF ILLINOIS DEPARTMENT OF TRANSPORTATION	SCHEDULE OF ELECTRICAL QUANTITIES				F.A. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.	
J:\projects\projects 2008\us-30_wolf_sm\83_500.dgn		DRAWN - MAA	REVISED -		SCALE:	SHEET NO.	OF	SHEETS	STA.	TO STA.	353	09-00029-00-LT	WILL	13 3
PLOT SCALE = NONE		CHECKED - MGK/PKG	REVISED -		CONTRACT NO. <i>63250</i>									
PLOT DATE = 6/29/2009		DATE - JULY 1, 2009	REVISED -		FED. ROAD DIST. NO. ILLINOIS/FAP 353/US 30 (LINCOLN HIGHWAY)									