

Description: Bituminous Materials (Prime Coat)										Unit: Gallon	
Location	Begin		End		Length (FT)	Width (FT)	Area (SY)	Appl. Rate (Gal/SY)	Quantity (Gal)		
	Station	Side	Station	Side					Subtotal	Cumm.	
Base											
franklin ave	9+21.7	Both	24+00.	Both			10533.0	0.1	1053.3	1053.3	
Binder											
franklin ave	9+21.7	Both	24+00.	Both			10533.0	0.1	1053.3	2106.6	

Description: Aggregate (Prime Coat)										Unit: Ton	
Location	Begin		End		Length (FT)	Width (FT)	Area (SY)	Appl. Rate (lb/SY)	Quantity (Ton)		
	Station	Side	Station	Side					Subtotal	Cumm.	
Base											
franklin ave	9+21.7	Both	24+00.	Both			10533.0	4	21.1	21.1	
Binder											
franklin ave	9+21.7	Both	24+00.	Both			10533.0	4	21.1	42.1	

Description: Leveling Binder (Machine Method)										Unit: Ton	
Location	Begin		End		Length (FT)	Width (FT)	Area (SY)	Depth (IN)	D	Quantity (Ton)	
	Station	Side	Station	Side						Subtotal	Cumm.
franklin ave	9+21.7	Both	24+00.	Both			10533.0	1.5	112	885	885

Description: Hot-Mix Asphalt Surface Removal - Butt Joint										Unit: Square Yard	
Location	Begin		End		Length (FT)	Width (FT)	Area (SF)	Quantity (SY)			
	Station	Side	Station	Side				Subtotal	Cumm.		
franklin ave	9+21.7	CL	9+26.2	CL	4.5	42.0	189.0	21.0	21.0		
atlantic ave	1+54.	CL	1+58.5	CL	4.5	36.4	163.8	18.2	39.2		
calwagner ave	2+49.	CL	2+53.5	CL	4.5	33.1	149.0	16.6	55.8		
calwagner ave	3+57.	CL	3+61.5	CL	4.5	38.1	171.5	19.1	74.8		
gustav ave	3+45.	CL	3+49.5	CL	4.5	42.9	193.1	21.5	96.3		
Ruby ave	1+74.	CL	1+78.5	CL	4.5	31.9	143.6	16.0	112.2		
Ruby ave	0+29.	CL	0+33.5	CL	4.5	31.5	141.8	15.8	128.0		
franklin ave	23+95.5	CL	24+00.	CL	4.5	65.0	292.5	32.5	160.5		
belmont ave	9+24.	RT	9+28.5	RT	4.5	45.0	202.5	22.5	183.0		

Description: Hot-Mix Asphalt Surface Course, Mix "D", N70										Unit: Ton	
Location	Begin		End		Length (FT)	Width (FT)	Area (SY)	Depth (IN)	D	Quantity (Ton)	
	Station	Side	Station	Side						Subtotal	Cumm.
franklin ave	9+21.7	Both	24+00.	Both			10533.0	1.75	112	1,032	1,032

Description: Portland Cement Concrete Sidewalk 5 Inch										Unit: Square Foot	
Location	Begin		End Station		Length (FT)	Width (FT)	Quantity (SF)				
	Station	Side	Station	Side			Subtotal	Cumm.			
Franklin Ave	13+87.	LT	13+97.	LT	10	7.8	78.0	78.0			

Description: AREA REFLECTIVE CRACK CONTROL TREATMENT									
Location	Begin		End		Length (FT)	Width (FT)	Area (SF)	Quantity (SY)	
	Station	Side	Station	Side				Subtotal	Cumm.
franklin ave	9+21.7	Both	24+00.	Both			94797	10533.0	10533.0

Description: DETECTABLE WARNINGS										Unit: Square Foot	
Location	Begin		End		Length (FT)	Width (FT)	Area (SF)	Quantity (SF)			
	Station	Side	Station	Side				Subtotal	Cumm.		
Franklin Ave	13+70.	LT					6	6.0	6.0		

Description: Hot-Mix Asphalt Surface Removal, 3 1/4"										Unit: Square Yard	
Location	Begin		End		Length (FT)	Width (FT)	Area (SF)	Quantity (SY)			
	Station	Side	Station	Side				Subtotal	Cumm.		
franklin ave	9+21.7	Both	24+00.	Both			94797	10533.0	10533.0		

Description: SIDEWALK REMOVAL										Unit: Square Foot	
Location	Begin		End		Area (SF)	Quantity (SF)					
	Station	Side	Station	Side		Subtotal	Cumm.				
Franklin Ave	13+87	LT	13+97.	LT	78	78.0	78.0				

Description: Thermoplastic Pavement Marking - Letters and Symbols									
Location	Begin		letter/symbol	Length (FT)	Width (FT)	Quantity (SF)			
	Station	Side				Subtotal	Cumm.		
franklin ave	11+90	CL	Left Arrow			15.6	15.6		
franklin ave	12+13	CL	ONLY			20.8	36.4		
franklin ave	23+39	CL	ONLY			20.8	57.2		
franklin ave	23+39	RT	ONLY	O/S 25'		20.8	78.0		
franklin ave	23+63	CL	Left Arrow			15.6	93.6		
franklin ave	23+63	RT	Right Arrow	O/S 25'		15.6	109.2		
franklin ave	16+45	LT	Handicap	O/S 20'		4.6	113.8		
franklin ave	16+45	RT	Handicap	O/S 20'		4.6	118.4		
franklin ave	18+00	LT	Handicap	O/S 15'		4.6	123.0		
franklin ave	20+10	RT	Handicap	O/S 20'		4.6	127.6		

Description: Thermoplastic Pavement Marking 24"										Unit: Linear Foot	
Location	Begin		End		Length (FT)	Quantity (LF)					
	Station	Side	Station	Side		Subtotal	Cumm.				
Stop Bars											
franklin ave	10+44	LT	10+51	RT	40.4	40.4	40.4				
franklin ave	16+67	LT	16+96	RT	33.1	33.1	73.5				
Calwagner St.	2+41.	RT	2+53.	LT	32.8	32.8	106.3				
Calwagner St.	3+59.	CL	3+65.	LT	19.0	19.0	125.3				
franklin ave	17+44.	LT	17+58.	CL	34.5	34.5	159.8				
Gustav St.	3+39.	RT	3+45.	CL	18.5	18.5	178.3				
franklin ave	23+94.	RT	24+08.	LT	36.6	36.6	214.9				
franklin ave	9+16.	LT	9+16.	RT	26.0	26.0	240.9				
belmont ave	9+44.	RT	9+44.	RT	23.6	23.6	264.5				
ruby st	9+99.	RT	10+16.	RT	16.5	16.5	281.0				
ruby st	9+80.	LT	9+99.	LT	13.8	13.8	294.8				

Description: Thermoplastic Pavement Marking 12"										Unit: Linear Foot	
Location	Begin		End		Length (FT)	Quantity (LF)					
	Station	Side	Station	Side		Subtotal	Cumm.				
Median											
franklin ave	12+25	CL	13+70.	CL	67.0	67.0	67.0				
franklin ave	14+08	CL	14+53	CL	18.7	18.7	85.7				
Disabled parking spaces											
franklin ave	16+27.	LT			31.1	31.1	116.8				
franklin ave	16+40.	RT			33.1	33.1	149.9				
franklin ave	18+07.	LT			53.5	53.5	203.4				
franklin ave	20+10.	RT			45.3	45.3	248.7				
no parking zones											
franklin ave	9+13.	RT	9+56.	RT	43.0	43.0	291.7				
Belmont Ave.		RT		RT	22.0	22.0	313.7				

FILE NAME = p:\10140450 - franklin ave resurfacing\plans\sheeta\F0140450qtam0001.dgn
 USER NAME = #USER#
 DESIGNED -
 DRAWN -
 CHECKED -
 PLOT SCALE = 480.0000' / IN.
 PLOT DATE = 7/14/2009

REVISOR -
 REVISED -
 REVISED -
 REVISED -
 DATE -

STATE OF ILLINOIS
 DEPARTMENT OF TRANSPORTATION

FRANKLIN AVENUE
 SCHEDULES OF QUANTITIES

SCALE: N/A SHEET NO. 1 OF 2 SHEETS STA. TO STA.

F.A.U. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
3533	09-00070-00-RS	COOK	16	6
CONTRACT NO. 63254				
ILLINOIS				FED. AID PROJECT