

SUMMARY OF QUANTITIES

CODE	PAY ITEM	UNIT	1000 TOTAL QUANTITY	1000 100% FEDERAL 0% LOCAL
21101615	TOPSOIL FURNISH AND PLACE, 4"	SQ YD	300	300
25000400	NITROGEN FERTILIZER NUTRIENT	POUND	5	5
25000500	PHOSPHORUS FERTILIZER NUTRIENT	POUND	5	5
25000600	POTASSIUM FERTILIZER NUTRIENT	POUND	5	5
25200100	SODDING	SQ YD	300	300
25200200	SUPPLEMENTAL WATERING	UNIT	10	10
40200800	AGGREGATE SURFACE COURSE, TYPE B	TON	40	40
40600100	BITUMINOUS MATERIALS (PRIME COAT)	GAL	1,450	1,450
40600400	MIXTURE FOR CRACKS, JOINTS, AND FLANGWAYS	TON	20	20
40600625	LEVELING BINDER (MACHINE METHOD), N50	TON	900	900
40600982	HOT-MIX ASPHALT SURFACE REMOVAL - BUTT JOINT	SQ YD	500	500
40603335	HOT-MIX ASPHALT SURFACE COURSE, MIX "D", N50	TON	1,700	1,700
40800050	INCIDENTAL HOT-MIX ASPHALT SURFACING	TON	5	5
42101300	PROTECTIVE COAT	SQ YD	200	200
42300300	PORTLAND CEMENT CONCRETE DRIVEWAY PAVEMENT, 7 INCH	SQ YD	40	40
42400200	PORTLAND CEMENT CONCRETE SIDEWALK 5 INCH	SQ FT	850	850
⊛ 42400800	DETECTABLE WARNINGS	SQ FT	60	60
⊛ 44000198	HOT-MIX ASPHALT SURFACE REMOVAL, VARIABLE DEPTH	SQ YD	13,400	13,400
⊛ 44000200	DRIVEWAY PAVEMENT REMOVAL	SQ YD	40	40
⊛ 44000600	SIDEWALK REMOVAL	SQ FT	850	850
⊛ 44001700	COMBINATION CONCRETE CURB AND GUTTER REMOVAL AND REPLACEMENT	FOOT	400	400
⊛ 44200924	CLASS B PATCHES, TYPE III, 7 INCH	SQ YD	50	50
⊛ 44200926	CLASS B PATCHES, TYPE IV, 7 INCH	SQ YD	350	350
60300305	FRAMES AND LIDS TO BE ADJUSTED	EACH	1	1
⊛ 60300310	FRAMES AND LIDS TO BE ADJUSTED (SPECIAL)	EACH	31	31
⊛ 60406000	FRAMES AND LIDS, TYPE 1, OPEN LID	EACH	5	5
⊛ 60406100	FRAMES AND LIDS, TYPE 1, CLOSED LID	EACH	5	5
67100100	MOBILIZATION	L SUM	1	1
⊛ 70101700	TRAFFIC CONTROL AND PROTECTION	L SUM	1	1
70300200	TEMPORARY PAVEMENT MARKING	FOOT	1,000	1,000
70300210	TEMPORARY PAVEMENT MARKING - LETTERS AND SYMBOLS	SQ FT	85	85
★ 78000100	THERMOPLASTIC PAVEMENT MARKING - LETTERS AND SYMBOLS	SQ FT	85	85
★ 78000200	THERMOPLASTIC PAVEMENT MARKING - LINE 4"	FOOT	5,400	5,400
★ 78000400	THERMOPLASTIC PAVEMENT MARKING - LINE 6"	FOOT	700	700
★ 78000600	THERMOPLASTIC PAVEMENT MARKING - LINE 12"	FOOT	100	100
★ 78000650	THERMOPLASTIC PAVEMENT MARKING - LINE 24"	FOOT	150	150
★⊛ 88600600	DETECTOR LOOP REPLACEMENT	FOOT	700	700
⊛ Z0004900	BITUMINOUS MIXTURE FOR PATCHING POTHOLES (HOT MIX)	TON	20	20

- ★ DENOTES SPECIALTY ITEM
 ⊛ DENOTES THAT A SPECIAL PROVISION HAS BEEN PROVIDED

Drawing file: W:\Projects\83809102 - Westchester Blvd Resurfacing\Quantities-Westchester Blvd.dwg Jul 14, 2009 - 10:45am



9913 Research Blvd
 Westchester, Illinois 60151-2798
 Phone: 708-968-6300
 Fax: 708-968-6322

USER NAME	DESIGNED	TG	REVISED
	DRAWN	TG	REVISED
PLOT SCALE	CHECKED	JG	REVISED
PLOT DATE	DATE	07/14/09	REVISED

**STATE OF ILLINOIS
 DEPARTMENT OF TRANSPORTATION**

SUMMARY OF QUANTITIES

ROUTE NO.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
FAU 2713	09-00074-00-RS	COOK	18	4
CONTRACT NO.			63257	
FED. ROAD DIST. NO. 1 ILLINOIS FED. AID PROJECT ARA-9003(324)				

SCALE: NONE SHEET NO. OF SHEETS STA. TO STA.