

| SUMMARY OF QUANTITIES | | | | 80% FEDERAL 20% STATE |
|-----------------------|--|--------|----------------|--------------------------------------|
| CODE NO. | ITEM | UNIT | TOTAL QUANTITY | CONSTRUCTION CODE ROADWAY 1000 |
| 20200100 | EARTH EXCAVATION | CU YD | 10 | 10 |
| 20400800 | FURNISHED EXCAVATION | CU YD | 36 | 36 |
| 40600115 | POLYMERIZED BITUMINOUS MATERIALS (PRIME COAT) | GALLON | 18620 | 18620 |
| 40600300 | AGGREGATE (PRIME COAT) | TON | 202 | 202 |
| 40600400 | MIXTURE FOR CRACKS, JOINTS, AND FLANGEWAYS | TON | 28 | 28 |
| 40600725 | POLYMERIZED LEVELING BINDER (HAND METHOD), N50 | TON | 46 | 46 |
| X4067107 | POLYMERIZED LEVELING BINDER (MACHINE METHOD), IL-4.75, N50 | TON | 4008 | 4008 |
| 40600895 | CONSTRUCTING TEST STRIP | EACH | 2 | 2 |
| 40600990 | TEMPORARY RAMP | SQ YD | 152 | 152 |
| 40603510 | POLYMERIZED HOT-MIX ASPHALT SURFACE COURSE, MIX "C", N50 | TON | 8016 | 8016 |
| 40800050 | INCIDENTAL HOT-MIX ASPHALT SURFACING | TON | 1106 | 1106 |
| 44000158 | HOT-MIX ASPHALT SURFACE REMOVAL, 2 1/4" | SQ YD | 101180 | 101180 |
| 48101200 | AGGREGATE SHOULDERS, TYPE B | TON | 1918 | 1918 |
| 67000400 | ENGINEER'S FIELD OFFICE, TYPE A | CAL MO | 2 | 2 |
| 67100100 | MOBILIZATION | L SUM | 1 | 1 |
| 70100460 | TRAFFIC CONTROL AND PROTECTION, STANDARD 701306 | L SUM | 1 | 1 |
| 70300100 | SHORT-TERM PAVEMENT MARKING | FOOT | 12890 | 12890 |
| 70300220 | TEMPORARY PAVEMENT MARKING - LINE 4" | FOOT | 99350 | 99350 |
| 70300240 | TEMPORARY PAVEMENT MARKING - LINE 6" | FOOT | 8056 | 8056 |
| 70301000 | WORK ZONE PAVEMENT MARKING REMOVAL | SQ FT | 1030 | 1030 |
| • 78001110 | PAINT PAVEMENT MARKING - LINE 4" | FOOT | 99350 | 99350 |
| • 78001130 | PAINT PAVEMENT MARKING - LINE 6" | FOOT | 8056 | 8056 |
| • 78100100 | RAISED REFLECTIVE PAVEMENT MARKER | EACH | 563 | 563 |
| 78300200 | RAISED REFLECTIVE PAVEMENT MARKER REMOVAL | EACH | 563 | 563 |
| • Z0055300 | RUMBLE STRIP | EACH | 1 | 1 |

• SPECIALTY ITEMS

| | | | |
|---|----------------------|------------|-----------|
| FILE NAME = | USER NAME = braboypc | DESIGNED - | REVISED - |
| cc:\pw\work\p\1001\BRABOYPC\10134845\036920-shr-cover.dgn | | DRAWN - | REVISED - |
| | | CHECKED - | REVISED - |
| | | | |

STATE OF ILLINOIS
DEPARTMENT OF TRANSPORTATION

SUMMARY OF QUANTITIES

| F.A.S RTE. | SECTION | COUNTY | TOTAL SHEETS | SHEET NO. |
|--------------------|--------------|--------|-----------------|--------------|
| 1252 | (24.R-4)RS-2 | BUREAU | 8 | 3 |
| CONTRACT NO. 66920 | | | | |