

## SUMMARY OF QUANTITIES

<b>I-74</b> VERMILION CO. RURAL MULTILANE 100% STATE MINOR STRUCTURE REPAIR  SFTY-2A S.N. 092-0001 S.N. 092-0002	<b>I-74</b> CHAMPAIGN CO. RURAL MULTILANE 100% STATE MINOR STRUCTURE REPAIR  SFTY-2A S.N. 010-0029 S.N. 010-0030	<b>IL-1</b> VERMILION CO. RURAL TWO LANE 100% STATE MINOR STRUCTURE REPAIR  SFTY-2A S.N. 092-0033	<b>US-136</b> VERMILION CO. RURAL TWO LANE 100% STATE MINOR STRUCTURE REPAIR  SFTY-2A S.N. 092-0144
---	---	---	---

CODE NO	ITEM	UNIT	TOTAL QUANTITY	LOCATION #1	LOCATION #2	LOCATION #3	LOCATION #4
20100500	TREE REMOVAL, ACRES	ACRE	0.5	0.25	0.25	0.0	0.0
28100107	STONE RIPRAP, CLASS A4	SQ YD	2095.0	0.0	0.0	970.0	1125.0
28100109	STONE RIPRAP, CLASS A5	SQ YD	250.0	100.0	150.0	0.0	0.0
28100709	STONE DUMPED RIPRAP, CLASS A5	SQ YD	1,180.0	790.0	390.0	0.0	0.0
28200200	FILTER FABRIC	SQ YD	2345.0	100.0	150.0	970.0	1125.0
44004000	PAVED DITCH REMOVAL	FOOT	230.0	100.0	130.0	0.0	0.0
66500105	WOVEN WIRE FENCE, 4'	FOOT	690.0	0.0	0.0	690.0	0.0
66501600	WOVEN WIRE GATES, 4'X16' DOUBLE	EACH	2.0	0.0	0.0	2.0	0.0
66503200	BARBED WIRE FENCE, FIVE STRAND	FOOT	210.0	0.0	0.0	210.0	0.0
66503400	BARBED WIRE FENCE REMOVAL	FOOT	610.0	0.0	0.0	610.0	0.0
67100100	MOBILIZATION	L SUM	1.0	0.3	0.3	0.2	0.2
70100450	TRAFFIC CONTROL AND PROTECTION, STANDARD 701201	L SUM	1.0	0.0	0.0	0.5	0.5
70100700	TRAFFIC CONTROL AND PROTECTION, STANDARD 701406	L SUM	1.0	0.5	0.5	0.0	0.0
X7015005	CHANGEABLE MESSAGE SIGN	CAL DA	28.0	14.0	14.0	0.0	0.0

\* D5 SCOUR MITIGATION 2009-3  
 \*\* CHAMPAIGN & VERMILION

FILE NAME =	USER NAME = szmsgm	DESIGNED - BJH	REVISED -	<b>STATE OF ILLINOIS DEPARTMENT OF TRANSPORTATION</b>	<b>SUMMARY OF QUANTITIES</b>	F.A. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
c:\pwork\VPWIDOT\SI\MSGM\d0120266\d570	70-plen.dgn	DRAWN - GMS	REVISED -			VAR.	*	**	22	5
	PLOT SCALE = 40.0000' / IN.	CHECKED -	REVISED -		SCALE:	SHEET NO. OF SHEETS STA. TO STA.		CONTRACT NO. 70770		
	PLOT DATE = 3/18/2009	DATE -	REVISED -		FED. ROAD DIST. NO.		ILLINOIS FED. AID PROJECT			