

ILLINOIS DEPARTMENT OF TRANSPORTATION
 SUMMARY OF QUANTITIES

CONTRACT 72D15

F.A.I. R.T.E.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
55	*	MACOUPIN	8	3
STA.		TO STA.		
FED. ROAD DIST. NO.	ILLINOIS	FED. AID PROJECT		

* D6 INTERMITTENT RS 2010

LOCATION OF WORK				100% STATE
				HMA ROADWAY 1-55 RESURFACING
SUMMARY OF QUANTITIES				CONSTRUCTION TYPE CODE
CODE NO.	ITEM	UNIT	TOTAL QUANTITY	1000-2A
40600200	BITUMINOUS MATERIALS (PRIME COAT)	TON	2	2
40600895	CONSTRUCTING TEST STRIP	EACH	2	2
40600855	POLYMERIZED LEVELING BINDER (MACHINE METHOD), N105	TON	523	523
40603575	POLYMERIZED HOT-MIX ASPHALT SURFACE COURSE, MIX "E", N105	TON	448	448
44000162	HOT-MIX ASPHALT SURFACE REMOVAL, 3 1/4"	SQ YD	5,333	5,333
44200577	CLASS A PATCHES, TYPE II, 12 INCH	SQ YD	60	60
44213000	PATCHING REINFORCEMENT	SQ YD	60	60
44213200	SAW CUTS	FOOT	400	400
67100100	MOBILIZATION	L SUM	1	1
70100420	TRAFFIC CONTROL AND PROTECTION, STANDARD 701411	EACH	2	2
70100800	TRAFFIC CONTROL AND PROTECTION, STANDARD 701401	L SUM	1	1
70106800	CHANGEABLE MESSAGE SIGN	CAL MO	2	2
70300100	SHORT-TERM PAVEMENT MARKING	FOOT	560	560
70301000	WORK ZONE PAVEMENT MARKING REMOVAL	SQ FT	187	187
* 78100100	RAISED REFLECTIVE PAVEMENT MARKER	EACH	51	51
78300200	RAISED REFLECTIVE PAVEMENT MARKER REMOVAL	EACH	51	51
* X7800620	URETHANE PAVEMENT MARKING - LINE 5"	FOOT	5,010	5,010

*Specialty Items

REVISIONS	
NAME	DATE

ILLINOIS DEPARTMENT OF TRANSPORTATION
 SUMMARY OF QUANTITIES
 FAI 55
 SECTION D6 INTERMITTENT RS 2010
 MACOUPIN COUNTY

SCALE: NOT DRAWN TO SCALE
 DATE _____ DRAWN BY _____
 CHECKED BY _____