

CONTRACT 72D15

F.A.I. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
55	*	MACOUPIN	8	5
STA.		TO STA.		
FED. ROAD DIST. NO.		ILLINOIS FED. AID PROJECT		

• D6 INTERMITTENT RS 2010

PAVING SCHEDULE

LOCATION	PAVEMENT WIDTH (FOOT)	HMA SURF REM 3 1/4" (SQ YD)	BIT MATL PR CT (TON)	LEVEL BINDER DEPTH (INCHES)	SURFACE DEPTH (INCHES)	LEVEL BINDER N105 (TON)	SURFACE N105 (TON)
I-55 MAINLINE NORTHBOUND							
STA 614+00.00 TO STA 635+00.00	12	2,800.00	1.06	1.75	1.50	274.40	235.20
STA 645+00.00 TO STA 664+00.00	12	2,533.33	0.96	1.75	1.50	248.27	212.80
TOTAL		5,333.33	2.02			522.67	448.00

PAVEMENT MARKING SCHEDULE

LOCATION	LENGTH (FOOT)	URETHANE PAVT MARK LINE - 5"			SHORT TERM PAVT MK (FOOT)	WORK ZONE PAVT MARK REM (SQ FT)	RAISED REFL REM (EACH)	RAISED REFL (EACH)
		EDGE LINE (FOOT)	CENTER LINE (FOOT)	TOTAL (FOOT)				
I-55 MAINLINE NORTHBOUND								
STA 614+00.00 TO STA 635+00.00	2,100.00	2,100.00	530.00	2,630.00	294.00	98.00	27	27
STA 645+00.00 TO STA 664+00.00	1,900.00	1,900.00	480.00	2,380.00	266.00	88.67	24	24
TOTAL		4,000.00	1,010.00	5,010.00	560.00	186.67	51	51

C:\p\mca\p\007\AUGUST\08\082731\08272015-nt-eh.dgn
 5/1/2015 2:08:07 PM 6/17/2015
 MREB

REVISIONS	
NAME	DATE

ILLINOIS DEPARTMENT OF TRANSPORTATION
SCHEDULE OF QUANTITIES
 FAI 55
 SECTION D6 INTERMITTENT RS 2010
 MACOUPIN COUNTY

SCALE _____ DRAWN BY _____
 DATE _____ CHECKED BY _____