

SUMMARY OF QUANTITIES			801-FED- 201-STATE TOTAL QUANTITIES	CONSTRUCTION TYPE CODE			
CODE NO	ITEM	UNIT		1000-2A	X071-2A	J000-2A	X028-2A
20100500	TREE REMOVAL, ACRES	ACRE	0.1			0.1	
20200100	EARTH EXCAVATION	CU YD	808	309		499	
20300100	CHANNEL EXCAVATION	CU YD	1127	1127			
20400800	FURNISHED EXCAVATION	CU YD	969	692		277	
20600110	GRANULAR EMBANKMENT, SPECIAL	TON	1140	1140			
20700400	POROUS GRANULAR EMBANKMENT, SPECIAL	CU YD	138		138		
* 21101505	TOPSOIL EXCAVATION AND PLACEMENT	CU YD	466	305		161	
* 25001000	SEEDING, CLASS 2 (SPECIAL)	ACRE	1.5	1		0.5	
* 25100630	EROSION CONTROL BLANKET	SQ YD	1560	947		613	
* 28000250	TEMPORARY EROSION CONTROL SEEDING	POUND	150	100		50	
28000300	TEMPORARY DITCH CHECKS	EACH	6	3		3	
28000400	PERIMETER EROSION BARRIER	FOOT	1110	860		250	
28100107	STONE RIPRAP, CLASS A4	SQ YD	1320		1155		165
28200200	FILTER FABRIC	SQ YD	1320		1155		165
31101200	SUB-BASE GRANULAR MATERIAL, TYPE B 4"	SQ YD	371			371	
35650700	BASE COURSE WIDENING	SQ YD	371	276		95	
40600100	BITUMINOUS MATERIALS (PRIME COAT)	GALLON	585	585			
40600300	AGGREGATE (PRIME COAT)	TON	4	4			
40600645	LEVELING BINDER (MACHINE METHOD), N90	TON	191	191			
40600982	HOT-MIX ASPHALT SURFACE REMOVAL - BUTT JOINT	SQ YD	204	204			
40600990	TEMPORARY RAMP	SQ YD	71	71			
40603345	HOT-MIX ASPHALT SURFACE COURSE, MIX "D", N90	TON	51	51			
40701956	HOT-MIX ASPHALT PAVEMENT (FULL-DEPTH), 13 3/4"	SQ YD	958	958			
40800050	INCIDENTAL HOT-MIX ASPHALT SURFACING	TON	24	24			
42000500	PORTLAND CEMENT CONCRETE PAVEMENT 10"	SQ YD	332			332	
42001165	BRIDGE APPROACH PAVEMENT	SQ YD	270	270			
42001200	PAVEMENT FABRIC	SQ YD	332			332	
44000100	PAVEMENT REMOVAL	SQ YD	403	180		223	
44004250	PAVED SHOULDER REMOVAL	SQ YD	276	276			
48101200	AGGREGATE SHOULDERS, TYPE B	TON	10	10			
48101600	AGGREGATE SHOULDERS, TYPE B 8"	SQ YD	661	369		292	
48203029	HOT-MIX ASPHALT SHOULDERS, 8"	SQ YD	816	453		363	
48203037	HOT-MIX ASPHALT SHOULDERS, 10"	SQ YD	1136	773		363	
48203100	HOT-MIX ASPHALT SHOULDERS	TON	15	15			
50100100	REMOVAL OF EXISTING STRUCTURES	EACH	2		1		1
50200100	STRUCTURE EXCAVATION	CU YD	154		154		
50300100	FLOOR DRAINS	EACH	10		10		
50300225	CONCRETE STRUCTURES	CU YD	37.8		37.8		

\* Specialty Items

FILE NAME =	USER NAME = steffennk	DESIGNED -	REVISED -	<b>STATE OF ILLINOIS DEPARTMENT OF TRANSPORTATION</b>	<b>SUMMARY OF QUANTITIES</b>				F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
ct:\pw_work\PWIDOT\STEFFENK\dms50690\74214-shr-soq.dgn	74214-shr-soq.dgn	DRAWN -	REVISED -		SCALE:	SHEET NO.	OF	SHEETS	STA.	TO STA.	Wayne	67	3
PLOT SCALE = 50.0000' / IN.		CHECKED -	REVISED -						FED. ROAD DIST. NO.	ILLINOIS FED. AID PROJECT	CONTRACT NO. 74214		
PLOT DATE = 1/12/2009		DATE -	REVISED -										