

SUMMARY OF QUANTITIES

80% FED.
20% STATE

CONSTRUCTION TYPE CODE

CODE NO	ITEM	UNIT	TOTAL QUANTITIES	CONSTRUCTION TYPE CODE			
				1000-2A	X071-2A	J000-2A	X028-2A
50300255	CONCRETE SUPERSTRUCTURE	CU YD	144.2		144.2		
50300260	BRIDGE DECK GROOVING	SQ YD	359		359		
50300280	CONCRETE ENCASEMENT	CU YD	4.2		4.2		
50300300	PROTECTIVE COAT	SQ YD	449		449		
50500105	FURNISHING AND ERECTING STRUCTURAL STEEL	L SUM	1		1		
50500505	STUD SHEAR CONNECTORS	EACH	1638		1638		
50800105	REINFORCEMENT BARS	POUND	48870				48870
50800205	REINFORCEMENT BARS, EPOXY COATED	POUND	36530		36530		
50800515	BAR SPLICERS	EACH	508		416		92
51201610	FURNISHING STEEL PILES HP12X63	FOOT	396		396		
51202305	DRIVING PILES	FOOT	396		396		
51205200	TEMPORARY SHEET PILING	SQ FT	793.9		470		323.9
51500100	NAME PLATES	EACH	2		1		1
52100520	ANCHOR BOLTS, 1"	EACH	24		24		
54003000	CONCRETE BOX CULVERTS	CU YD	170.4				170.4
59100100	GEOCOMPOSITE WALL DRAIN	SQ YD	88		88		
60100905	PIPE DRAINS 4"	FOOT	34	34			
60109580	PIPE UNDERDRAINS FOR STRUCTURES 4"	FOOT	135		135		
* 63000001	STEEL PLATE BEAM GUARD RAIL, TYPE A, ⁶ FOOT POSTS	FOOT	600	300		300	
* 63000025	STEEL PLATE BEAM GUARD RAIL, ATTACHED TO STRUCTURES	FOOT	75			75	
* 63100085	TRAFFIC BARRIER TERMINAL, TYPE 6	EACH	4	4			
* 63100167	TRAFFIC BARRIER TERMINAL, TYPE 1 (SPECIAL) TANGENT	EACH	8	4		4	
63200310	GUARDRAIL REMOVAL	FOOT	1194	636		558	
66600105	FURNISHING AND ERECTING RIGHT-OF-WAY MARKERS	EACH	4			4	
67000400	ENGINEER'S FIELD OFFICE, TYPE A	CAL MO	8	4		4	
67100100	MOBILIZATION	L SUM	1	0.5		0.5	
70100405	TRAFFIC CONTROL AND PROTECTION, STANDARD 701321	EACH	2	1		1	
70100450	TRAFFIC CONTROL AND PROTECTION, STANDARD 701201	L SUM	1	0.5		0.5	
70100500	TRAFFIC CONTROL AND PROTECTION, STANDARD 701326	L SUM	1	0.5		0.5	
70103815	TRAFFIC CONTROL SURVEILLANCE	CAL DA	6	3		3	
70106500	TEMPORARY BRIDGE TRAFFIC SIGNALS	EACH	2	1		1	
70300100	SHORT-TERM PAVEMENT MARKING	FOOT	203	133		70	
70301000	WORK ZONE PAVEMENT MARKING REMOVAL	SQ FT	68	44		24	
70400100	TEMPORARY CONCRETE BARRIER	FOOT	1400	1025		375	
70400200	RELOCATE TEMPORARY CONCRETE BARRIER	FOOT	1325	975		350	

*Specialty Items

FILE NAME =	USER NAME = steffenk	DESIGNED -	REVISED -	STATE OF ILLINOIS DEPARTMENT OF TRANSPORTATION	SUMMARY OF QUANTITIES				F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.		
c:\pwwork\pwwork\STEFFENK\dms50690\74214-sht-soq.dgn		DRAWN -	REVISED -		SCALE:	SHEET NO.	OF	SHEETS	STA.	TO STA.	328	(98R1, 108R1)B1	Wayne	67	4
PLOT SCALE = 50.0000' / IN.		CHECKED -	REVISED -												
PLOT DATE = 1/12/2009		DATE -	REVISED -												