

SUMMARY OF QUANTITIES			80% FED. 20% STATE TOTAL QUANTITIES	CONSTRUCTION TYPE CODE			
CODE NO	ITEM	UNIT		1000-2A	X071-2A	J000-2A	X028-2A
* 78001110	PAINT PAVEMENT MARKING - LINE 4"	FOOT	4567	2992		1575	
* 78100100	RAISED REFLECTIVE PAVEMENT MARKER	EACH	12	10		2	
* 78100105	RAISED REFLECTIVE PAVEMENT MARKER (BRIDGE)	EACH	2	2			
* 78100300	REPLACEMENT REFLECTOR	EACH	18	10		8	
* 78200410	GUARDRAIL MARKERS, TYPE A	EACH	22	14		8	
* 78201000	TERMINAL MARKER - DIRECT APPLIED	EACH	8	4		4	
78300100	PAVEMENT MARKING REMOVAL	SQ FT	964	470		494	
78300200	RAISED REFLECTIVE PAVEMENT MARKER REMOVAL	EACH	10	10			
* 80500105	SERVICE INSTALLATION, TYPE A (MODIFIED)	EACH	1			1	
* 81012500	CONDUIT IN TRENCH, 1 1/2" DIA., PVC	FOOT	35			35	
* 81100500	CONDUIT ATTACHED TO STRUCTURE, 1 1/2" DIA., GALVANIZED STEEL	FOOT	14			14	
* 81900200	TRENCH AND BACKFILL FOR ELECTRICAL WORK	FOOT	35			35	
* 85800100	FLASHER CONTROLLER	EACH	1			1	
* 87301225	ELECTRIC CABLE IN CONDUIT, SIGNAL NO. 14 3C	FOOT	60			60	
* 88040030	SIGNAL HEAD, POLYCARBONATE, LED, 1-FACE, 1-SECTION, POST MOUNTED	EACH	1			1	
* 88200400	TRAFFIC SIGNAL BACKPLATE, FORMED PLASTIC	EACH	1			1	
* 89502400	REMOVE EXISTING FLASHING BEACON INSTALLATION COMPLETE	EACH	1			1	
* A2001016	TREE, ACER RUBRUM (RED MAPLE), 2" CALIPER, BALLED AND BURLAPPED	EACH	5	5			
* A2001716	TREE, ACER SACCHARUM (SUGAR MAPLE), 2" CALIPER, BALLED AND BURLAPPED	EACH	5	5			
* B2001116	TREE, CERCIS CANADENSIS (EASTERN REDBUD) 2" CALIPER, TREE FORM, BALLED AND BURLAPPED	EACH	5	5			
* B2001316	TREE, CORNUS FLORIDA (FLOWERING DOGWOOD), 2" CALIPER, TREE FORM, BALLED AND BURLAPPED	EACH	5	5			
X0322050	RAISED REFLECTIVE PAVEMENT MARKER, REFLECTOR REMOVAL	EACH	18	10		8	
X0323988	TEMPORARY SOIL RETENTION SYSTEM	SQ FT	136		136		
<del>20030250</del>	IMPACT ATTENUATORS, TEMPORARY (NON-REDIRECTIVE), TEST LEVEL 3	EACH	4	2		2	
<del>20030350</del>	IMPACT ATTENUATORS, RELOCATE (NON- REDIRECTIVE), TEST LEVEL 3	EACH	4	2		2	
*Specialty Hems							

Rev.