

PAY CODE NUMBER	ITEM DESCRIPTION	UNIT	TOTAL QUANTITY RURAL	F		
				80% FEDERAL 20% STATE 096-20II X028-2A	80% FEDERAL 20% STATE 096-007I X071-2A	80% FEDERAL 20% STATE 096-0072 X071-2A
20200100	EARTH EXCAVATION	CU YD	4420	355	3000	1065
20300100	CHANNEL EXCAVATION	CU YD	785		315	470
20400800	FURNISHED EXCAVATION	CU YD	9725	30	6705	2990
20700400	POROUS GRANULAR EMBANKMENT, SPECIAL	CU YD	293		170	123
20800150	TRENCH BACKFILL	CU YD	291	192	99	
25000210	SEEDING, CLASS 2A	ACRE	10.00	1.00	5.75	3.25
25000400	NITROGEN FERTILIZER NUTRIENT	POUND	900	90	517.5	292.5
25000500	PHOSPHORUS FERTILIZER NUTRIENT	POUND	900	90	517.5	292.5
25000600	POTASSIUM FERTILIZER NUTRIENT	POUND	900	90	517.5	292.5
25000700	AGRICULTURAL GROUND LIMESTONE	TON	20	2.0	11.5	6.5
25100115	MULCH, METHOD 2	ACRE	10.00	1.00	5.75	3.25
28000250	TEMPORARY EROSION CONTROL SEEDING	POUND	1000	100	575	325
28000300	TEMPORARY DITCH CHECKS	EACH	6	4	2	
28000400	PERIMETER EROSION BARRIER	FOOT	4288	475	2193	1620
28000500	INLET AND PIPE PROTECTION	EACH	12	1	8	3
28100107	STONE RIPRAP, CLASS A4	SQ YD	2018	205	784	1029
28200200	FILTER FABRIC	SQ YD	2018	205	784	1029
31101000	SUB-BASE GRANULAR MATERIAL, TYPE B	TON	4300		2835	1465
35501316	HOT-MIX ASPHALT BASE COURSE, 8"	SQ YD	2673		2673	
35600712	HOT-MIX ASPHALT BASE COURSE WIDENING, 9"	SQ YD	854		414	440
35650700	BASE COURSE WIDENING	SQ YD	1436	285	565	586
40200800	AGGREGATE SURFACE COURSE, TYPE B	TON	568		308	260
40600100	BITUMINOUS MATERIALS (PRIME COAT)	GALLON	1227	87	646	494
40600982	HOT-MIX ASPHALT SURFACE REMOVAL - BUTT JOINT	SQ YD	814	188	280	346
40600990	TEMPORARY RAMP	SQ YD	144	36	54	54
40603085	HOT-MIX ASPHALT BINDER COURSE, IL-19.0, N70	TON	2017.4	294.0	869.2	854.2
40603315	HOT-MIX ASPHALT SURFACE COURSE, MIX "C", N70	TON	693.0	59.8	380.4	252.8
42001165	BRIDGE APPROACH PAVEMENT	SQ YD	424		212	212
42001300	PROTECTIVE COAT	SQ YD	456		228	228
44000100	PAVEMENT REMOVAL	SQ YD	24	24		
44004250	PAVED SHOULDER REMOVAL	SQ YD	852	188	312	352
44004300	PAVEMENT BREAKING	SQ YD	2410		1278	1132
48101200	AGGREGATE SHOULDERS, TYPE B	TON	290	44	246	
48203029	HOT-MIX ASPHALT SHOULDERS, 8"	SQ YD	390		184	206
48203100	HOT-MIX ASPHALT SHOULDERS	TON	167.8		73.5	94.3
50100300	REMOVAL OF EXISTING STRUCTURES NO.1	EACH	1	1		
50100400	REMOVAL OF EXISTING STRUCTURES NO.2	EACH	1		1	
50100500	REMOVAL OF EXISTING STRUCTURES NO.3	EACH	1			1
50105220	PIPE CULVERT REMOVAL	FOOT	247		247	
50200100	STRUCTURE EXCAVATION	CU YD	619	338	173	108
50300225	CONCRETE STRUCTURES	CU YD	119.1		36.4	82.7
50300255	CONCRETE SUPERSTRUCTURE	CU YD	267.5		122.3	145.2
50300260	BRIDGE DECK GROOVING	SQ YD	646		273	373
50300280	CONCRETE ENCASEMENT	CU YD	43.6		5.6	38.0
50300300	PROTECTIVE COAT	SQ YD	853		361	492
50500505	STUD SHEAR CONNECTORS	EACH	3636		1188	2448

* DENOTES SPECIALTY ITEM

FILE NAME = P:\0340601\04.FIN\0960055\Drawings\QuantitiesSummary.dgn	USER NAME = rook	DESIGNED -	REVISED -
PLOT SCALE = 20,000' / IN.	CHECKED -	REVISED -	REVISED -
PLOT DATE = 3/26/2009	DATE -	REVISED -	REVISED -

STATE OF ILLINOIS
DEPARTMENT OF TRANSPORTATION

SUMMARY OF QUANTITIES

SCALE: SHEET NO. 1 OF 3 SHEETS STA. TO STA.

F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
823	(22BY-1,22BY2,22BR)B-1	WAYNE	142	3
FED. ROAD DIST. NO. ILLINOIS FED. AID PROJECT			CONTRACT NO. 74238	