

**PROTECTIVE COAT**

LOCATION	STATION TO	STATION	SQ YD
SN 096-0072	294+55.00	294+85.00	114
SN 096-0072	295+97.00	296+27.00	114
SN 096-0071	300+94.00	301+24.00	114
SN 096-0071	302+06.00	302+36.00	114
TOTAL			456

**PAVEMENT REMOVAL**

LOCATION	STATION TO	STATION	SQ YD
SN 096-2011	239+52.00	239+60.00	24
TOTAL			24

**PAVED SHOULDER REMOVAL**

LOCATION	STATION TO	STATION	OFFSET	SQ YD
SN 096-2011	238+25.00	239+79.00	LT&RT	136
SN 096-2011	240+01.00	241+55.00	LT&RT	52
SN 096-0072	287+00.00	294+98.00	LT&RT	266
SN 096-0072	296+02.00	298+60.00	LT&RT	86
SN 096-0071	298+60.00	300+34.00	LT	29
SN 096-0071	301+29.00	301+44.00	LT	3
SN 096-0071	301+99.00	309+25.00	LT	122
SN 096-0071	298+60.00	301+30.00	RT	45
SN 096-0071	301+84.00	302+69.00	RT	14
SN 096-0071	303+33.00	309+25.00	RT	99
TOTAL				852

**PAVEMENT BREAKING**

LOCATION	STATION TO	STATION	OFFSET	SQ YD
SN 096-0072	292+25.00	294+55.00	RT	281
SN 096-0072	296+27.00	298+60.00	RT	285
SN 096-0072	292+25.00	294+55.00	LT	281
SN 096-0072	296+27.00	298+60.00	LT	285
SN 096-0071	298+60.00	300+94.00	RT	286
SN 096-0071	302+36.00	305+25.00	RT	353
SN 096-0071	298+60.00	300+94.00	LT	286
SN 096-0071	302+36.00	305+25.00	LT	353
TOTAL				2410

**AGGREGATE SHOULDERS, TYPE B**

LOCATION	STATION TO	STATION	OFFSET	TON
SN 096-2011	238+25.00	241+55.00	RT	22
SN 096-2011	238+25.00	241+55.00	LT	22
DITCH BANK N.	1+00.00	5+00.00	LT	60
DITCH BANK N.	1+33.00	5+00.00	RT	53
DITCH BANK S.	45+25.00	49+67.00	LT	63
DITCH BANK S.	45+25.00	50+00.00	RT	70
TOTAL				290

**HOT-MIX ASPHALT SHOULDERS, 8"**

LOCATION	STATION TO	STATION	OFFSET	SQ YD
SN 096-0072	292+25.00	294+55.00	LT	102
SN 096-0072	296+27.00	298+60.00	LT	104
SN 096-0071	298+60.00	299+65.00	LT	47
SN 096-0071	300+74.00	301+03.00	LT	13
SN 096-0071	302+45.00	305+25.00	LT	124
TOTAL				390

**HOT-MIX ASPHALT SHOULDERS**

LOCATION	STATION TO	STATION	OFFSET	TON
SN 096-0072	288+41.59	292+25.00	LT	94.3
SN 096-0071	305+25.00	308+20.00	LT	73.5
TOTAL				167.8

**TEMPORARY PAVEMENT MARKING - LINE 4"**

LOCATION	STATION TO	STATION	OFFSET	FOOT
SN 096-2011	238+49.00	241+32.00	LT&RT	566
SN 096-2011	238+57.00	241+26.00	LT&RT	538
SN 096-2011	238+25.00	241+55.00	LT&RT	739
SN 096-0072	285+92.73	298+60.00	LT&RT	2422
SN 096-0072	285+79.87	298+60.00	LT&RT	2440
SN 096-0072	287+00.00	298+60.00	LT&RT	2610
SN 096-0071	298+60.00	311+57.20	LT&RT	2439
SN 096-0071	298+60.00	311+06.58	LT&RT	2368
SN 096-0071	298+60.00	309+25.00	LT&RT	2085
TOTAL				16207

**WORKZONE PAVEMENT MARKING REMOVAL**

LOCATION	STATION TO	STATION	OFFSET	SQ FT
SN 096-2011	238+49.00	241+32.00	LT&RT	189
SN 096-2011	238+57.00	241+26.00	LT&RT	179
SN 096-2011	238+25.00	241+55.00	LT&RT	246
SN 096-0072	285+92.73	298+60.00	LT&RT	807
SN 096-0072	285+79.87	298+60.00	LT&RT	813
SN 096-0072	287+00.00	298+60.00	LT&RT	870
SN 096-0071	298+60.00	311+57.20	LT&RT	813
SN 096-0071	298+60.00	311+06.58	LT&RT	789
SN 096-0071	298+60.00	309+25.00	LT&RT	695
TOTAL				5401

**THERMOPLASTIC PAVEMENT MARKING - LINE 4"**

LOCATION	STATION TO	STATION	OFFSET	FOOT
SN 096-2011	238+25.00	241+55.00	LT&RT	739
SN 096-0072	287+00.00	298+60.00	LT&RT	2610
SN 096-0071	298+60.00	309+25.00	LT&RT	2085
TOTAL				5434

**RAISED REFLECTIVE PAVEMENT MARKERS**

LOCATION	STATION TO	STATION	EACH
SN 096-2011	238+25.00	241+55.00	4
SN 096-0072	287+00.00	298+60.00	15
SN 096-0071	298+60.00	309+25.00	13
TOTAL			32

**GUARDRAIL MARKERS & BARRIER WALL MARKERS**

	STATION TO	OFFSET	GUARDRAIL MARKERS	BARRIER WALL MARKERS
SN 096-0072				
BEGIN STA.	292+04.35	RT		
END STA.	298+44.35	RT	7	1
BEGIN STA.	293+04.35	LT		
END STA.	298+77.65	LT	6	1
SN 096-0071				
BEGIN STA.	299+24.35	RT		
END STA.	2+22.88	RT	5	1
BEGIN STA.	48+77.18	LT		
END STA.	304+96.13	LT	5	1
TOTAL			23	4

**TERMINAL MARKER - DIRECT APPLIED**

LOCATION	STATION	OFFSET	EACH
SN 096-0072	292+04.35	RT	1
SN 096-0072	293+04.35	LT	1
SN 096-0072	298+77.65	LT	1
DITCH BANK N.	2+22.88	RT	1
DITCH BANK S.	48+77.18	LT	1
SN 096-0071	304+96.13	LT	1
TOTAL			6

**BRIDGE APPROACH PAVEMENT REMOVAL**

LOCATION	STATION TO	STATION	SQ YD
SN 096-2011	239+60.00	239+80.00	53
SN 096-2011	240+00.00	240+20.00	53
SN 096-0072	294+78.00	294+98.00	53
SN 096-0072	296+02.00	296+22.00	53
SN 096-0071	301+14.54	301+34.54	53
SN 096-0071	301+90.16	302+10.16	53
TOTAL			318

**SECTION CORNERS**

STATION	OFFSET	DESCRIPTION
289+04.59	0.00' LT/RT	NE, COR
		NE 1/4, SE 1/4
		2-2-9