

901.FED./101.STATE

PAY CODE NUMBER	ITEM DESCRIPTION	UNIT	TOTAL QUANTITY TWO-LANE RURAL ROADWAY J000-1A
20200100	EARTH EXCAVATION	CU YD	545
2101505	TOPSOIL EXCAVATION AND PLACEMENT	CU YD	225
25000210	SEEDING, CLASS 2A	ACRE	0.50
25000400	NITROGEN FERTILIZER NUTRIENT	POUND	45
25000500	PHOSPHORUS FERTILIZER NUTRIENT	POUND	45
25000600	POTASSIUM FERTILIZER NUTRIENT	POUND	45
25100115	MULCH, METHOD 2	ACRE	0.50
28000250	TEMPORARY EROSION CONTROL SEEDING	POUND	50
28000300	TEMPORARY DITCH CHECKS	EACH	2
28000400	PERIMETER EROSION BARRIER	FOOT	767
30200650	PROCESSING MODIFIED SOIL 12"	SQ YD	1106
31001500	LIME	TON	27.7
35300500	PORTLAND CEMENT CONCRETE BASE COURSE 10"	SQ YD	947
40600100	BITUMINOUS MATERIALS (PRIME COAT)	GALLON	134
40603340	HOT-MIX ASPHALT SURFACE COURSE, MIX "D", N70	TON	150
44000155	HOT-MIX ASPHALT SURFACE REMOVAL, 1 1/2"	SQ YD	738
44004250	PAVED SHOULDER REMOVAL	SQ YD	294
48203029	HOT-MIX ASPHALT SHOULDERS, 8"	SQ YD	234
60600095	CLASS SICRETE (OUTLET)	CU YD	11
60605000	COMBINATION CONCRETE CURB AND GUTTER, TYPE B-6.24	FOOT	165
66600105	FURNISHING AND ERECTING RIGHT-OF-WAY MARKERS	EACH	4
67000500	ENGINEER'S FIELD OFFICE, TYPE B	CAL MC	1
67100100	MOBILIZATION	L SUM	1
70100460	TRAFFIC CONTROL AND PROTECTION, STANDARD 701306	L SUM	1
70100500	TRAFFIC CONTROL AND PROTECTION, STANDARD 701326	L SUM	1
70103815	TRAFFIC CONTROL SURVEILLANCE	CAL DA	19
70300210	TEMPORARY PAVEMENT MARKING - LETTERS AND SYMBOLS	SQ FT	53
70300220	TEMPORARY PAVEMENT MARKING - LINE 4"	FOOT	844
70300250	TEMPORARY PAVEMENT MARKING - LINE 8"	FOOT	1168
70300260	TEMPORARY PAVEMENT MARKING - LINE 12"	FOOT	535

901.FED./101.STATE

PAY CODE NUMBER	ITEM DESCRIPTION	UNIT	TOTAL QUANTITY TWO-LANE RURAL ROADWAY J000-1A
78000100	THERMOPLASTIC PAVEMENT MARKING - LETTERS AND SYMBOLS	SQ FT	53
78000200	THERMOPLASTIC PAVEMENT MARKING - LINE 4"	FOOT	844
78000500	THERMOPLASTIC PAVEMENT MARKING - LINE 8"	FOOT	1168
78000600	THERMOPLASTIC PAVEMENT MARKING - LINE 12"	FOOT	535
78100100	RAISED REFLECTIVE PAVEMENT MARKER	EACH	21
78300100	PAVEMENT MARKING REMOVAL	SQ FT	90

* DENOTES SPECIALTY ITEM

FILE NAME =	USER NAME = mook1ag	DESIGNED -	REVISED -	STATE OF ILLINOIS DEPARTMENT OF TRANSPORTATION	SUMMARY OF QUANTITIES				F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
P:\2348782\hutsorville\Drawings\QuantitiesSummary.dgn		DRAWN -	REVISED -						332	22N	CRAWFORD	22	3
PLOT SCALE = 20,000 // IN.		CHECKED -	REVISED -		SCALE: SHEET NO. OF SHEETS STA. TO STA.				FED. ROAD DIST. NO. [ILLINOIS] FED. AID PROJECT				
PLOT DATE = 12/16/2008		DATE -	REVISED -						CONTRACT NO. 74300				