



Illinois Department of Transportation

2300 South Dirksen Parkway / Springfield, Illinois / 62764

August 31, 2009

SUBJECT: FAI Route 70 (I-55/70)
Project IM-070-1 (183)011
Section 60-(7,8,9,10)RS,60-(8,9,10)BR
Madison County
Contract No. 76A73
Item No. 102, September 18 2009 Letting
Addendum A

NOTICE TO PROSPECTIVE BIDDERS:

Attached is an addendum to the plans or proposal. This addendum involves revised and/or added material.

1. Replaced the Schedule of Prices.
2. Revised sheets 2, 2A, 3, 7 and 7A of the Plans.
3. Added sheet 21A to the Plans.
4. Revised pages ii & iii of the Table of Contents to the Special Provisions.
5. Added page iv to the Table of Contents to the Special Provisions.
6. Revised pages 116 and 117 of the Special Provisions.

Prime contractors must utilize the enclosed material when preparing their bid and must include any Schedule of Prices changes in their bidding proposal.

Bidders using computer-generated bids are cautioned to reflect any and all Schedule of Prices changes, if involved, into their computer programs.

Very truly yours,

Charles Ingersoll, Chief
Bureau of Design and Environment

A handwritten signature in cursive script, reading "Ted B. Walschleger" followed by a small "P.E." to the right.

By: Ted B. Walschleger, P. E.
Engineer of Project Management

cc: Mary C. Lamie, Region 5, District 8; Bill Frey; R. E. Anderson; Estimates

TBW:DB:jc

ILLINOIS DEPARTMENT OF TRANSPORTATION
 SCHEDULE OF PRICES
 CONTRACT
 NUMBER - 76A73

State Job # - C-98-046-07
 PPS NBR - 8-82082-0000
 County Name - MADISON -
 Code - 119 - -
 District - 8 - -
 Section Number - 60-(7,8,9,10)RS,60-(8,9,10)BR

Project Number
 IM-070-1/183/011

Route
 FAI 70

* REVISED : AUGUST 31, 2009

Item Number	Pay Item Description	Unit of Measure	Quantity	x	Unit Price	=	Total Price
X0321743	SILICONE JT SEAL 1	FOOT	228.000				
* DELETED							
X0322935	PIPE CULVERTS CLEANED	EACH	1.000				
X0323077	SILICONE JT SEAL 2.75	FOOT	212.000				
X0323150	JUN BX AL AS 18X18X10	EACH	11.000				
X0324632	SILICONE JT SEALER SP	FOOT	46.000				
X0325476	RADAR VEH DETECT SYST	EACH	11.000				
X0325922	CELLULAR MODEM	EACH	11.000				
X0326091	LP 50 W/CAM LOW SYS	EACH	8.000				
X0326678	REPL CATHOD PROT RECT	EACH	1.000				
* X0326692	MOT AID CALL BOX REM	EACH	20.000				
X0349800	CONC HDWL - P UNDR RM	EACH	384.000				
X4066580	POL HMA SC SMA N80	TON	32,994.000				
X4400220	CURB REM & REPLACMT	FOOT	1,545.000				
X7330105	OSS WALKWAY TY A	FOOT	30.000				

ILLINOIS DEPARTMENT OF TRANSPORTATION
 SCHEDULE OF PRICES
 CONTRACT
 NUMBER - 76A73

State Job # - C-98-046-07
 PPS NBR - 8-82082-0000
 County Name - MADISON -
 Code - 119 - -
 District - 8 - -
 Section Number - 60-(7,8,9,10)RS,60-(8,9,10)BR

Project Number
 IM-070-1/183/011

Route
 FAI 70

* REVISED : AUGUST 31, 2009

Item Number	Pay Item Description	Unit of Measure	Quantity	x	Unit Price	=	Total Price
X8100065	CON T 4 PVC TY C	FOOT	330.000				
Z0005300	BOX CUL TO BE CLEANED	EACH	1.000				
Z0017202	DOWEL BARS 1 1/2	EACH	623.000				
Z0029999	IMPACT ATTENUATOR REM	EACH	4.000				
Z0030150	IMPACT ATTEN NRD TL3	EACH	4.000				
Z0040530	PIPE UNDERDRAIN REMOV	FOOT	199,240.000				
Z0050900	REM CONC FDN	EACH	6.000				
Z0075310	TIE BARS 3/4	EACH	1,330.000				
Z0076600	TRAINEES	HOUR	2,500.000		0.800		2,000.000
20100500	TREE REMOV ACRES	ACRE	6.820				
20400800	FURNISHED EXCAV	CU YD	105.000				
21400100	GRADING & SHAP DITCH	FOOT	900.000				
25000200	SEEDING CL 2	ACRE	7.070				
25100115	MULCH METHOD 2	ACRE	7.070				
28000250	TEMP EROS CONTR SEED	POUND	707.000				

ILLINOIS DEPARTMENT OF TRANSPORTATION
 SCHEDULE OF PRICES
 CONTRACT
 NUMBER - 76A73

State Job # - C-98-046-07
 PPS NBR - 8-82082-0000
 County Name - MADISON -
 Code - 119 - -
 District - 8 - -
 Section Number - 60-(7,8,9,10)RS,60-(8,9,10)BR

Project Number
 IM-070-1/183/011

Route
 FAI 70

* REVISED : AUGUST 31, 2009

Item Number	Pay Item Description	Unit of Measure	Quantity	x	Unit Price	=	Total Price
28100101	STONE RIPRAP CL A1	SQ YD	12.000				
28100107	STONE RIPRAP CL A4	SQ YD	261.000				
28100705	STONE DUMP RIP CL A3	SQ YD	178.000				
28200200	FILTER FABRIC	SQ YD	273.000				
31100700	SUB GRAN MAT A 8	SQ YD	3,407.000				
35300720	PCC BSE CSE 13	SQ YD	2,904.000				
40600200	BIT MATLS PR CT	TON	134.400				
40600300	AGG PR CT	TON	641.800				
* 40600645	LEV BIND MM N90	TON	2,908.000				
* DELETED							
40600895	CONSTRUC TEST STRIP	EACH	2.000				
40600982	HMA SURF REM BUTT JT	SQ YD	928.000				
40600990	TEMPORARY RAMP	SQ YD	1,152.000				
40603240	P HMA BC IL19.0 N90	TON	29,019.000				
40800050	INCIDENTAL HMA SURF	TON	21.000				

ILLINOIS DEPARTMENT OF TRANSPORTATION
 SCHEDULE OF PRICES
 CONTRACT
 NUMBER - 76A73

State Job # - C-98-046-07
 PPS NBR - 8-82082-0000
 County Name - MADISON - -
 Code - 119 - -
 District - 8 - -
 Section Number - 60-(7,8,9,10)RS,60-(8,9,10)BR

Project Number
 IM-070-1/183/011

Route
 FAI 70

* REVISED : AUGUST 31, 2009

Item Number	Pay Item Description	Unit of Measure	Quantity	x	Unit Price	=	Total Price
44000153	HMA SURF REM 1	SQ YD	35,912.000				
44000158	HMA SURF REM 2 1/4	SQ YD	239,616.000				
44000161	HMA SURF REM 3	SQ YD	15,681.000				
44000198	HMA SURF REM VAR DP	SQ YD	1,286.000				
44004250	PAVED SHLD REMOVAL	SQ YD	2,341.000				
44201031	CL B PATCH T2 15	SQ YD	77.100				
44201035	CL B PATCH T3 15	SQ YD	330.000				
44201037	CL B PATCH T4 15	SQ YD	350.100				
44201903	CL D PATCH T3 21	SQ YD	40.000				
44213100	PAVEMENT FABRIC	SQ YD	680.100				
44213200	SAW CUTS	FOOT	2,294.000				
45200300	JT OR CRACK FILLING	POUND	192.000				
48101200	AGGREGATE SHLDS B	TON	2,361.000				
48203029	HMA SHOULDERS 8	SQ YD	2,075.000				
48203100	HMA SHOULDERS	TON	17,909.000				

ILLINOIS DEPARTMENT OF TRANSPORTATION
 SCHEDULE OF PRICES
 CONTRACT
 NUMBER - 76A73

State Job # - C-98-046-07
 PPS NBR - 8-82082-0000
 County Name - MADISON - -
 Code - 119 - -
 District - 8 - -
 Section Number - 60-(7,8,9,10)RS,60-(8,9,10)BR

Project Number
 IM-070-1/183/011

Route
 FAI 70

* REVISED : AUGUST 31, 2009

Item Number	Pay Item Description	Unit of Measure	Quantity	x	Unit Price	=	Total Price
50104650	SLOPE WALL REMOV	SQ YD	2.000				
50105225	PIPE CULVERT REM SPL	FOOT	50.000				
50200100	STRUCTURE EXCAVATION	CU YD	3.000				
50500405	F & E STRUCT STEEL	POUND	3,260.000				
50500715	JACK & REM EX BEARING	EACH	16.000				
51100100	SLOPE WALL 4	SQ YD	2.000				
52000340	NEOPRENE EXPAN JT 4	FOOT	178.000				
52100010	ELAST BEARING ASSY T1	EACH	16.000				
52100520	ANCHOR BOLTS 1	EACH	72.000				
54213669	PRC FLAR END SEC 24	EACH	1.000				
54247130	GRATING-C FL END S 24	EACH	1.000				
54248510	CONCRETE COLLAR	CU YD	1.000				
58700300	CONCRETE SEALER	SQ FT	72,692.000				
59200101	BRIDGE WASHING N1	EACH	1.000				
59200102	BRIDGE WASHING N2	EACH	1.000				

ILLINOIS DEPARTMENT OF TRANSPORTATION
 SCHEDULE OF PRICES
 CONTRACT
 NUMBER - 76A73

State Job # - C-98-046-07
 PPS NBR - 8-82082-0000
 County Name - MADISON -
 Code - 119 - -
 District - 8 - -
 Section Number - 60-(7,8,9,10)RS,60-(8,9,10)BR

Project Number
 IM-070-1/183/011

Route
 FAI 70

* REVISED : AUGUST 31, 2009

Item Number	Pay Item Description	Unit of Measure	Quantity	x	Unit Price	=	Total Price
59200103	BRIDGE WASHING N3	EACH	1.000				
59200104	BRIDGE WASHING N4	EACH	1.000				
59200105	BRIDGE WASHING N5	EACH	1.000				
59200106	BRIDGE WASHING N6	EACH	1.000				
59200107	BRIDGE WASHING N7	EACH	1.000				
59200108	BRIDGE WASHING N8	EACH	1.000				
59300100	CONTR LOW-STRENG MATL	CU YD	10.000				
60100060	CONC HDWL FOR P DRAIN	EACH	384.000				
60100074	SHOULDER REM & REPL 8	FOOT	36,330.000				
60100081	SHOULDER REM/REPL 12	FOOT	155,055.000				
60107600	PIPE UNDERDRAINS 4	FOOT	191,580.000				
60108100	PIPE UNDERDRAIN 4 SP	FOOT	7,660.000				
60260100	INLETS ADJUST	EACH	2.000				
63000001	SPBGR TY A 6FT POSTS	FOOT	23,237.500				
63100045	TRAF BAR TERM T2	EACH	24.000				

ILLINOIS DEPARTMENT OF TRANSPORTATION
 SCHEDULE OF PRICES
 CONTRACT
 NUMBER - 76A73

State Job # - C-98-046-07
 PPS NBR - 8-82082-0000
 County Name - MADISON -
 Code - 119 - -
 District - 8 - -
 Section Number - 60-(7,8,9,10)RS,60-(8,9,10)BR

Project Number
 IM-070-1/183/011

Route
 FAI 70

* REVISED : AUGUST 31, 2009

Item Number	Pay Item Description	Unit of Measure	Quantity	x	Unit Price	=	Total Price
63100070	TRAF BAR TERM T5	EACH	3.000				
63100085	TRAF BAR TERM T6	EACH	6.000				
63100087	TRAF BAR TERM T6A	EACH	3.000				
63100089	TRAF BAR TERM T6B	EACH	9.000				
63100167	TR BAR TRM T1 SPL TAN	EACH	36.000				
63200310	GUARDRAIL REMOV	FOOT	20,032.000				
63500105	DELINEATORS	EACH	877.000				
63500120	DELINEATOR REMOVAL	EACH	877.000				
64200105	SHOULDER RUMBLE STRIP	FOOT	140,153.000				
66500105	WOV W FENCE 4	FOOT	4,700.000				
66500305	WOV W GATE 4X4 SINGL	EACH	1.000				
67000400	ENGR FIELD OFFICE A	CAL MO	12.000				
67100100	MOBILIZATION	L SUM	1.000				
70100420	TRAF CONT-PROT 701411	EACH	27.000				
70100450	TRAF CONT-PROT 701201	L SUM	1.000				

ILLINOIS DEPARTMENT OF TRANSPORTATION
 SCHEDULE OF PRICES
 CONTRACT
 NUMBER - 76A73

State Job # - C-98-046-07
 PPS NBR - 8-82082-0000
 County Name - MADISON -
 Code - 119 - -
 District - 8 - -
 Section Number - 60-(7,8,9,10)RS,60-(8,9,10)BR

Project Number
 IM-070-1/183/011

Route
 FAI 70

* REVISED : AUGUST 31, 2009

Item Number	Pay Item Description	Unit of Measure	Quantity	x	Unit Price	=	Total Price
70100700	TRAF CONT-PROT 701406	L SUM	1.000				
70100800	TRAF CONT-PROT 701401	L SUM	1.000				
70100825	TRAF CONT-PROT 701456	L SUM	1.000				
70103815	TR CONT SURVEILLANCE	CAL DA	120.000				
70106301	TC-PROT 701601 LOC 1	L SUM	1.000				
70106302	TC-PROT 701601 LOC 2	L SUM	1.000				
70106800	CHANGEABLE MESSAGE SN	CAL MO	156.000				
70300100	SHORT-TERM PAVT MKING	FOOT	22,104.000				
70300220	TEMP PVT MK LINE 4	FOOT	35,979.000				
70300240	TEMP PVT MK LINE 6	FOOT	164,263.000				
70300250	TEMP PVT MK LINE 8	FOOT	17,704.000				
70300260	TEMP PVT MK LINE 12	FOOT	484.000				
70300280	TEMP PVT MK LINE 24	FOOT	16.000				
70301000	WORK ZONE PAVT MK REM	SQ FT	108,900.000				
72000100	SIGN PANEL T1	SQ FT	585.000				

ILLINOIS DEPARTMENT OF TRANSPORTATION
 SCHEDULE OF PRICES
 CONTRACT
 NUMBER - 76A73

State Job # - C-98-046-07
 PPS NBR - 8-82082-0000
 County Name - MADISON -
 Code - 119 - -
 District - 8 - -
 Section Number - 60-(7,8,9,10)RS,60-(8,9,10)BR

Project Number
 IM-070-1/183/011

Route
 FAI 70

* REVISED : AUGUST 31, 2009

Item Number	Pay Item Description	Unit of Measure	Quantity	x	Unit Price	=	Total Price
72000300	SIGN PANEL T3	SQ FT	4,477.750				
72400330	REMOV SIGN PANEL T3	SQ FT	4,477.750				
72900200	METAL POST TY B	FOOT	624.000				
73300200	OVHD SIN STR-SPAN T2A	FOOT	60.000				
73600100	REMOV OH SIN STR-SPAN	EACH	2.000				
78000100	THPL PVT MK LTR & SYM	SQ FT	664.000				
78000200	THPL PVT MK LINE 4	FOOT	34,881.000				
78000400	THPL PVT MK LINE 6	FOOT	157,520.000				
78000500	THPL PVT MK LINE 8	FOOT	16,567.000				
78000600	THPL PVT MK LINE 12	FOOT	484.000				
78000650	THPL PVT MK LINE 24	FOOT	16.000				
78003130	PREF PL PM TB LINE 6	FOOT	20,710.000				
78003140	PREF PL PM TB LINE 8	FOOT	230.000				
78008210	POLYUREA PM T1 LN 4	FOOT	1,098.000				
78008230	POLYUREA PM T1 LN 6	FOOT	6,743.000				

ILLINOIS DEPARTMENT OF TRANSPORTATION
 SCHEDULE OF PRICES
 CONTRACT
 NUMBER - 76A73

State Job # - C-98-046-07
 PPS NBR - 8-82082-0000
 County Name - MADISON - -
 Code - 119 - -
 District - 8 - -
 Section Number - 60-(7,8,9,10)RS,60-(8,9,10)BR

Project Number
 IM-070-1/183/011

Route
 FAI 70

* REVISED : AUGUST 31, 2009

Item Number	Pay Item Description	Unit of Measure	Quantity	x	Unit Price	=	Total Price
78008240	POLYUREA PM T1 LN 8	FOOT	1,137.000				
78100100	RAISED REFL PAVT MKR	EACH	2,332.000				
78100105	RAISED REF PVT MKR BR	EACH	16.000				
78200410	GUARDRAIL MKR TYPE A	EACH	212.000				
78201000	TERMINAL MARKER - DA	EACH	36.000				
78300200	RAISED REF PVT MK REM	EACH	1,276.000				
80300100	LOCATE UNDERGR CABLE	FOOT	83,430.000				
80500100	SERV INSTALL TY A	EACH	11.000				
81012500	CON T 1 1/2 PVC	FOOT	2,670.000				
81012800	CON T 3 PVC	FOOT	130.000				
81018400	CON P 1 1/2 GALVS	FOOT	385.000				
81100800	CON AT ST 3 GALVS	FOOT	20.000				
81400700	HANDHOLE PCC	EACH	14.000				
81400720	DBL HANDHOLE PCC	EACH	11.000				
81702130	EC C XLP USE 1C 6	FOOT	1,344.000				

ILLINOIS DEPARTMENT OF TRANSPORTATION
 SCHEDULE OF PRICES
 CONTRACT
 NUMBER - 76A73

State Job # - C-98-046-07
 PPS NBR - 8-82082-0000
 County Name - MADISON- -
 Code - 119 - -
 District - 8 - -
 Section Number - 60-(7,8,9,10)RS,60-(8,9,10)BR

Project Number
 IM-070-1/183/011

Route
 FAI 70

* REVISED : AUGUST 31, 2009

Item Number	Pay Item Description	Unit of Measure	Quantity	x	Unit Price	=	Total Price
81900200	TR & BKFIL F ELECT WK	FOOT	2,800.000				
83012400	LT P A 45MH TEN MT	EACH	3.000				
83600200	LIGHT POLE FDN 24D	FOOT	146.000				
84200500	REM EX LT UNIT SALV	EACH	14.000				
86300305	CONT CAB TYPE III SPL	EACH	11.000				
87000105	ECA C EPRTC 2C 10#10G	FOOT	330.000				
87301715	ELCBL C COMM 18 6PR	FOOT	240.000				
87800210	CONC FDN TY D SPL	FOOT	44.000				

TRAINING AND INSTALLATION..... 33

WARRANTY..... 34

FINAL SYSTEM ACCEPTANCE 34

STATUS OF UTILITIES TO BE ADJUSTED 35

JACK AND REMOVE EXISTING BEARINGS 35

CLEANING AND PAINTING CONTACT SURFACE AREAS OF EXISTING STEEL STRUCTURES..... 37

CLEANING AND PAINTING NEW METAL STRUCTURES..... 42

CONTAINMENT AND DISPOSAL OF LEAD PAINT CLEANING RESIDUES..... 49

SILICONE BRIDGE JOINT SEALER..... 70

BRIDGE DECK CONCRETE SEALER..... 73

ALKALI-SILICA REACTION FOR CAST-IN-PLACE CONCRETE (BDE) 73

ALKALI-SILICA REACTION FOR PRECAST AND PRECAST PRESTRESSED CONCRETE (BDE)..... 76

APPROVAL OF PROPOSED BORROW AREAS, USE AREAS, AND/OR WASTE AREAS INSIDE ILLINOIS STATE BORDERS (BDE) 79

CEMENT (BDE) 79

CONCRETE ADMIXTURES (BDE) 82

CONCRETE JOINT SEALER (BDE) 84

CONCRETE MIX DESIGNS (BDE) 85

CONSTRUCTION AIR QUALITY - DIESEL VEHICLE EMISSIONS CONTROL (BDE) 87

CONSTRUCTION AIR QUALITY - IDLING RESTRICTIONS (BDE)..... 88

DETERMINATION OF THICKNESS (BDE)..... 89

DISADVANTAGED BUSINESS ENTERPRISE PARTICIPATION (BDE) 100

DOWEL BARS (BDE) 107

ENGINEER’S FIELD OFFICE TYPE A (BDE) 107

EQUIPMENT RENTAL RATES (BDE)..... 110

FLAGGER AT SIDE ROADS AND ENTRANCES (BDE) 111

HOT-MIX ASPHALT - FIELD VOIDS IN THE MINERAL AGGREGATE (BDE)..... 111

HOT-MIX ASPHALT – PLANT TEST FREQUENCY (BDE) 113

HOT-MIX ASPHALT – TRANSPORTATION (BDE) 114

IMPACT ATTENUATORS (BDE)..... 114

LIQUIDATED DAMAGES (BDE)..... 116

METAL HARDWARE CAST INTO CONCRETE (BDE)..... 117

MULTILANE PAVEMENT PATCHING (BDE)..... 118

NATIONAL POLLUTANT DISCHARGE ELIMINATION SYSTEM / EROSION AND SEDIMENT CONTROL DEFICIENCY DEDUCTION (BDE) 118

Revised 08/31/2009

NOTCHED WEDGE LONGITUDINAL JOINT (BDE)..... 119

PARTIAL EXIT RAMP CLOSURE FOR FREEWAY/EXPRESSWAY (BDE) 120

PAYMENTS TO SUBCONTRACTORS (BDE) 121

PAYROLLS AND PAYROLL RECORDS (BDE) 122

PERSONAL PROTECTIVE EQUIPMENT (BDE) 123

PLASTIC BLOCKOUTS FOR GUARDRAIL (BDE) 123

POLYUREA PAVEMENT MARKING (BDE)..... 124

POST CLIPS FOR EXTRUDED ALUMINUM SIGNS (BDE) 131

PRECAST CONCRETE HANDLING HOLES (BDE) 131

PUBLIC CONVENIENCE AND SAFETY (BDE) 133

RECLAIMED ASPHALT PAVEMENT (RAP) (BDE) 133

REFLECTIVE SHEETING ON CHANNELIZING DEVICES (BDE) 139

REINFORCEMENT BARS (BDE) 140

REINFORCEMENT BARS - STORAGE AND PROTECTION (BDE)..... 141

RETROREFLECTIVE SHEETING, NONREFLECTIVE SHEETING, AND TRANSLUCENT OVERLAY
 FILM FOR HIGHWAY SIGNS (BDE) 142

SELF-CONSOLIDATING CONCRETE FOR CAST-IN-PLACE CONSTRUCTION (BDE)..... 148

SELF-CONSOLIDATING CONCRETE FOR PRECAST PRODUCTS (BDE)..... 152

SIGN PANELS AND SIGN PANEL OVERLAYS (BDE) 153

SILT FILTER FENCE (BDE) 154

STEEL PLATE BEAM GUARDRAIL (BDE) 154

STONE GRADATION TESTING (BDE)..... 154

SUBCONTRACTOR MOBILIZATION PAYMENTS (BDE) 154

SURFACE TESTING OF PAVEMENTS (BDE) 155

TEMPORARY EROSION CONTROL (BDE) 161

THERMOPLASTIC PAVEMENT MARKINGS (BDE) 162

TRAINING SPECIAL PROVISIONS 163

TYPE ZZ RETROREFLECTIVE SHEETING, NONREFLECTIVE SHEETING, AND TRANSLUCENT
 OVERLAY FILM FOR HIGHWAY SIGNS (BDE) 165

WOVEN WIRE FENCE (BDE) 170

BITUMINOUS MATERIALS COST ADJUSTMENTS (BDE) (RETURN FORM WITH BID) 170

FUEL COST ADJUSTMENT (BDE) (RETURN FORM WITH BID) 173

STEEL COST ADJUSTMENT (BDE) (RETURN FORM WITH BID) 177

Revised 08/31/2009

404 PERMIT SN 060-2002 181
404 PERMIT SN 060-2544 198
NATIONWIDE PERMITS AND CONDITIONS..... 215
IEPA REGIONAL CONDITIONS..... 228

Added 08/31/2009

Basis of Payment. This work, will be paid for at the contract unit price per each for IMPACT ATTENUATORS (FULLY REDIRECTIVE, NARROW); IMPACT ATTENUATORS (FULLY REDIRECTIVE, WIDE); IMPACT ATTENUATORS (FULLY REDIRECTIVE, RESETTABLE); IMPACT ATTENUATORS (SEVERE USE, NARROW); IMPACT ATTENUATORS (SEVERE USE, WIDE); IMPACT ATTENUATORS (PARTIALLY REDIRECTIVE); or IMPACT ATTENUATORS (NON-REDIRECTIVE), of the test level specified.

Sand module attenuator bases will be paid for at the contract unit price per square yard (square meter) for ATTENUATOR BASE.

Regrading of slopes or approaches will be paid for according to Section 202 and/or Section 204 of the Standard Specifications.

LIQUIDATED DAMAGES (BDE)

Effective: April 1, 2009

Revise the table in Article 108.09 of the Standard Specifications to read:

"Schedule of Deductions for Each Day of Overrun in Contract Time			
Original Contract Amount		Daily Charges	
From More Than	To and Including	Calendar Day	Work Day
\$ 0	\$ 100,000	\$ 375	\$ 500
100,000	500,000	625	875
500,000	1,000,000	1,025	1,425
1,000,000	3,000,000	1,125	1,550
3,000,000	5,000,000	1,425	1,950
5,000,000	10,000,000	1,700	2,350
10,000,000	And over	3,325	4,650"

Revised 08/31/2009

METAL HARDWARE CAST INTO CONCRETE (BDE)

Effective: April 1, 2008

Revised: April 1, 2009

Add the following to Article 503.02 of the Standard Specifications:

“(g) Metal Hardware Cast into Concrete 1006.13”

Revised 08/31/2009