

# SUMMARY OF QUANTITIES

SUMMARY OF QUANTITIES			URBAN 90/10 FEM/ST TOTAL QUANTITIES	CONSTRUCTION TYPE CODE								
				MAINLINE ROADWAY 1000	TR 162 E 060-0172 SFTY-2A	IL 159 060-0269 SFTY-2A	I-55/70 060-0018/19 SFTY-2A	US 40 060-0267 SFTY-2A	I-70 WB 060-0022 SFTY-2A	I-270 EB/WB 060-0057/58 SFTY-2A	SIGNS Y002-1C	ITS Y032-1F
CODE NO	ITEM	UNIT										
20100500	TREE REMOVAL, ACRES	ACRE	6.82	6.82								
20400800	FURNISHED EXCAVATION	CU YD	105	105								
21400100	GRADING AND SHAPING DITCHES	FOOT	900	900								
25000200	SEEDING, CLASS 2	ACRE	7.07	7.07								
25100115	MULCH, METHOD 2	ACRE	7.07	7.07								
28000250	TEMPORARY EROSION CONTROL SEEDING	POUND	707	707								
28100101	STONE RIPRAP, CLASS A1	SQ YD	12			12						
28100107	STONE RIPRAP, CLASS A4	SQ YD	261	261								
28100705	STONE DUMPED RIPRAP, CLASS A3	SQ YD	178	178								
28200200	FILTER FABRIC	SQ YD	273	261		12						
31100700	SUB-BASE GRANULAR MATERIAL, TYPE A 8"	SQ YD	3407	3407								
35300720	PORTLAND CEMENT CONCRETE BASE COURSE 13"	SQ YD	2904	2904								
40600200	BITUMINOUS MATERIALS (PRIME COAT)	TON	134.4	134.4								
40600300	AGGREGATE (PRIME COAT)	TON	641.8	641.8								
40600645	LEVELING BINDER (MACHINE METHOD), N90	TON	2908	2908								
40600895	CONSTRUCTING TEST STRIP	EACH	2	2								
40600982	HOT-MIX ASPHALT SURFACE REMOVAL - BUTT JOINT	SQ YD	928	928								
40600990	TEMPORARY RAMP	SQ YD	1152	1152								
40603240	POLYMERIZED HOT-MIX ASPHALT BINDER COURSE, IL-19.0, N90	TON	29019	29019								
40800050	INCIDENTAL HOT-MIX ASPHALT SURFACING	TON	21	21								
44000153	HOT-MIX ASPHALT SURFACE REMOVAL, 1"	SQ YD	35912	35912								
44000158	HOT-MIX ASPHALT SURFACE REMOVAL, 2 1/4"	SQ YD	239616	239616								
44000161	HOT-MIX ASPHALT SURFACE REMOVAL, 3"	SQ YD	15681	15681								
44000198	HOT-MIX ASPHALT SURFACE REMOVAL, VARIABLE DEPTH	SQ YD	1286	1286								
44004250	PAVED SHOULDER REMOVAL	SQ YD	2341	2341								
44201031	CLASS B PATCHES, TYPE II, 15 INCH	SQ YD	77.1	77.1								
44201035	CLASS B PATCHES, TYPE III, 15 INCH	SQ YD	330	330								
44201037	CLASS B PATCHES, TYPE IV, 15 INCH	SQ YD	350.1	350.1								
44201903	CLASS D PATCHES, TYPE III, 21 INCH	SQ YD	40	40								
44213100	PAVEMENT FABRIC	SQ YD	680.1	680.1								
44213200	SAW CUTS	FOOT	2294	2294								
45200300	JOINT OR CRACK FILLING	POUND	192		36	156						

Rev. 8-31-09

\*60-(7,8,9,10)RS, 60-(8,9,10)BR

FILE NAME =	USER NAME = conoverpj	DESIGNED -	REVISED -	<b>STATE OF ILLINOIS DEPARTMENT OF TRANSPORTATION</b>	<b>SUMMARY OF QUANTITIES</b>	F.A.I. RTE. 70	SECTION •	COUNTY MADISON	TOTAL SHEETS 150	SHEET NO. 3
ca:\pwwork\pwwork\CONOVERPJ\dms71073\d76a73-sh-t-plan.dgn		DRAWN -	REVISED -			CONTRACT NO. 76A73		FED. ROAD DIST. NO. - ILLINOIS FED. AID PROJECT		
	PLOT SCALE = 58,0000' / IN.	CHECKED -	REVISED -		SCALE: _____	SHEET NO. 1 OF 6 SHEETS		STA. _____ TO STA. _____		
	PLOT DATE = 6/25/2009	DATE -	REVISED -							