

SUMMARY OF QUANTITIES

SUMMARY OF QUANTITIES			URBAN 90/10 FED/ST TOTAL	CONSTRUCTION TYPE CODE								
CODE NO	ITEM	UNIT	QUANTITIES	MAINLINE ROADWAY 1000	TR 162 E 060-0172 SFTY-2A	IL 159 060-0269 SFTY-2A	I-55/70 060-0018/19 SFTY-2A	US 40 060-0267 SFTY-2A	I-70 WB 060-0022 SFTY-2A	I-270 EB/WB 060-0057/58 SFTY-2A	SIGNS Y002-1C	ITS Y032-1F
48101200	AGGREGATE SHOULDERS, TYPE B	TON	2361	2361								
48203029	HOT-MIX ASPHALT SHOULDERS, 8"	SQ YD	2075	2075								
48203100	HOT-MIX ASPHALT SHOULDERS	TON	17909	17909								
50104650	SLOPE WALL REMOVAL	SQ YD	2				2					
50105225	PIPE CULVERT REMOVAL (SPECIAL)	FOOT	50	50								
50200100	STRUCTURE EXCAVATION	CU YD	3					3				
50500405	FURNISHING AND ERECTING STRUCTURAL STEEL	POUND	3260		3260							
50500715	JACK AND REMOVE EXISTING BEARINGS	EACH	16		16							
51100100	SLOPE WALL 4 INCH	SQ YD	2				2					
52000340	NEOPRENE EXPANSION JOINT 4"	FOOT	178						178			
52100010	ELASTOMERIC BEARING ASSEMBLY, TYPE I	EACH	16		16							
52100520	ANCHOR BOLTS, 1"	EACH	72		40					32		
54213669	PRECAST REINFORCED CONCRETE FLARED END SECTIONS 24"	EACH	1	1								
54247130	GRATING FOR CONCRETE FLARED END SECTION 24"	EACH	1	1								
54248510	CONCRETE COLLAR	CU YD	1					1				
58700300	CONCRETE SEALER	SQ FT	72692		6448	31976	14652	19616				
59200101	BRIDGE WASHING NO. 1	EACH	1		1							
59200102	BRIDGE WASHING NO. 2	EACH	1			1						
59200103	BRIDGE WASHING NO. 3	EACH	1				1					
59200104	BRIDGE WASHING NO. 4	EACH	1				1					
59200105	BRIDGE WASHING NO. 5	EACH	1					1				
59200106	BRIDGE WASHING NO. 6	EACH	1						1			
59200107	BRIDGE WASHING NO. 7	EACH	1							1		
59200108	BRIDGE WASHING NO. 8	EACH	1							1		
59300100	CONTROLLED LOW-STRENGTH MATERIAL	CU YD	10				6	4				
60100060	CONCRETE HEADWALL FOR PIPE DRAINS	EACH	384	384								
60100074	SHOULDER REMOVAL AND REPLACEMENT 8"	FOOT	36330	36330								
60107600	PIPE UNDERDRAINS 4"	FOOT	191580	191580								
60108100	PIPE UNDERDRAINS 4" (SPECIAL)	FOOT	7660	7660								
60260100	INLETS TO BE ADJUSTED	EACH	2	2								
* 63000001	STEEL PLATE BEAM GUARD RAIL, TYPE A, 6 FOOT POSTS	FOOT	23237.5	23237.5								
* 63100045	TRAFFIC BARRIER TERMINAL, TYPE 2	EACH	24	24								
* 63100070	TRAFFIC BARRIER TERMINAL, TYPE 5	EACH	3	3								

* SPECIALTY ITEM

*60-(7,8,9,10)RS, 60-(8,9,10)BR

FILE NAME =	USER NAME = conoverpj	DESIGNED -	REVISED -	STATE OF ILLINOIS DEPARTMENT OF TRANSPORTATION	SUMMARY OF QUANTITIES	F.A.I. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
ca:\pwwork\PIWIDOT\CONOVERPJ\dms71073.dwg	76e73-sht-plan.dgn	DRAWN -	REVISED -			70	.	MADISON	150	4
	PLOT SCALE = 50.0000' / IN.	CHECKED -	REVISED -							
	PLOT DATE = 6/25/2009	DATE -	REVISED -			SCALE: _____	SHEET NO. 2 OF 6 SHEETS	STA. _____	TO STA. _____	FED. ROAD DIST. NO. [ILLINOIS] FED. AID PROJECT
								CONTRACT NO. 76A73		