

SUMMARY OF QUANTITIES

SUMMARY OF QUANTITIES			URBAN 90/10 FED/ST TOTAL QUANTITIES	CONSTRUCTION TYPE CODE								
CODE NO	ITEM	UNIT		MAINLINE ROADWAY 1000	TR 162 E 060-0172 SFTY-2A	IL 159 060-0269 SFTY-2A	I-55/70 060-0018/19 SFTY-2A	US 40 060-0267 SFTY-2A	I-70 WB 060-0022 SFTY-2A	I-270 EB/WB 060-0057/58 SFTY-2A	SIGNS Y002-1C	ITS Y032-1F
81018400	CONDUIT PUSHED, 1 1/2" DIA., GALVANIZED STEEL	FOOT	385									385
81400700	HANDHOLE, PORTLAND CEMENT CONCRETE	EACH	14									14
81400720	DOUBLE HANDHOLE, PORTLAND CEMENT CONCRETE	EACH	11									11
81702130	ELECTRIC CABLE IN CONDUIT, 600V (XLP-TYPE USE) 1/C NO. 6	FOOT	1344									1344
81900200	TRENCH AND BACKFILL FOR ELECTRICAL WORK	FOOT	2800									2800
83012400	LIGHT POLE, ALUMINUM, 45 FT. M.H., TENON MOUNT	EACH	3									3
83600200	LIGHT POLE FOUNDATION, 24" DIAMETER	FOOT	146									146
84200500	REMOVAL OF EXISTING LIGHTING UNIT, SALVAGE	EACH	14								14	
86300305	CONTROLLER CABINET TYPE III, SPECIAL	EACH	11									11
87000105	ELECTRIC CABLE ASSEMBLY IN CONDUIT, 600V (EPR-TYPE TC) 2/C NO. 10 AND NO. 10 GROUND	FOOT	330									330
87301715	ELECTRIC CABLE IN CONDUIT, COMMUNICATION NO. 18 6 PAIR	FOOT	240									240
87800210	CONCRETE FOUNDATION, TYPE D (SPECIAL)	FOOT	44									44
X0321743	SILICONE JOINT SEALER, 1"	FOOT	228			228						
X0322729	MATERIAL TRANSFER DEVICE	TON	62013	62013								
X0322935	PIPE CULVERTS TO BE CLEANED	EACH	1	1								
X0323077	SILICONE JOINT SEALER, 2 3/4"	FOOT	212							212		
X0323150	JUNCTION BOX, ALUMINUM, ATTACHED TO STRUCTURE, 18" X 18" X 10"	EACH	11									11
X0324632	SILICONE JOINT SEALER (SPECIAL)	FOOT	46					46				
X0325476	RADAR VEHICLE DETECTION SYSTEM	EACH	11									11
X0326091	LIGHT POLE, STEEL 50 FT. WITH CAMERA LOWERING SYSTEM	EACH	8									8
X0349800	CONCRETE HEADWALL FOR PIPE UNDERDRAIN REMOVAL	EACH	384	384								
X4066580	POLYMERIZED HOT-MIX ASPHALT SURFACE COURSE, STONE MATRIX ASPHALT, N80	TON	32994	32994								
X4400220	CURB REMOVAL AND REPLACEMENT	FOOT	1545	1545								
X7330105	OVERHEAD SIGN STRUCTURE WALKWAY, TYPE A	FOOT	30								30	
X8100065	CONDUIT IN TRENCH, 4" DIA., PVC TYPE C	FOOT	330									330
Z0005300	BOX CULVERTS TO BE CLEANED	EACH	1	1								
Z0017202	DOWEL BARS 1 1/2"	EACH	623	623								
Z0029999	IMPACT ATTENUATOR REMOVAL	EACH	4	4								

△ NON-PART (100% STATE)

* SPECIALTY ITEM

Rev.

*60-(7,8,9,10)RS, 60-(8,9,10)BR

FILE NAME =	USER NAME = conoverp.j	DESIGNED -	REVISED -	STATE OF ILLINOIS DEPARTMENT OF TRANSPORTATION	SUMMARY OF QUANTITIES	F.A.I. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.	
es:\pwwork\PIWIDOT\CONOVERPJ\dms71073\d876e73-shd-plan.dgn	76e73-shd-plan.dgn	DRAWN -	REVISED -			70	.	MADISON	150	7	
PLOT SCALE = 50,0000' / IN.		CHECKED -	REVISED -								
PLOT DATE = 6/25/2009		DATE -	REVISED -								
						SCALE: _____		SHEET NO. 5 OF 6 SHEETS		STA. _____ TO STA. _____	
						FED. ROAD DIST. NO. - ILLINOIS FED. AID PROJECT					
						CONTRACT NO. 76A73					