

SCHEDULE OF QUANTITIES

SCHEDULE OF QUANTITIES			CONSTRUCTION TYPE CODE											
CODE NO	ITEM	UNIT	TOTAL QUANTITIES	MP12.7	MP13.4	MP13.9	MP14.6	MP15.3	MP15.9	MP17.0	MP17.6	MP18.6	MP19.1	MP19.7
80300100	LOCATING UNDERGROUND CABLE	FOOT	2460	20	575	20	565	20	20	785	20	20	395	20
80500100	SERVICE INSTALLATION, TYPE A	EACH	11	1	1	1	1	1	1	1	1	1	1	1
81012500	CONDUIT IN TRENCH, 1 1/2" DIA., PVC	FOOT	2670	265	285	60	545	75	65	765	75	55	405	75
81012800	CONDUIT IN TRENCH, 3" DIA., PVC	FOOT	130	10	30	10	10	10	10	10	10	10	10	10
81018400	CONDUIT PUSHED, 1 1/2" DIA., GALVANIZED STEEL	FOOT	385		50		160			75			100	
81100800	CONDUIT ATTACHED TO STRUCTURE, 3" DIA., GALVANIZED STEEL	FOOT	20		20									
81400700	HANDHOLE, PORTLAND CEMENT CONCRETE	EACH	14		2		4			4			4	
81400720	DOUBLE HANDHOLE, PORTLAND CEMENT CONCRETE	EACH	11	1	1	1	1	1	1	1	1	1	1	1
81702130	ELECTRIC CABLE IN CONDUIT, 600V (XLP-TYPE USE) 1/C NO. 6	FOOT	1344	1120	1452	300	2984	360	320	3524	360	280	2384	360
81900200	TRENCH AND BACKFILL FOR ELECTRICAL WORK	FOOT	2800	275	315	70	555	85	75	775	85	65	415	85
83012400	LIGHT POLE, ALUMINUM, 45 FT. M.H., TENON MOUNT	EACH	3			1		1				1		
83600200	LIGHT POLE FOUNDATION, 24" DIAMETER	FOOT	146	15	11	11	15	15	13	15	15	12	12	12
86300305	CONTROLLER CABINET TYPE III, SPECIAL	EACH	11	1	1	1	1	1	1	1	1	1	1	1
87000105	ELECTRIC CABLE ASSEMBLY IN CONDUIT, 600V (EPR-TYPE TC) 2/C NO. 10 AND NO. 10 GROUND	FOOT	330	30	30	30	30	30	30	30	30	30	30	30
87301715	ELECTRIC CABLE IN CONDUIT, COMMUNICATION NO. 18 6 PAIR	FOOT	240	30	30		30		30	30	30		30	30
87800210	CONCRETE FOUNDATION, TYPE D (SPECIAL)	FOOT	44	4	4	4	4	4	4	4	4	4	4	4
X0323150	JUNCTION BOX, ALUMINUM, ATTACHED TO STRUCTURE, 18" X 18" X 10"	EACH	11	1	1	1	1	1	1	1	1	1	1	1
X0325476	RADAR VEHICLE DETECTION SYSTEM	EACH	11	1	1	1	1	1	1	1	1	1	1	1
X0326091	LIGHT POLE, STEEL 50 FT. WITH CAMERA LOWERING SYSTEM	EACH	8	1	1		1		1	1	1		1	1
X8100065	CONDUIT IN TRENCH, 4" DIA., PVC TYPE C	FOOT	330	30	30	30	30	30	30	30	30	30	30	30
XXXXXXXX1	CELLULAR MODEM	EACH	11	1	1	1	1	1	1	1	1	1	1	1

* 60-(7,8,9,10)RS, 60-(8,9,10)BR

FILE NAME =	USER NAME = prestonme	DESIGNED -	REVISED -	STATE OF ILLINOIS DEPARTMENT OF TRANSPORTATION	ITS SCHEDULE OF QUANTITIES	F.A.I. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
es:\pw\work\PWIDOT\PRESTONME\dms71073\d76e73-shr-ITS.dgn		DRAWN -	REVISED -			-70-		MADISON	150	132
PLOT SCALE = 5/8"=1'-0" / IN.		CHECKED -	REVISED -							
PLOT DATE = 7/9/2009		DATE -	REVISED -							
						SCALE: _____ SHEET NO. ___ OF ___ SHEETS		STA. _____ TO STA. _____		FED. ROAD DIST. NO. _____ ILLINOIS FED. AID PROJECT
										CONTRACT NO. 76A73