

		100% STATE FUNDING								
SP	CODE NO.	ITEM	UNIT	URBAN		ROADWAY J000-2A	HIGHWAY LIGHTING Y030-1E	PEDESTRIAN BRIDGE STR NO 082-0394 X932-2A	RETAINING WALL STR NO 082-W228 Y007	RETAINING WALL STR NO 082-W229 Y007
				TOTAL QUANTITY						
	20100110	TREE REMOVAL (6 TO 15 UNITS DIAMETER)	UNIT	72		72				
	20200100	EARTH EXCAVATION	CU YD	82		82				
	20201200	REMOVAL AND DISPOSAL OF UNSUITABLE MATERIAL	CU YD	100		100				
	20400800	FURNISHED EXCAVATION	CU YD	695		695				
	20700220	POROUS GRANULAR EMBANKMENT	CU YD	100		100				
	20800150	TRENCH BACKFILL	CU YD	58		58				
*	21101615	TOPSOIL FURNISH AND PLACE, 4"	SQ YD	6,067		6,067				
*	25000210	SEEDING, CLASS 2A	ACRE	1.2		1.2				
*	25000400	NITROGEN FERTILIZER NUTRIENT	POUND	108		108				
*	25000500	PHOSPHORUS FERTILIZER NUTRIENT	POUND	108		108				
*	25000600	POTASSIUM FERTILIZER NUTRIENT	POUND	108		108				
*	25100115	MULCH, METHOD 2	ACRE	1.2		1.2				
	25100630	EROSION CONTROL BLANKET	SQ YD	607		607				
	28000250	TEMPORARY EROSION CONTROL SEEDING	POUND	324		324				
	28000400	PERIMETER EROSION BARRIER	FOOT	2,437		2,437				
	28000500	INLET AND PIPE PROTECTION	EACH	23		23				
	28100107	STONE RIPRAP, CLASS A4	SQ YD	214		214				
	28200200	FILTER FABRIC	SQ YD	214		214				
	31100200	SUB-BASE GRANULAR MATERIAL, TYPE A	CU YD	6		6				
	31100300	SUB-BASE GRANULAR MATERIAL, TYPE A 4"	SQ YD	233		233				
	31100700	SUB-BASE GRANULAR MATERIAL, TYPE A 8"	SQ YD	481		481				
	31200600	STABILIZED SUBBASE - CEMENT AGGREGATE MIXTURE, 4"	SQ YD	430		430				
	35300400	PORTLAND CEMENT CONCRETE BASE COURSE 9"	SQ YD	191		191				
	40201000	AGGREGATE FOR TEMPORARY ACCESS	TON	200		200				
	40603080	HOT-MIX ASPHALT BINDER COURSE, IL-19.0, N50	TON	31		31				
	40603085	HOT-MIX ASPHALT BINDER COURSE, IL-19.0, N70	TON	51		51				
	40603310	HOT-MIX ASPHALT SURFACE COURSE, MIX "C", N50	TON	32		32				
	40603340	HOT-MIX ASPHALT SURFACE COURSE, MIX "D", N70	TON	33		33				
	42001300	PROTECTIVE COAT	SQ YD	934		934				
	42400200	PORTLAND CEMENT CONCRETE SIDEWALK 5 INCH	SQ FT	7,411		7,411				
	42400800	DETECTABLE WARNINGS	SQ FT	16		16				
	44000100	PAVEMENT REMOVAL	SQ YD	227		227				
	44000200	DRIVEWAY PAVEMENT REMOVAL	SQ YD	20		20				
	44000500	COMBINATION CURB AND GUTTER REMOVAL	FOOT	238		238				
	44000600	SIDEWALK REMOVAL	SQ FT	5,314		5,314				
	44001980	CONCRETE BARRIER REMOVAL	FOOT	104		104				
	44004250	PAVED SHOULDER REMOVAL	SQ YD	447		447				
	48300500	PORTLAND CEMENT CONCRETE SHOULDERS 10"	SQ YD	430		430				
	50200100	STRUCTURE EXCAVATION	CU YD	1,310				360	265	685
	50300225	CONCRETE STRUCTURES	CU YD	501				501		
	50300255	CONCRETE SUPERSTRUCTURE	CU YD	240					118	122

* SPECIALTY ITEM

FILE NAME = DBTRI-76C47-sht-summary-01.dgn	USER NAME = millerda	DESIGNED - DJM	REVISED -							F.A.I. RTE. 64	SECTION 82-1-1HBR	COUNTY ST. CLAIR	TOTAL SHEETS 93	SHEET NO. 5
	PLOT SCALE = 47.2222' / IN.	CHECKED - JL	REVISED -											
	PLOT DATE = 6/16/2009	DATE - 05/01/09	REVISED -							SCALE: NONE	SHEET NO. 1 OF 4 SHEETS	STA. TO STA.		CONTRACT NO. 76C47
											FED. ROAD DIST. NO. ILLINOIS FED. AID PROJECT			